

PROJECT NO.	SHEET NO.	TOTAL NO.
2019CPT.13.03.10571, 2019CPT.13.03.20571	9	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1220000000-E	1245000000-E	1260000000-E	1297000000-E	1308000000-E	1330000000-E	1519000000-E	1523000000-E	1575000000-E	1704000000-E	1803500000-E	1820000000-E	1838000000-E	1838500000-N	1891000000-E	2605000000-N														
												INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	MILLING ASPHALT PAVEMENT, 1-1/2" DEPTH	MILLING ASPHALT PAVEMENT, 0" TO 1-1/2" DEPTH	INCIDENTAL MILLING	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, DOUBLE SEAL	ASPHALT SURFACE TREATMENT, FOG SEAL	EMULSION FOR ASPHALT SURFACE TREATMENT	VACUUM TRUCK	LATEX MODIFIED MICRO-SURFACING, TYPE III	CONCRETE CURB RAMP														
												MI	FT	TON	SMI	TON	SY	SY	SY	TON	TON	TON	TON	SY	SY	GAL	WK	SY	EA												
2019CPT.13.03.10571	Madison	1	US 25-70	FROM NC 208 TO BEG PASSING LANE AT TOP OF THE MTN (MP 15.92 TO MP 17.85)	1	2	2WU	NO	NO	1.93	26	97	3.86	502	340	2,400	1,800		2,733	164	500																				
2019CPT.13.03.10571	Madison	2	NC 209	FROM PVMNT JOINT NORTH OF SR 1175 TO PVMNT JOINT AT SPRING CREEK UNITED METHODIST CHURCH (MP 13.91 TO MP 8.63)	1	2	2WU	NO	NO	5.28	20	264	10.56	1,373	89		600		5,760	346	900																				
2019CPT.13.03.10571	Madison	3	US 25/70	FROM THE END OF MAP 1 TO THE R/R TRACKS IN HOT SPRINGS (MP 17.85 TO MP 20.86)	1,2,6	136	2WU	NO	NO	3.01	34	151	6.02	783	1,560	4,150	712		5,568	334	300							7													
TOTAL FOR PROJ NO. 2019CPT.13.03.10571												10.22		512	20.44	2,658	1,989	6,550	3,112		14,061	844	1,700																		7
2019CPT.13.03.20571	Madison	4	SR 1502	FROM SR 1503 TO SR 1501 (MP 0.01 TO MP 3.62)	3	2	2WD	NO	NO	3.61	22	181	7.22	939				4,330		260	650																				
2019CPT.13.03.20571	Madison	5	SR 1531	FROM SR 1530 TO SR 1530 (MP 0.00 TO MP 4.25)	4	2	2WU	NO	NO	4.25	18						1,355				900	44,880	44,880	24,684	*																
2019CPT.13.03.20571	Madison	6	SR 1001	FROM BRIDGE #328 TO SR 1118 (MP 8.37 TO MP 5.94)	5	2	2WU	NO	NO	2.43	20										400						28,512														
2019CPT.13.03.20571	Madison	7	SR 1390	FROM NC 213 TO JOINT AT BRIDGE #59 (MP 1.47 TO MP 0.07)	3	2	2WU	NO	NO	1.4	20	70	2.80	364				1,527		92	400																				
2019CPT.13.03.20571	Madison	8	SR 1501	FROM SR 1502 TO EOM (MP 0.01 TO MP 0.58)	3	2	2WU	NO	NO	0.57	21	28	1.14	148				653		39	175																				
2019CPT.13.03.20571	Madison	9	SR 1503	FROM US 23 TO SR 1502 (MP 0.01 TO MP 0.24)	3	2	2WU	NO	NO	0.23	20	12	0.46	60	219		533	251		15	125																				
2019CPT.13.03.20571	Madison	10	SR 1549	FROM SR 1631 TO NC 213 (MP 0.06 TO MP 1.41)	3	2	2WU	NO	NO	1.35	22	68	2.70	351				1,619		97	350																				
2019CPT.13.03.20571	Madison	11	SR 1347	FROM US 23 TO EOP (MP 0.00 TO MP 2.15)	4	2	2WU	NO	NO	2.15	19										550	23,965	23,965	13,181	*																
2019CPT.13.03.20571	Madison	12	SR 1314	FROM SR 1316 TO NC 212 (MP 0.01 TO MP 3.43)	5	2	2WU	NO	NO	3.42	19										125						38,122														
2019CPT.13.03.20571	Madison	13	SR 1393	FROM US 25/70 TO SR 1198 (MP 0.76 TO MP 0.01)	4	2	2WU	NO	NO	0.75	18										150	7,920	7,920	4,356	*																
2019CPT.13.03.20571	Madison	14	SR 1530	FROM SR 1527 TO YANCEY COUNTY LINE (MP 5.37-MP 7.13)	3	2	2WU	NO	NO	1.76	19	88	3.52	458				1,825		109	700																				
2019CPT.13.03.20571	Madison	15	SR 1399	FROM SR 1395 TO SR 1388 (MP 0.01 TO MP 1.31)	4	2	2WU	NO	NO	1.3	18										60	13,728	13,728	7,551																	
2019CPT.13.03.20571	Madison	16	SR 1569	FROM SR 1570 TO SR 1574 (MP 1.4 TO MP 2.17P)	4	2	2WU	NO	NO	0.77	17										100	7,679	7,679	4,224																	
2019CPT.13.03.20571	Madison	17	SR 1119	FROM SR 1118 TO SR 1116 (MP 0.00 TO MP 1.05)	4	2	2WU	NO	NO	1.05	18										300	11,088	11,088	6,099																	
2019CPT.13.03.20571	Madison	18	SR 1458	FROM SR 1313 TO EOP (MP 0.00 TO MP 0.68)	4	2	2WU	NO	NO	0.68	17										50	6,782	6,782	3,730																	
2019CPT.13.03.20571	Madison	19	SR 1505	FROM SR 1503 TO EOP (MP 0.00 TO MP 1.94)	4	2	2WU	NO	NO	1.94	18										700	20,486	20,486	11,268																	
2019CPT.13.03.20571	Madison	20	SR 1502	FROM SR 1501 TO EOP (MP 3.62 TO MP 4.92)	3	2	2WU	NO	NO	1.3	21	65	2.60	338				1,489		89	600																				
TOTAL FOR PROJ NO. 2019CPT.13.03.20571												28.96		512	20.44	2,658	219		1,888	11,694	701	6,335	136,528	136,528	75,093	7	66,634														
GRAND TOTAL												39.18		1,024	40.88	5,316	2,208		6,550	5,000	11,694	14,061	1,545	8,035	136,528	136,528	75,093	7	66,634												