ECONOLITE ASC/3-2070 OVERLAP PROGRAMMING DETAIL

(program controller as shown)

1. From Main Menu select 2. CONTROLLER

2. From CONTROLLER Submenu select 2. VEHICLE OVERLAPS

overlap g

| Sele | c† (| ТМС | G V | VEH | + (| DVI | _P | [(| G] | ar | hd | ' | 101 | RM, | ۹L | 1 | | |
|-----------------------------|------|-----|-----|-----|-----|-----|----|-----|----|----|----|----------|-----|-----|----|---|---|---|
| ТMG | | | | | | | | | | | | | | | | | | |
| PF | HAS | ΞS | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6 |
| INCL | UDE | ΞD | • | • | • | • | • | • | • | Х | • | • | • | • | • | • | • | • |
| LAG GRN 0.0 YEL 0.0 RED 0.0 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |

overlap a

Select TMG VEH OVLP [A] and 'PPLT FYA'

| TMG VEH OVLP[A] TYPE:PPLT FYA |
|---|
| PROTECTED LEFT TURN PHASE 1 OPPOSING THROUGH OVERLAP G |
| FLASHING ARROW OUTPUTCH9 ISOLATE |
| DELAY START OF: FYAO.O CLEARANCEO.O ACTION PLAN SF BIT DISABLE |

END PROGRAMMING


Toggle Until Positioned on Overlap G

Toggle Until Positioned on Overlap A

IN ORDER TO INSURE THAT SIGNALS FLASH CONCURRENTLY ON THE SAME APPROACH, MAKE THE FOLLOWING FLASHER CIRCUIT CHANGES:

1. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-4 AND TERMINATE ON T2-2. 2. ON REAR OF PDA - REMOVE WIRE FROM TERM. T2-5 AND TERMINATE ON T2-3. 3. REMOVE FLASHER UNIT 2.

THE CHANGES LISTED ABOVE TIES ALL PHASES AND OVERLAPS TO FLASHER UNIT 1.



www.stantec.com License No. F-0672 750 N.Gr

| PROJECT REFERENCE NO. | SHEET NO. |
|-----------------------|-----------|
| U - 4405 | SIG-15.2 |

FLASHER CIRCUIT MODIFICATION DETAIL

| | THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 06-0274T1 DESIGNED: March 2018 SEALED: 03-29-2018 REVISED: N/A | |
|---|---|--|
| Phase I | | |
| t 2 of 2 | | DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED |
| RICAL AND PROGRAMMING DETAILS FOR: | US 401 (Raeford Road) | SEAL |
| Prepared in the Offices of: Nobility and Not NORTH CARCELLISION | at NC 162 (Bunce Road)/ SR 1411 (Bunce Road) | SEAL |
| Super Contraction | | teville |
| | PLAN DATE:March 2018REVIEWED BY:L OvePREPARED BY:G B SpellREVIEWED BY: | ern FNGINEER |
| Concernation of Management | REVISIONS INIT. | DATE DocuSigned by JULIN 3/29/2018 |
| Greenfield Pkwy,Garner,NC 27529 | | 96363FER84996497E DATE SIG. INVENTORY NO. 06-0274TI |