



NOTES:
 1. THE CONTRACTOR SHALL LOCATE THE EXISTING FIBER CABLE RUNNING NORTH ALONG PURDUE DRIVE AND TERMINATING IN 06-0224. THE CONTRACTOR SHALL BACK PULL THIS CABLE FOR TERMINATION IN NEW AERIAL SPICE ENCLOSURE AS SHOWN.

GENERAL NOTE:
 AFTER ALL NEW CABLES ARE INSTALLED AND THE SYSTEM INTERSECTIONS ARE OPERATING, REMOVE THE EXISTING CABLES LABELED "REM". PRIOR TO REMOVING, COORDINATE THESE ACTIVITIES WITH PWC. PWC CONTACT: DARLENE GOODHART AT (910) 223-4526.

1. INSTALL REA, PE - 22, SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE	15. DIRECTIONAL DRILL CONDUIT	30. INSTALL AERIAL SPICE ENCLOSURE	46. INSTALL SIDEWALK GUY ASSEMBLY
2. INSTALL REA, PE - 38, (FIGURE - 8) SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE	16. BORE AND JACK CONDUIT	31. INSTALL POLE MOUNTED CABINET	47. INSTALL MESSENGER CABLE
3. INSTALL 3-CONDUCTOR, CLASS B, STRANDED UNDERGROUND POWER CABLE	17. INSTALL CABLE(S) IN EXISTING CONDUIT	32. INSTALL BASE MOUNTED SPICE CABINET (336) WITH EXTEND BASE	48. REMOVE EXISTING COMMUNICATIONS CABLE AND MESSENGER CABLE
4. INSTALL SMFO CABLE	18. INSTALL CABLE(S) IN NEW CONDUIT	33. REMOVE EXISTING SPICE CABINET	49. REMOVE EXISTING COMMUNICATIONS CABLE
5. INSTALL WEATHERPROOF CATEGORY 5e UTP - 4 PAIR 23 AWG CABLE (PoE)	19. INSTALL CABLE(S) IN EXISTING RISER	34. INSTALL CABINET FOUNDATION	50. INSTALL ETHERNET SWITCH
6. INSTALL FIBER OPTIC DROP CABLE	20. INSTALL CABLE(S) IN NEW RISER	35. REMOVE EXISTING CABINET FOUNDATION	51. INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE
7. INSTALL TRACER WIRE	21. INSTALL CABLE(S) IN EXISTING CONDUIT STUBOUTS	36. INSTALL CCTV CAMERA ASSEMBLY	52. INSTALL DELINEATOR MARKER
8. TRENCH	22. INSTALL NEW CONDUIT INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	37. INSTALL CCTV CAMERA WOOD POLE	53. STORE 50 FEET OF COMMUNICATIONS CABLE
9. INSTALL PVC CONDUIT	23. INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	38. INSTALL CCTV CAMERA METAL POLE AND FOUNDATION	54. LASH CABLE(S) TO EXISTING PWC FIBER OPTIC LINE
10. INSTALL RIGID, GALVANIZED STEEL CONDUIT	24. INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET	39. INSTALL JUNCTION BOX	55. LASH CABLE(S) TO EXISTING MESSENGER CABLE
11. INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD	25. INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET	40. INSTALL OVERSIZED JUNCTION BOX	56. LASH CABLE(S) TO NEW MESSENGER CABLE
12A. INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL	26. TERMINATE COMMUNICATIONS CABLE ON EXISTING TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET	41. REMOVE EXISTING JUNCTION BOX	57. MODIFY EXISTING ELECTRICAL SERVICE
12B. INSTALL CABLES/DROP CABLE THROUGH NIPPLE ON METAL POLE (SIGNAL OR JOINT USE). INSTALL HEAT SHRINK TUBING OVER NIPPLE.	27. INSTALL NEW TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET	42. INSTALL WOOD POLE	58. INSTALL NEW ELECTRICAL SERVICE FOR DMS/CCTV
13. INSTALL OUTER-DUCT POLYETHYLENE CONDUIT	28. INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPICE CABLE IN CABINET	43. REMOVE EXISTING WOOD POLE	59. INSTALL NEW BASE MOUNTED CABINET (336)
14. INSTALL POLYETHYLENE CONDUIT	29. INSTALL UNDERGROUND SPICE ENCLOSURE	44. INSTALL AERIAL GUY ASSEMBLY	60. SEAL ALL CONDUIT ENTERING JUNCTION BOXES AND SIGNAL/CCTV/DMS CONTROL CABINETS WITH MOLDABLE DUCT SEAL
		45. INSTALL STANDARD GUY ASSEMBLY	

Stantec Consulting Services Inc.
 801 Jones Franklin Road
 Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672

PHASE III FIBER TRUNK CABLE INSTALLATION

Prepared for the Offices of:

 750 N. Greenfield Plaza, Garner, NC 27529

US 401 BUSINESS (RAEFORD ROAD) SIGNAL SYSTEM AND COMMUNICATIONS CABLE / CONDUIT ROUTING PLANS

DIVISION 06 CUMBERLAND CO. FAYETTEVILLE

PLAN DATE: MARCH 2018 REVIEWED BY: D. HARRIS

PREPARED BY: J. INGRAM REVIEWED BY: B. WATSON

SEAL

Lawrence E. Overton
 ENGINEER
 SEAL 045933
 DATE 3/29/2018

SCALE: NTS

REVISIONS	INIT.	DATE

3/27/2018 U:*171001766*tr\transportation\des\ign*ITS U-4405*SCP Cable Routing.dgn F:\les*260_90_U-4405_SCP_18_180329.dgn j.ingram