

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS SECTION SUMMARY SHEET

Note: Embankment does not include backfill for undercut.

Station	Uncl. Exc. (LT) (cu. yd.)	Undercut (LT) (cu. yd.)	Embt (LT) (cu. yd.)	Uncl. Exc. (CL) (cu. yd.)	Undercut (CL) (cu. yd.)	Embt (CL) (cu. yd.)	Uncl. Exc. (RT) (cu. yd.)	Undercut (RT) (cu. yd.)	Embt (RT) (cu. yd.)
68+50.00			18	1		67	1		103
69+00.00	1		12	1		69	2		62
69+50.00	3		5	1		79	2		43
70+00.00	12		1	1		92	2		67
70+50.00	24			1		101	3		68
71+00.00	21					106	4		65
71+50.00	8		2			106	4		65
72+00.00	5		3			96	2		57
72+50.00	4		3			74	1		45
73+00.00	4		6			60	6		45
73+50.00	5		33			57	11		53
74+00.00	4		58			55	10		36
74+50.00	3		58			55	7		14
75+00.00	3		60			60	4		14
75+50.00	2		62			75	7		13
76+00.00	1		32			42	5		6
76+50.00							2		7
77+00.00									
77+50.00			85				1		14
78+00.00			223				1		44
78+50.00			298						54
79+00.00	1		320				1		43
79+50.00	12		357				44		23
80+00.00	12		526				44		19
80+50.00			778			11	1		37
81+00.00			1,022			31			44
81+50.00			1,111			48			46
82+00.00			1,011			61			48
82+50.00			800			72			56
83+00.00			603			88	1		140
83+50.00			510			107	2		208
84+00.00			403			118	1		241
84+50.00			311			114	1		274
85+00.00			246			102	1		280
85+50.00			103	1		78	2		275
86+00.00				3		58	2		217
86+50.00			57	3		56	2		154
87+00.00			99	2		57	1		124
87+50.00			82	1		57			125
88+00.00			72			60			125
88+50.00	1		66			66			120
89+00.00	1		69			70			84
89+50.00	3		64			49			43
90+00.00	7		50			36			60
90+50.00	7		43			38			85
91+00.00	2		41			31			81
91+50.00	1		34			31			80
92+00.00	2		55			36			78
92+50.00	5		75			43			74
93+00.00	9		52			38			65
93+50.00	13		26			16			58
94+00.00	17		7						45
94+50.00	24		1				1		20

Station	Uncl. Exc. (LT) (cu. yd.)	Undercut (LT) (cu. yd.)	Embt (LT) (cu. yd.)	Uncl. Exc. (CL) (cu. yd.)	Undercut (CL) (cu. yd.)	Embt (CL) (cu. yd.)	Uncl. Exc. (RT) (cu. yd.)	Undercut (RT) (cu. yd.)	Embt (RT) (cu. yd.)
95+00.00	31						4		4
95+50.00	27		9				6		6
96+00.00	24		9				6		8
96+50.00	27						5		13
97+00.00	22		1				4		20
97+50.00	13		7				4		25
98+00.00	7		8				3		33
98+50.00	2		2				1		21
99+00.00									2
99+50.00									
100+00.00									
100+50.00	4		5				3		4
101+00.00	25		5				8		3
101+50.00	43		2				13		
102+00.00	50		9				11		5
102+50.00	57		12				5		18
103+00.00	52		18				3		28
103+50.00	42		26				3		31
104+00.00	33		29				3		34
104+50.00	24		26				3		43
105+00.00	17		16				4		60
105+50.00	11		15				5		75
106+00.00	7		20				5		78
106+50.00	7		17				4		69
107+00.00	8		10				3		62
107+50.00	5		17				2		54
108+00.00	1		45				1		65
108+50.00			55						78
109+00.00			55						68
109+50.00			53						60
110+00.00	1		43						51
110+50.00	1		54						43
111+00.00	1		65				1		44
111+50.00	1		57				1		39
112+00.00	1		47				1		41
112+50.00	2		39				1		37
113+00.00	2		32						15
113+50.00	2		30						
114+00.00	4		24						
114+50.00	9		15				3		19
115+00.00	14		8				9		4
115+50.00	18		9				6		8
116+00.00	17		14						15
116+50.00	14		35						23
117+00.00	11		59						34
117+50.00	6		80						38
118+00.00	2		123						34
118+50.00			152				1		27
119+00.00			139				2		22
119+50.00			127				2		18
120+00.00			103				2		13
120+50.00			79				3		7
121+00.00			93				4		3

Note: "Quantities are approximate only. The Resident Engineer will re-cross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid. The Embankment Column does not include backfill for Undercut"

5/28/99

I:\MAY-2018-19599-01\Drawings\Roadway\NCD001\U-4405\Roadway\XSC\U4405_rdy.XSC--summary.dgn
 8:33:36 AM 5/28/99