



TIP NO. U-5725R-3822	SHEET NO. SIGN-1
APPROVED:  6/28/2018	
DATE: 6/28/2018	
SEAL 	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

**STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION**

**SIGNING PLAN  
HALIFAX COUNTY**

**LOCATION: NC-125 FROM I-95 TO OLD FARM ROAD SOUTH, SR 1627 (THREE  
BRIDGES ROAD) FROM NC-125 TO PREMIER BOULEVARD**

**ROADWAY STANDARD DRAWING**

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
903.10	GROUND MOUNTED SIGN SUPPORTS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS
1264.01	OBJECT MARKERS - TYPES
1264.02	OBJECT MARKERS - INSTALLATION

**SUMMARY OF QUANTITIES**

ITEM NO.		ITEM DESCRIPTION	QUANTITY	UNIT
DESC. NO.	SECT. NO.			
4025000000	901	CONTRACTOR FURNISHED, TYPE D SIGN	7	S.F.
4025000000	901	CONTRACTOR FURNISHED, TYPE E SIGN	472	S.F.
4025000000	901	CONTRACTOR FURNISHED, TYPE F SIGN	90	S.F.
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	1395	L.F.
4096000000	904	SIGN ERECTION, TYPE D	1	EA.
4102000000	904	SIGN ERECTION, TYPE E	60	EA.
4108000000	904	SIGN ERECTION, TYPE F	8	EA.
4116100000	904	SIGN ERECTION, RELOCATE TYPE D (GROUND MOUNTED)	10	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	30	EA.
4158000000	907	DISPOSAL OF SIGN SYSTEM, WOOD	3	EA.
4192000000	907	DISPOSAL OF SUPPORT, U-CHANNEL	10	EA.
4915000000	1264	7' U-CHANNEL POSTS	6	EA.
4955000000	1264	OBJECT MARKERS (END OF ROAD)	3	EA.
4957000000	1264	OBJECT MARKERS (TYPE 3)	3	EA.

**GENERAL NOTES**


- SIGNS FURNISHED BY STATE
- IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.
- WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

**INDEX**

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2	D, E AND F SIGNS
SIGN-3 THRU SIGN-18	SIGNING PLAN SHEETS

**PLAN REVIEWED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT**

A.I. ALQUDWAH, P.E.	SIGNING & DELINEATION REGIONAL ENGINEER
D.M. EATON, P.E.	SIGNING & DELINEATION PROJECT DESIGN ENGINEER



**PLAN PREPARED BY: Kimley-Horn and Associates**

MATT WEST, P.E.	PROJECT DESIGN ENGINEER
MITCH MAGEE, E.I.T.	DESIGNER



6/28/2018 \$FILEL\$

CONTRACT: C204149 T.I.P.: U-5725/R-3822