

	• •	
BENT 3 CONTROL LINE	BENT 4 CONTROL LINE	
#4B13E BARS (3 BAR RUNS)	+4B14E BARS (3 BAR RUNS)	
	#4U2E BARS	
	CONTROL LINE #4B13E BARS	CONTROL LINE #4B13E BARS (3 BAR RUNS) (3 BAR RUNS) (3 BAR RUNS)

<u>SPAN C</u>

<u>SPAN D</u>

<u>SPAN E</u>

PLAN OF SIDEWALK DIMENSIONS ARE MEASURED ALONG OUTSIDE FACE OF CONCRETE PARAPET

	NOTES:
11	#4U2E BARS MAY BE PUSHED INTO GREEN CONCRETE AFTER SPAN HAS SCREEDED OFF.
 ♀_) €_JOINT @ END BENT 2	SIDEWALK IN ALL SPANS SHALL NOT BE CAST UNTIL ALL SLAB CONCRETE IN ALL SPANS HAS BEEN CAST AND HAS REACHED A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI.
	GROOVED CONTRACTION JOINTS, $\frac{1}{2}$ " IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE SIDEWALK IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINTS SHALL BE LOCATED AT A SPACING OF 8 FT. TO 10 FT. BETWEEN EXPANSION JOINTS. NO CONTRACTION JOINT WILL BE REQUIRED FOR SEGMENTS LESS THAN 10 FT. IN LENGTH.
	ALL REINFORCING STEEL IN THE SIDEWALK SHALL BE EPOXY COATED.
	SEE ``EXPANSION JOINT SEAL DETAILS FOR SIDEWALK'' SHEETS FOR COVER PLATE DETAILS.
	SEE APPROACH SLAB SHEETS, FOR SIDEWALK ON APPROACH SLAB.
4G2E	CONCRETE AND REINFORCING STEEL FOR THE SIDEWALK IS INCLUDED IN THE SUPERSTRUCTURE BILL OF MATERIALS. PAYMENT FOR THE SIDEWALK SHALL BE INCLUDED IN THE PAY ITEM "REINFORCED CONCRETE DECK SLAB".

#4U2E BARS MAY BE SHIFTED SLIGHTLY TO AVOID EXPANSION JOINTS IN SIDEWALK.

PROJECT NO.	<u>R-3822</u>
HALIFAX	COUNTY
STATION: <u>99+17</u>	<u>.60 -L1-</u>

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH SUPERSTRUCTURE

SIDEWALK DETAILS

REVISIONS					SHEET NO.	
N0.	BY:	DATE:	N0.	BY:	DATE:	S-33
1			3			TOTAL SHEETS
2			4			58



Kimley Worn

421 Fayetteville Street, Suite 600 Raleigh, NC 27601-1772 Phone (919) 677-2000 F-0102