


TIP NO. R-3825B	SHEET NO. SIGN-1A
APPROVED: <i>Ayman Alqudwah</i> F32AC5CAF985472	
DATE: 6/5/2018	
SEAL	
	
<b>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</b>	

## R-3825B FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION
	(FINAL PAVEMENT MARKINGS) THERMOPLASTIC (24", 120 MILS)
T2	WHITE STOPBAR THERMOPLASTIC (4", 90 MILS)
TA	WHITE EDGELINE
TB	YELLOW EDGELINE THERMOPLASTIC (4", 120 MILS)
T8	2 FT. - 6 FT./SP WHITE MINSKIP
T9	2 FT. - 6 FT./SP YELLOW MINSKIP
TC	10 FT. WHITE SKIP
TD	3 FT. - 9 FT./SP WHITE MINSKIP
TE	WHITE SOLD LANE LINE
TI	YELLOW DOUBLE CENTER THERMOPLASTIC (8", 90 MILS)
TP	YELLOW DIAGONAL THERMOPLASTIC (8", 120 MILS)
T13	3 FT. - 9 FT./SP WHITE MINSKIP
TQ	WHITE CROSSWALK LINE
TR	WHITE SOLD LANE LINE
	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)
	UA - LEFT TURN ARROW
	UB - RIGHT TURN ARROW
	UC - STRAIGHT ARROW
	UD - COMBO LEFT/STRAIGHT ARROW
	UE - COMBO RIGHT/STRAIGHT ARROW
	UF - COMBO LEFT/RIGHT ARROW
	UG - COMBO LEFT/RIGHT/STRAIGHT ARROW
	UN - 24" YIELD LINE TRIANGLE
	UI - ALPHANUMERIC CHARACTER
	UP - MERGE ARROW
	UT - U-TURN ARROW
	(MARKERS) PERMANENT RAISED MARKERS
MA	YELLOW & YELLOW
MB	CRYSTAL & RED

SYMBOL	DESCRIPTION
	(FINAL PAVEMENT MARKINGS) THERMOPLASTIC (6", 90 MILS)
T6	WHITE EDGELINE
T7	YELLOW EDGELINE THERMOPLASTIC (6", 120 MILS)
T11	2 FT. - 6 FT./SP WHITE MINSKIP
T12	2 FT. - 6 FT./SP YELLOW MINSKIP
TJ	10 FT. WHITE SKIP
TK	3 FT. - 9 FT./SP WHITE MINSKIP
TL	WHITE SOLD LANE LINE
T16	YELLOW DOUBLE CENTER THERMOPLASTIC (12", 90 MILS)
TS	WHITE GORELINE
TU	WHITE DIAGONAL
TV	YELLOW DIAGONAL THERMOPLASTIC (12", 120 MILS)
TT	WHITE SOLD LANE LINE
T14	3 FT. - 9 FT./SP WHITE MINSKIP COLD APPLIED PLASTIC (6")
C6	WHITE EDGELINE
C7	YELLOW EDGELINE
CJ	10 FT. WHITE SKIP
CK	3 FT. - 9 FT./SP WHITE MINSKIP COLD APPLIED PLASTIC (12")
CS	WHITE GORELINE (MARKERS) SNOWPLOWABLE MARKERS
ME	YELLOW & YELLOW
MF	CRYSTAL & RED

06/05/18  
 P:\TIP\Projects-R\R3825B\Traffic\Signing\CADD\PM Plan\R-3825b\_pmp\_psh\_s01.dgn  
 User:rtward

**PAVEMENT MARKING SCHEDULE**