PROJECT REFERENCE NO.	SHEET NO.
R-3825B	EC-03B
R/W SHEET NO.	

Prepared in the Office of: AECOM
NC FIRM LICENSE No: F-0342
701 Corporate Center Drive, Suite 475
Raleigh, NC 27607
(919) 854-6200 - (919) 854-6259 (FAX)

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
19	-L-	204+50	207+00	LT	565
19	-L-	207+00	208+50	LT	405
19	-L-	208+50	211+00	LT	455
19	-L-	211+00	213+00	LT	540
19	-L-	204+50	214+00	RT	2135
19	-L-	214+00	216+00	RT	450
20	-L-	222+27	228+00	LT	520
21	-L-	233+23	234+50	LT	235
22	-L-	250+40	251+00	LT	100
22	-L-	251+13	252+50	LT	380
22	-L-	252+50	257+50	LT	1020
22	-L-	247+00	248+00	RT	70
22	-L-	254+25	255+50	RT	255
22	-L-	255+50	257+50	RT	540
22	-Y13-	19+50	21+50	LT	460
23	-Y13-	16+50	19+00	LT	460
23	-Y13-	28+15	29+25	LT	205
23	-Y13-	31+00	33+16	LT	350
23	-Y13-	29+00	36+96	RT	1280
		SUBTOTAL THIS SHEET			10,425
		SHEET 3A SUBTOTAL			34,130
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					26,695
				TOTAL	71,520
				SAY	72,000

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	18+00	22+00	RT	1100
6	-L-	40+00	45+50	RT	1855
6	-L-	40+50	47+00	LT	1460
6	-Y4-	11+25	12+00	LT	175
9	-L-	82+10	82+60	RT	85
9	-Y8-	10+50	11+30	LT	75
10	-L-	92+50	93+00	RT	135
10	-L-	98+00	101+00	RT	485
11	-L-	103+00	106+00	RT	420
13	-L-	128+50	129+00	LT	70
13	-L-	128+25	128+57	RT	45
13	-L-	128+60	128+93	RT	50
14	-L-	141+00	142+00	LT	225
16	-L-	173+50	175+00	LT	405
16	-L-	175+00	176+00	LT	225
16	-L-	176+50	178+00	LT	405
16	-L-	177+30	178+00	RT	190
16	-L-	175+50	175+80	RT	85
17	-L-	178+00	184+00	LT	1610
17	-L-	178+00	181+00	RT	615
			SUBTOTAL		9,715
		ADDITIONAL PSRM TO BE INSTALLED			0
				TOTAL	9,715
				SAY	9,750

REVISIONS

DATE/TIME: 9:31:07 AM
DGN: R:\Erosion Control\R3825B_REV-EC-EC03.dgn