PROJECT NO.	SHEET NO.	TOTAL NO.
WBS 50442.3.1	11	
I-5798		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1297000000-E 1½" MILLING	1297000000-E 3" MILLING	1524200000-E SURFACE COURSE, S9.5D	1577000000-E POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1839140000-E ULTRA-THIN BONDED WEARING COURSE	1840000000-E MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	2830000000-N ADJ. OF MANHOLES	2845000000-N ADJ. OF METER OR VALVE BOX	4600000000-N LANE CLOSURE	4600000000-N RAMP/ LOOP CLOSURES	5255000000-N PORTABLE LIGHTING	6000000000-E TEMPORARY SILT FENCE	6009000000-E STONE FOR EROSION CONTROL, CLASS B	6012000000-E SEDIMENT CONTROL STONE	6071010000-E WATTLE	6071020000-E POLYACRYLAMIDE (PAM)	6084000000-E SEED & MULCHING	7444000000-E INDUCTIVE LOOP
										MI	FT	CY	TONS	SMI	SY	SY	TONS	TONS	140	TON	LF	EA	EA	EA	EA	LS	LF	TON	TON	LF	LB	AC	LF
WBS 50442.3.1	Mecklenburg	1	I-485 (OUTER)	ROCKY RIVER RD. TO I-85	1&3	4	MD	YES	NO	5.18	68	20	15	0.20	58,826	108,461	23,162	1,653	260	6,400	52,944			76			350	50	35	75	4	0.10	
TOTAL FOR MAP NO. 1										**5.18**		**20**	**15**	**0.20**	**58,826**	**108,461**	**23,162**	**1,653**	**260**	**6,400**	**52,944**			**76**			**350**	**50**	**35**	**75**	**4**	**0.10**	
WBS 50442.3.1	Mecklenburg	2	I-485 (INNER)	ROCKY RIVER RD. TO I-85	1& 3	3	MD	YES	NO	5.20	60	20	15	0.20	59,816	59,004	14,938	1,166	105	6,042	52,868			42			350	50	35	72	4	0.10	
TOTAL FOR MAP NO. 2										**5.20**		**20**	**15**	**0.20**	**59,816**	**59,004**	**14,938**	**1,166**	**105**	**6,042**	**52,868**			**42**			**350**	**50**	**35**	**72**	**4**	**0.10**	
WBS 50442.3.1	Mecklenburg	3	LOOP	FROM OUTER I-485 TO NC 49	2&3	1		NO	NO	0.186	35	30	10	0.30	3,718		312	18	165				1		3		100	20	10	20	1	0.10	180
TOTAL FOR MAP NO. 3										**0.186**		**30**	**10**	**0.30**	**3,718**		**312**	**18**	**165**				**1**		**3**		**100**	**20**	**10**	**20**	**1**	**0.10**	**180**
WBS 50442.3.1	Mecklenburg	4	RAMP	FROM NC 49 TO OUTER I-485	2&3	1		NO	NO	0.357	34	40	20	0.30	7,114		598	34	125						2		100	20	10	15	1	0.10	
TOTAL FOR MAP NO. 4										**0.357**		**40**	**20**	**0.30**	**7,114**		**598**	**34**	**125**						**2**		**100**	**20**	**10**	**15**	**1**	**0.10**	
WBS 50442.3.1	Mecklenburg	5	RAMP	FROM I-485 TO US 29	2&3	1		NO	NO	0.036	24				512		43	2	80						2					15	1		
TOTAL FOR MAP NO. 5										**0.036**					**512**		**43**	**2**	**80**						**2**					**15**	**1**		
WBS 50442.3.1	Mecklenburg	6	RAMP	FROM US 29 TO OUTER I-485	2&3	2		NO	NO	0.214	36	50	30	0.30	4,512		379	22	115				2		3		190	30	18	16	1	0.10	
TOTAL FOR MAP NO. 6										**0.214**		**50**	**30**	**0.30**	**4,512**		**379**	**22**	**115**				**2**		**3**	*	**190**	**30**	**18**	**16**	**1**	**0.10**	
WBS 50442.3.1	Mecklenburg	7	RAMP	FROM INNER I-485 TO US 29	2&3	2		NO	NO	0.352	46	30	20	0.30	9,547		836	48	45			1			3		100	15	10	15	1	0.20	180
TOTAL FOR MAP NO. 7										**0.352**		**30**	**20**	**0.30**	**9,547**		**836**	**48**	**45**			**1**			**3**		**100**	**15**	**10**	**15**	**1**	**0.20**	**180**
WBS 50442.3.1	Mecklenburg	8	LOOP	FROM US 29 TO INNER I-485	2&3	1		NO	NO	0.189	24				2,667		224	13	170						1					15	1		
TOTAL FOR MAP NO. 8										**0.189**					**2,667**		**224**	**13**	**170**						**1**					**15**	**1**		
WBS 50442.3.1	Mecklenburg	9	RAMP	FROM US 29 EAST TO INNER I-485	2&3	1		NO	NO	0.202	24				2,848		239	14	70						3					15	1		
TOTAL FOR MAP NO. 9										**0.202**					**2,848**		**239**	**14**	**70**						**3**					**15**	**1**		
WBS 50442.3.1	Mecklenburg	10	RAMP	FROM INNER I-485 TO NC 49	2&3	2		NO	NO	0.316	38	30	20	0.20	6,524		760	43	195				1		2		100	15	10	20	2	0.20	210
TOTAL FOR MAP NO. 10										**0.316**		**30**	**20**	**0.20**	**6,524**		**760**	**43**	**195**				**1**		**2**		**100**	**15**	**10**	**20**	**2**	**0.20**	**210**
WBS 50442.3.1	Mecklenburg	11	LOOP	FROM NC 49 TO INNER I-485	2&3	2		NO	NO	0.294	36	40	30	0.20	6,200		521	30	130						2		200	20	20	10	1	0.10	
TOTAL FOR MAP NO. 11										**0.294**		**40**	**30**	**0.20**	**6,200**		**521**	**30**	**130**						**2**		**200**	**20**	**20**	**10**	**1**	**0.10**	
TOTAL FOR PROJ NO. WBS 50442.3.1										**12.526**		**260**	**160**	**2.00**	**162,284**	**167,465**	**42,012**	**3,043**	**1,460**	**12,442**	**105,812**	**1**	**4**	**118**	**21**		**1,490**	**220**	**148**	**288**	**18**	**1.00**	**570**
															329,749									**139**									
GRAND TOTAL										**12.526**		**260**	**160**	**2.00**	**162,284**	**167,465**	**42,012**	**3,043**	**1,460**	**12,442**	**105,812**	**1**	**4**	**118**	**21**	**1.00**	**1,490**	**220**	**148**	**288**	**18**	**1.00**	**570**