PROJECT NO.	SHEET NO.
WBS 50442.3.1	12
I-5798	

THERMOPLASTIC AND PAINT QUANTITIES

										4400000000-E	4423000000-N	4424000000-N	4434000000-N	4510000000-N	4710000000-E	4721000000-E	4725000000-E					4775000000-E		
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	STATIONARY WORK ZONE SIGN	WORK ZONE DIGITAL SPEED LIMIT SIGNS	WORK ZONE PRESENCE LIGHTING	SEQUENTIAL FLASHING WARNING LIGHTS	LAW ENFORCEMENT	24" X 120 M WHITE THERMO	THERMO MSG ONLY 120 M	THERMO RT ARROW 90 M	THERMO MERGE ARROW 90 M	THERMO STR & RT ARROW 90 M	THERMO LT ARROW 90 M	THERMOPLASTIC PAVEMENT MARKINGSYMBOL MERGE ARROW(90 MILS)	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE 2 (6") WHITE	COLD APPLIED PLASTIC PAVEMENT MARKING LINES,TYPE 2 (6") YELLOW	COLD APPLIED PLASTIC PAVEMENT MARKING LINES,TYPE 2 (6") YELLOW
								MI	FT	SF	EA	EA	EA	HR	LF	EA	EA	EA	EA	EA	EA	LF	LF	LF
WBS 50442.3.1	Mecklenburg	1	I-485 (OUTER)	ROCKY RIVER RD. TO I-85	1&3	4	MD	5.18	68	160	3	21	36	110		20	10	6	5			831	475	
	TOTAL FOR MAP NO. 1							**5.18**		**160**	**3**	**21**	**36**	**110**		**20**	**10**	**6**	**5**			**831**	**475**	
WBS 50442.3.1	Mecklenburg	2	I-485 (INNER)	ROCKY RIVER RD. TO I-85	1& 3	3	MD	5.20	60	159	2	7	12	110		12	6	10	6			816		486
	TOTAL FOR MAP NO. 2							**5.20**		**159**	**2**	**7**	**12**	**110**		**12**	**6**	**10**	**6**			**816**		**486**
WBS 50442.3.1	Mecklenburg	3	LOOP	FROM OUTER I-485 TO NC 49	2&3	1		0.186	35					10	30	24	3			6				
	TOTAL FOR MAP NO. 3							**0.186**						**10**	**30**	**24**	**3**			**6**				
WBS 50442.3.1	Mecklenburg	4	RAMP	FROM NC 49 TO OUTER I-485	2&3	1		0.357	34					10			1							
	TOTAL FOR MAP NO. 4							**0.357**						**10**			**1**							
WBS 50442.3.1	Mecklenburg	5	RAMP	FROM I-485 TO US 29	2&3	1		0.036	24					10										
	TOTAL FOR MAP NO. 5							**0.036**						**10**										
WBS 50442.3.1	Mecklenburg	6	RAMP	FROM US 29 TO OUTER I-485	2&3	2		0.214	36					10	24			3			3			
	TOTAL FOR MAP NO. 6							**0.214**						**10**	**24**			**3**			**3**			
WBS 50442.3.1	Mecklenburg	7	RAMP	FROM INNER I-485 TO US 29	2&3	2		0.352	46					10	30		3			6				
	TOTAL FOR MAP NO. 7							**0.352**						**10**	**30**		**3**			**6**				
WBS 50442.3.1	Mecklenburg	8	LOOP	FROM US 29 TO INNER I-485	2&3	1		0.189	24					10										
	TOTAL FOR MAP NO. 8							**0.189**						**10**										
WBS 50442.3.1	Mecklenburg	9	RAMP	FROM US 29 EAST TO INNER I-485	2&3	1		0.202	24					10										
	TOTAL FOR MAP NO. 9							**0.202**						**10**										
WBS 50442.3.1	Mecklenburg	10	RAMP	FROM INNER I-485 TO NC 49	2&3	2		0.316	38					10	148	12	2			4				
	TOTAL FOR MAP NO. 10							**0.316**						**10**	**148**	**12**	**2**			**4**				
WBS 50442.3.1	Mecklenburg	11	LOOP	FROM NC 49 TO INNER I-485	2&3	2		0.294	36					10							4			
	TOTAL FOR MAP NO. 11							**0.294**						**10**							**4**			
TOTAL FOR PROJ NO. WBS 50442.3.1								**12.526**		**319**	**5**	**28**	**48**	**310**	**232**	**68**	**25**	**19**	**11**	**16**	**7**	**1,647**	**475**	**486**
																			78				**2,608**	
GRAND TOTAL								**12.526**		**319**	**5**	**28**	**48**	**310**	**232**	**68**	**25**	**19**	**11**	**16**	**7**	**1,647**	**475**	**486**
																			78				**2,608**	