


### EDI MODEL 2018ECLIP-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)

REMOVE DIODE JUMPERS 1-5, 1-6, 2-5, 2-6, 2-13, 3-8, 4-7, 4-8, 4-14, 5-13, 6-13, 7-14, and 8-14.



REMOVE JUMPERS AS SHOWN

**NOTES:**

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Ensure that jumper SEL9 is removed from the monitor board.

### NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Ensure that Red Enable is active at all times during normal operation. To prevent Red Failures on unused monitor channels, tie unused red monitor inputs 9,10, 11,12,13,14,15 & 16 to load switch AC+ per the cabinet manufacturer's instructions.
3. Enable Simultaneous Gap-Out for all Phases.
4. Program phases 2 and 6 for Startup In Green.
5. Program phases 2 and 4 for 'STARTUP PED CALL'.
6. Program phases 2 and 6 for Yellow Flash.
7. The cabinet and controller are part of the Gilead Road Closed Loop System.

### SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S2P	S3	S4	S4P	S5	S6	S6P	S7	S8	S8P	S9	S10	S11	S12	S13	S14
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OLA	OLB	SPARE	OLC	OLD	SPARE
SIGNAL HEAD NO.	11,12	82	21,22	P21, P22	31	41,42	P41, P42	51	61,62	NU	62	71,72	81,82	NU	NU	NU	NU	NU
RED		128			101			134			107							
YELLOW		129			102			135			108							
GREEN		130			103			136			109							
RED ARROW	125				116			131			122							
YELLOW ARROW	126	126			117			132			123	123						
GREEN ARROW	127	127			118			133			124	124						
Hand icon					113			104										
Walking person icon					115			106										

NU = Not Used

### EQUIPMENT INFORMATION


CONTROLLER.....2070E  
 CABINET.....EXISTING 332 W/ AUX  
 SOFTWARE.....ECONOLITE OASIS  
 CABINET MOUNT.....BASE  
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE  
 LOAD SWITCHES USED.....S1,S2,S2P,S3,S4,S4P,S5,S6,S7,S8  
 PHASES USED.....1,2,2 PED,3,4,4 PED,5,6,7,8  
 OVERLAPS.....NONE

### COUNTDOWN PEDESTRIAN SIGNAL OPERATION

Countdown Ped Signals are required to display timing only during Ped Clearance Interval. Consult Ped Signal Module user's manual for instructions on selecting this feature.

### INPUT FILE POSITION LAYOUT

(front view)



EX. : 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE  
 ST = STOP TIME


### SPECIAL DETECTOR NOTE

Install a video detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

### INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
PED PUSH BUTTONS											
P21,P22	T88-4,6	I12U	67	29	PED 2	2 PED					
P41,P42	T88-5,6	I12L	69	31	PED 4	4 PED					

NOTE: INSTALL DC ISOLATORS IN INPUT FILE SLOT I12.



### PHASE SEQUENCE PROGRAMMING DETAIL

(program controller as shown below)

FROM OASIS LOCAL CONTROLLER MAIN MENU  
 SELECT: 4 PHASE SEQUENCE

PHASE SEQUENCE: PAGE 1	NEXT: PAGES)						
1   1	2	0	0	0	4	0	3
2   5	6	0	0	7	8	0	0
3   0	0	0	0	0	0	0	0
4   0	0	0	0	0	0	0	0

**HNTB** HNTB NORTH CAROLINA, P.C.  
 343 E. Six Forks Road, Suite 200  
 Raleigh, North Carolina 27609  
 NC License No: C-1554  
 (919) 546-8997

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 10-1753 T1  
 DESIGNED: December 2017  
 SEALED: 04-23-2018  
 REVISED: N/A

Electrical Detail - Sheet 1 of 1  
 Signal Upgrade  
 Temporary Design 1

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SR 2136 (Gilead Road) at Reese Boulevard

Division 10 Mecklenburg Co. Huntersville

PLAN DATE: December 2017 REVIEWED BY: A.D. Klinksiek

PREPARED BY: A.H. Thornburg REVIEWED BY: N.R. Simmons

REVISIONS INIT. DATE

Seal: NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 031464 NITASHA R. SIMMONS

DocuSigned by: Natasha R. Simmons 4/23/2018

SIG. INVENTORY NO. 10-1753 T1