

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PAVEMENT REMOVAL SUMMARY

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD ²
-L-	29+64	30+60	RT	220
-L-	33+33	33+97	RT	18
-L-	36+22	37+30	RT	148
-L-	39+06	41+04	RT	447
-L-	47+20	47+86	LT	188
-L-	49+80	51+24	LT	197
-Y-	19+09	19+40	RT	87
-Y-	19+95	21+72	RT	81
-Y-	21+11	22+26	LT	129
-Y-	22+67	22+94	LT	46
-Y-	22+68	22+89	RT	104
-Y-	23+80	24+00	RT	56
-Y-	24+27	24+96	RT	54
-Y-	24+43	24+76	LT	38
-Y3-	12+10	13+10	RT	599
-Y5-	10+14	11+63	RT	298
-Y7-	11+95	12+67	RT	90
-SR-	10+62	12+48	RT	289
-SR-	10+65	11+32	LT	33
-SR-	17+70	18+93	LT	101
-SR-	19+75	20+25	LT	44
-SR2-	10+83	11+49	RT	32
-SR2-	10+83	11+83	LT	259
TOTAL:				3559
SAY:				3560

CHAIN LINK FENCE SUMMARY

SURVEY LINE	STATION	STATION	LENGTH
-W1-	34+02.56	36+14.65	255
-W2-	36+50.65	39+39.95	327
TOTAL:			582
SAY:			585

* W MEASURED FROM "N" AT THE BEGINNING OF THE ANCHOR TO "N" AT THE END OF THE ANCHOR.
 "N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL
 TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.
 FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL.
 W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL.
 G = GATING IMPACT ATTENUATOR TYPE 350
 NG = NON-GATING IMPACT ATTENUATOR TYPE 350

NOTE: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Fine Grading, Clearing and Grubbing and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading."

GUARDRAIL SUMMARY

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOUL. WIDTH	FLARE LENGTH		W*		ANCHORS							IMPACT ATTENUATOR TYPE 350 EA G NG	SINGLE FACED GUARDRAIL	REMOVE EXISTING GUARDRAIL	REMOVE AND STOCKPILE EXISTING GUARDRAIL	REMARKS		
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	APPROACH END	TRAILING END	XI MOD	B-77	GREU TL-3	M-350	TYPE III	CAT-1	VI MOD						BIC	AT-1
-L-	35+30.00	35+92.59	LT	62.50																								GUARDRAIL AT RETAINING WALL
-L-	37+66.00	39+28.50	LT	162.50																								GUARDRAIL AT RETAINING WALL
-L-	47+26.80	47+95.55	LT	68.75			47+50.00		2.0 - 3.0	4.0	50.0'		1.0'															
-L-	52+00.00	55+68.73	RT	368.75			53+00.00		15.5 - 16.5	17.5	50.0'		1.0'															324
-L-	55+82.33	57+65.00	LT	131.25			56+65.00		15.5 - 16.5	17.5	50.0'		1.0'															
-SR-	12+76.10	12+89.12																										28
ADDITIONAL POSTS:				10.00																								
TOTAL:				793.75																								
TOTAL ANCHOR LENGTH:				168.75																								
TOTAL GUARDRAIL LENGTH:				625.00																								
SAY:				625.00 LF																								

5:\16\2016\proj\sh01\sh01\U-5114-rdy-psh03B-2.dgn