


CONFIDENTIAL AND PROPRIETARY PROPERTY OF
EBDG - NC, PLLC
 MAY NOT BE USED FOR CONSTRUCTION OR PROVIDED TO
 ANY THIRD PARTIES WITHOUT PRIOR WRITTEN CONSENT.
 © 2018 ELLIOTT BAY DESIGN GROUP.


WINDOW LIST								
NO.	QTY.	DECK	SPACE	FR / A-B	NOMINAL SIZE (W x H)	THICKNESS (in)	FIRE	REMARKS
1-W1	2	HOLD	EOS	2/B	36 x 35	TBD	A60	WIRE-INSERTED GLASS; GN 6
1-W2	2	HOLD	EOS	5/B	45 x 35	TBD	A60	WIRE-INSERTED GLASS; GN 6
2-W1	3	MAIN	PASSENGER LOUNGE	17/A,18/B	33 x 48	1/4	-	-
2-W2	8	MAIN	PASSENGER LOUNGE	14/A-14/B	81 x 48	1/4	-	-
3-W1	2	01	CREW LOUNGE	4/A,6/A	36 x 36	1/4	-	-
3-W2	1	01	CREW LOUNGE	1/B	24 x 36	1/4	-	-
3-W3	1	01	CREW HEAD	6/B	24 x 36	1/4	-	HORIZONTAL SPLIT, TOP OPEN; PRIVACY GLASS OR SUITABLE TINTED; GN 5
4-W1	2	BRIDGE	PILOT HOUSE	6/A,6/B	82 x 40	1/4	-	CUSTOM SHAPE
4-W2	4	BRIDGE	PILOT HOUSE	5/A,5/B	48 x 40	1/4	-	CUSTOM SHAPE, SLIDING OPENABLE
4-W3	4	BRIDGE	PILOT HOUSE	3/A,3/B	27 x 40	1/4	-	CUSTOM SHAPE
4-W4	2	BRIDGE	PILOT HOUSE	2/A,2/B	30 x 40	1/4	-	CUSTOM SHAPE

REVISION HISTORY					
REV	ZONE	DESCRIPTION	DWN	DATE	APVD

GENERAL NOTES
1. VESSEL TO BE CONSTRUCTED IN ACCORDANCE WITH 46 CFR SUBCHAPTER H REGULATIONS.
2. FRAME SPACING IS 24" UNLESS NOTED OTHERWISE.
3. ALL GLASS SHALL BE TEMPERED.
4. WINDOWS IN PASSENGER SPACES SHALL HAVE A FINISHED INTERIOR SILL HEIGHT GREATER THAN THE HEIGHT OF THE PASSENGER SEAT BACKS.
5. WINDOW SHALL BE SPLIT HORIZONTALLY AND THE TOP HALF SHALL OPEN. WINDOW SHALL BE PRIVACY GLASS OR SUITABLY TINTED.
6. EOS WINDOWS SHALL HAVE A MINIMUM STC RATING OF 43.



OUTBOARD PROFILE



VESSEL PARTICULARS	
LENGTH OVERALL:	183'-7"
LENGTH DESIGN LOAD WATERLINE:	178'-3/8"
BEAM, MOLDED:	46'-0"
BEAM OVER GUARDS:	46'-10"
DEPTH AT SIDE:	10'-6"
DRAFT AT DLWL:	4'-6"
FREEBOARD AT SIDE:	6'-0"
TOTAL PASSENGER CAPACITY:	300 MAX.
VEHICLE CAPACITY:	40 SV

REFERENCES	
1.	18026-200-832-1 TECHNICAL SPECIFICATION
2.	18026-200-101-1 PROFILES AND DECK ARRANGEMENTS



Elliott Bay Design Group
 North Carolina, PLLC

CLIENT: NORTH CAROLINA D.O.T.
 RALEIGH, NORTH CAROLINA



PROJECT: DOUBLE-ENDED AZIMUTH DRIVE FERRY



WINDOW SCHEDULE					
SIZE	D	DWG NO.	18026-200-624-1	REV	-
SCALE	1/8"=1'-0"	FILE NAME	18026-200-624-1-	SHEET	1 OF 3
DWN	MWR	MOD	CKD KAJ	APVD	KAJ
				APVD DATE	8/3/2018

8/3/2018 2:26:52 PM

CONFIDENTIAL AND PROPRIETARY PROPERTY OF
EBDG - NC, PLLC
 MAY NOT BE USED FOR CONSTRUCTION OR PROVIDED TO
 ANY THIRD PARTIES WITHOUT PRIOR WRITTEN CONSENT.
 ©2018 ELLIOTT BAY DESIGN GROUP.





SIZE	D	DWG NO.	18026-200-624-1	REV	-
SCALE	1/8"=1'-0"	FILE NAME	18026-200-624-1-	SHEET	2 OF 3

8/3/2018 2:29:00 PM

CONFIDENTIAL AND PROPRIETARY PROPERTY OF
EBDG - NC, PLLC
 MAY NOT BE USED FOR CONSTRUCTION OR PROVIDED TO
 ANY THIRD PARTIES WITHOUT PRIOR WRITTEN CONSENT.
 © 2018 ELLIOTT BAY DESIGN GROUP.

6 5 4 3 2 1



SIZE	D	DWG NO.	18026-200-624-1	REV	-
SCALE	1/8"=1'-0"	FILE NAME	18026-200-624-1-	SHEET	3 OF 3

6 5 4 3 2 1

8/3/2018 2:29:10 PM