



MAP 1
NC 62
Mill 1/2" Depth.
Pave 1/2" S9.5C

MAP 2
NC 109
Mill 1/2" Depth
Pave 1/2" S9.5C
Mill and Pave same day.
DO NOT Pave ramps.
Tie into new surfaces at
NC 62 / Julian Ave.
intersection.

MAP 14
Fisher Ferry St. SR 2183
Mill 1/2" Depth.
Pave with 1/2" S9.5C

MAP 15
Liberty St. SR 2055
Mill 1/2" Depth.
Pave 1/2" S9.5C
Tie into new surface at NC 62.

MAP 16
Kennedy Rd. SR 2066
Mill 1/2" Depth.
Pave 1/2" S9.5C
Tie into new surface at Liberty St.
Pave to south of intersection of
Fuller Mill Rd. SR 2091

MAP 30
Quail SR 2766
Mill 1/2" Depth
Pave 1/2" S9.5B
NO SHOULDER WORK
NO THERMO

MAP 31
Summers Trail SR 2767
Mill 1/2" Depth
Pave 1/2" S9.5B
NO SHOULDER WORK
NO THERMO

MAP 32
Game Trail SR 2806
NO MILL
NO SHOULDER WORK
NO THERMO
Pave 1/2" S9.5B

MAP 33
Kaylan Lane SR 2834
NO MILL
NO THERMO
Pave 1/2" S9.5B

MAP 34
Heritage Court SR 2835
NO MILL
NO THERMO
Pave 1/2" S9.5B

DAVIDSON COUNTY
NORTH CAROLINA

Project Note: Installation of signal loops will be handled by state forces.