

NICHOLAS J. TENNYSON Secretary

June 13, 2016

MEMORANDUM TO: David Leonard, P.E.

DDC Engineer – Division 3

DocuSigned by:

K.J. Kim

FROM: Kyung Kim, P.E.

Eastern Regional Geologian Manager

STATE PROJECT: 40238.1.4 (U-4902D)

FEDERAL PROJECT: NHS-0017(76) COUNTY: New Hanover

DESCRIPTION: US 17 Business (Market Street) from Lendire Road SR 2734

(Marsh Oaks Drive)

SUBJECT: Roadway Subsurface Inventory Report and Roadway Design

Recommendations Report

The Geotechnical Engineering Unit has reviewed and presents the following report prepared by Catlin Engineers & Scientists for the above referenced project.

Roadway Subsurface Inventory Report: 20 pages Roadway Design Recommendations Report: 5 pages

Please call Dean N Argenbright, L.G. at (252) 355-9054 or Majid Khazaei, P.E. at (919) 662-4710 if there are any questions concerning this memorandum.

Attachment KJK/DNA/MK





Telephone: (910) 452-5861 Fax: (910) 452-7563

www.catlinusa.com

June 13, 2016

MEMORANDUM TO: John L. Pilipchuk, LG, PE

State Geotechnical Engineer

FROM: Steven V. Hudson, LG

CATLIN Geotechnical Geologist

STATE PROJECT: 40238.1.4 (U-4902D)

F.A. NUMBER: NHS-0017(76) COUNTY: NEW HANOVER

DESCRIPTION: US 17 Business (Market Street) from Lendire Road to Marsh

Oaks Drive

SUBJECT: Geotechnical Report – Design and Construction

Recommendations

CATLIN Engineers and Scientists (CATLIN) has completed a subsurface investigation for this project and presents the following recommendations:

I. SLOPE/EMBANKMENT STABILITY

A. Slope Design

Recommend roadway side slopes be constructed no steeper than 3:1 (H:V) in order to assist in erosion control and establish vegetation.

B. Undercut (Soft Foundation Soils)

Include 200 cubic yards in the contract as a contingency item to be used at the discretion of the Engineer.

C. Geotextile for Soil Stabilization

Include 200 square yards of fabric for soil stabilization in the contract as a contingency item to be used at the discretion of the Engineer.

II. SUBGRADE STABILITY

A. Subsurface Drainage – Subsurface Drains

Recommend including 200 linear feet of subdrain pipe (Roadway Standard Drawing 815.02) in the contract as a contingency item to be used at the discretion of the Engineer.

B. Undercut for Subgrade Stability

Include 200 cubic yards in the contract as a contingency item to be used at the discretion of the Engineer.

C. Aggregate Subgrade

Include 100 cubic yards of shallow undercut for aggregate subgrade in the contract as a contingency item to be used at the discretion of the Engineer.

D. Geotextile for Soil Stabilization

Recommend contingency of 200 square yards of soil stabilization fabric to be used for subgrade stability as outlined in Section II.B.

Recommend 300 square yards be included in the contract for soil stabilization as a contingency item for use with aggregate subgrade as outlined in Section II.C.

Recommend an additional 200 square yards for soil stabilization be included in the contract as a contingency item to be used at the discretion of the Engineer.

III. BORROW SPECIFICATIONS

A. Borrow Criteria

Common borrow for embankment construction to subgrade shall meet Coastal Plain specifications outlined in the Standard Specifications, Article 1018-2, Section II.

B. Select Granular Material

Recommend 400 cubic yards of Select Granular Material be included as a contingency in the contract for backfill as detailed in Sections I.B and II.B.

Recommend 200 cubic yards of Select Granular Material, Class II and/or III to be included in the contract as a contingency item. Select granular material for embankment/backfill for geotextile for soil stabilization if required, or backfill in

water shall meet the criteria outlined in the Standard Specifications, Article 1016-3, Class II and/or III.

C. Shrinkage Factor

A shrinkage factor of 25 percent is recommended for calculation of earthwork in the contract.

D. Borrow Reconnaissance and Availability

Sandy soils with good to excellent engineering properties are available in nearby areas.

E. Class IV Subgrade Stabilization Material

A quantity of 190 tons of Class IV subgrade stabilization material should be included in the project contract as backfill for the Aggregate Subgrade referenced in Section II.C. The material should meet the requirement of Standard Specifications, Article 10-16-3 Class IV.

IV. MISCELLANEOUS

A. Reduction of Unclassified Excavation – Loss Due to Clearing and Grubbing

No significant loss of unclassified excavation is anticipated due to clearing and grubbing.


B. Reduction of Unclassified Excavation - Unsuitable Waste

Unclassified excavation will be predominantly derived from ditch and subgrade excavation and is comprised primarily of granular material which is estimated to be 100 percent suitable for embankment construction.

C. Water Wells


No water wells were identified with the proposed right of way limits on this project. However, if any water wells are identified during construction activities, the well/s should be sealed by a North Carolina Certified Well Contractor in accordance with the North Carolina Department of Transportation Standard Specification, Section 205, "Sealing Abandoned Wells".

Prepared By:



U4902D_GEO_Rdwy_Recs_FINAL.docx

Prepared By:



CATLIN Geotechnical Engineer

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION GEOTECHNICAL ENGINEERING UNIT



Summary of Quantities

WBS Number: 40238.1.4 County: New Hanover

TIP Number: U-4902D Field Office: GFO

Description: US 17 Business (Market Street) from Lendire Road to Marsh Oaks Drive

| Project Engineer: | JCW (CATLIN) | | | |
|--------------------|--------------|--|--|--|
| Project Geologist: | SVH (CATLIN) | | | |

| No. Quantity Adjustment Special Provision (SP) Reference Section Anginnent Station Quantity % 0036000000-E Undercut Excavation 225 - Roadway Excavation I. B Contingency N/A N/A 200 CY 003600000-E Undercut Excavation 225 - Roadway Excavation II. B Contingency N/A N/A 200 CY 019500000-E Select Granular Material 265 - Select Granular Material III. B Contingency N/A N/A 600 CY 019500000-E Select Granular Material 265 - Select Granular Material III. B Contingency N/A N/A 600 CY 019600000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization I. C Contingency N/A N/A 200 SY 109950000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization II. D Contingency N/A N/A N/A SY 109950000-E Shallow Undercut 505 - Aggregate Subgrade III | Pay Item | Pay Item/ | Spec Book Section No. or | Report | 1 Alignment | Alignment | lignment Begin | End | Quantity | Units / |
|--|---|-----------------------------------|---|---------|-------------|-----------|----------------|----------|----------|---------|
| 0036000000-E Undercut Excavation 225 - Roadway Excavation II. B Contingency N/A N/A 200 CY 0195000000-E Select Granular Material 265 - Select Granular Material III. B Contingency N/A N/A 600 CY 0196000000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization I. C Contingency N/A N/A 200 SY 0196000000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization II. D Contingency N/A N/A N/A 200 SY 1099500000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization II. D Contingency N/A N/A N/A 700 SY 1099500000-E Shallow Undercut 505 - Aggregate Subgrade II. C Contingency N/A N/A N/A 100 CY 1099700000-E Class IV Subgrade Stabilization 505 - Aggregate Subgrade III. E Contingency N/A N/A 100 CY 1099700000- | No. | Quantity Adjustment | Special Provision (SP) Reference | Section | | Station | Station | Quantity | % | |
| Total Quantity of Undercut Excavation = 400 CY 0195000000-E Select Granular Material 265 - Select Granular Material III. B Contingency N/A N/A 600 CY 0196000000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization II. C Contingency N/A N/A 200 SY 0196000000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization II. D Contingency N/A N/A 700 SY Total Quantity of Geotextile for Soil Stabilization 900 SY 1099500000-E Shallow Undercut 505 - Aggregate Subgrade III. C Contingency N/A N/A 100 CY 1099700000-E Class IV Subgrade Stabilization 505 - Aggregate Subgrade III. E Contingency N/A N/A 190 TON 109970000-E Class IV Subgrade Stabilization 505 - Aggregate Subgrade III. E Contingency N/A N/A 190 TON 2044000000-E 6" Perforated Subdrain Pipe 815 - Subsurface Drainage II. A Contingency N/A N/A N/A 200 LF | 0036000000-Е | Undercut Excavation | 225 - Roadway Excavation | I. B | Contingency | N/A | N/A | 200 | CY | |
| O19500000-E Select Granular Material 265 - Select Granular Material III. B Contingency N/A N/A 600 CY | 0036000000-Е | Undercut Excavation | 225 - Roadway Excavation | II. B | Contingency | N/A | N/A | 200 | CY | |
| Total Quantity of Select Granular Material = 600 CY 0196000000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization II. C Contingency N/A N/A 200 SY 0196000000-E Geotextile for Soil Stabilization 270 - Geotextile for Soil Stabilization II. D Contingency N/A N/A 700 SY Total Quantity of Geotextile for Soil Stabilization 900 SY 1099500000-E Shallow Undercut 505 - Aggregate Subgrade II. C Contingency N/A N/A 100 CY 1099700000-E Class IV Subgrade Stabilization 505 - Aggregate Subgrade III. E Contingency N/A N/A 190 TON Total Quantity of Class IV Subgrade Stabilization 190 TON 2044000000-E 6" Perforated Subdrain Pipe 815 - Subsurface Drainage II. A Contingency N/A N/A N/A 200 LF | Total Quantity of Undercut Excavation = | | | | | | | 400 | CY | |
| 0196000000-EGeotextile for Soil Stabilization270 - Geotextile for Soil StabilizationI. CContingencyN/AN/A200SY019600000-EGeotextile for Soil Stabilization270 - Geotextile for Soil StabilizationII. DContingencyN/AN/AN/A700SYTotal Quantity of Geotextile for Soil Stabilization900SY1099500000-EShallow Undercut505 - Aggregate SubgradeII. CContingencyN/AN/A100CY109970000-EClass IV Subgrade Stabilization505 - Aggregate SubgradeIII. EContingencyN/AN/A190TON204400000-E6" Perforated Subdrain Pipe815 - Subsurface DrainageII. AContingencyN/AN/AN/A200LF | 0195000000-E | Select Granular Material | 265 - Select Granular Material | III. B | Contingency | N/A | N/A | 600 | CY | |
| 019600000-EGeotextile for Soil Stabilization270 - Geotextile for Soil StabilizationII. DContingencyN/AN/A700SYTotal Quantity of Geotextile for Soil Stabilization = For Soil Stabilization = For Soil Stabilization900SY1099500000-EShallow Undercut505 - Aggregate SubgradeII. CContingencyN/AN/A100CY109970000-EClass IV Subgrade Stabilization505 - Aggregate SubgradeIII. EContingencyN/AN/A190TON2044000000-E6" Perforated Subdrain Pipe815 - Subsurface DrainageII. AContingencyN/AN/AN/A200LF | Total Quantity of Select Granular Material = | | | | | | | 600 | CY | |
| Total Quantity of Geotextile for Soil Stabilization = 900 SY 109950000-E Shallow Undercut 505 - Aggregate Subgrade II. C Contingency N/A N/A 100 CY 109970000-E Class IV Subgrade Stabilization 505 - Aggregate Subgrade III. E Contingency N/A N/A 190 TON 109970000-E Class IV Subgrade Stabilization 505 - Aggregate Subgrade III. E Contingency N/A N/A 190 TON 109970000-E 6" Perforated Subdrain Pipe 815 - Subsurface Drainage II. A Contingency N/A N/A 200 LF | 0196000000-E | Geotextile for Soil Stabilization | 270 - Geotextile for Soil Stabilization | I. C | Contingency | N/A | N/A | 200 | SY | |
| 109950000-EShallow Undercut505 - Aggregate SubgradeII. CContingencyN/AN/A100CYTotal Quantity of Shallow Undercut = 100CY1099700000-EClass IV Subgrade Stabilization505 - Aggregate SubgradeIII. EContingencyN/AN/A190TONTotal Quantity of Class IV Subgrade Stabilization = 100TON2044000000-E6" Perforated Subdrain Pipe815 - Subsurface DrainageII. AContingencyN/AN/AN/A200LF | 0196000000-E | Geotextile for Soil Stabilization | 270 - Geotextile for Soil Stabilization | II. D | Contingency | N/A | N/A | 700 | SY | |
| Total Quantity of Shallow Undercut = 100 CY 1099700000-E Class IV Subgrade Stabilization 505 - Aggregate Subgrade III. E Contingency N/A N/A 190 TON Total Quantity of Class IV Subgrade Stabilization = 190 TON 204400000-E 6" Perforated Subdrain Pipe 815 - Subsurface Drainage II. A Contingency N/A N/A 200 LF | Total Quantity of Geotextile for Soil Stabilization = | | | | | | | 900 | SY | |
| 1099700000-E Class IV Subgrade Stabilization 505 - Aggregate Subgrade III. E Contingency N/A N/A 190 TON Total Quantity of Class IV Subgrade Stabilization = 190 TON 2044000000-E 6" Perforated Subdrain Pipe 815 - Subsurface Drainage II. A Contingency N/A N/A 200 LF | 1099500000-E | Shallow Undercut | 505 - Aggregate Subgrade | II. C | Contingency | N/A | N/A | 100 | CY | |
| Total Quantity of Class IV Subgrade Stabilization = 190 TON 204400000-E 6" Perforated Subdrain Pipe 815 - Subsurface Drainage II. A Contingency N/A N/A 200 LF | Total Quantity of Shallow Undercut = | | | | | | | 100 | CY | |
| 2044000000-E 6" Perforated Subdrain Pipe 815 - Subsurface Drainage II. A Contingency N/A N/A 200 LF | 1099700000-E | Class IV Subgrade Stabilization | 505 - Aggregate Subgrade | III. E | Contingency | N/A | N/A | 190 | TON | |
| | Total Quantity of Class IV Subgrade Stabilization = | | | | | | | 190 | TON | |
| Total Quantity of 6" Perforated Subdrain Pipe = 200 LF | 2044000000-E | 6" Perforated Subdrain Pipe | 815 - Subsurface Drainage | II. A | Contingency | N/A | N/A | 200 | LF | |
| | Total Quantity of 6" Perforated Subdrain Pipe = | | | | | | 200 | LF | | |

| These Items Only Impact Earthwork Totals | | | | | | | | | |
|--|------------------|-------------------|--------|-----|-----|-----|----|---|--|
| N/A | Shrinkage Factor | 235 - Embankments | III. C | N/A | N/A | N/A | 25 | % | |