

Maps 2 thru 4 are omitted.

PROJECT NO.	SHEET NO.	TOTAL NO.
2019CPT.08.06.10471, etc	11	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGT	WID	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	1.5" MILLING	INCIDENTAL MILLING	INTER-MEDIATE COURSE, I19.0C	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ADJ. OF MAN HOLES	ADJ. OF METER OR VALVE BOXES	INDUCTIVE LOOP SAWCUT	LEAD-IN CABLE (14-2 PAIR)	
										MI	FT	SMI	TON	SY	SY	TONS	TONS	TONS	TONS	EA	EA	LF	LF		
2019CPT.08.06.10471	Hoke	1	US HWY 401(LAURINBURG RD)	FROM SR 1208(CRAWFORD WRIGHT RD.) TO START OF MULTI. LN	1	2	2WU	NO	NO	1.78	28	3.56	500	32,420			2,945		197						
			TOTAL FOR PROJ NO. 2019CPT.08.06.10471									1.78		3.56	500	32,420			2,945		197				
2019CPT.08.06.10831	Scotland	5	US 401 BUS.(N. MAIN/WAGRAM RD.)	FROM US HWY. 15 BUS.(ABERDEEN RD.) TO US HWY. 401(MCCOLL RD)	5,6	2	2WU	NO	NO	1.43	30	1.44	201	25,571				2,365	142	11	7	4			
			6	US HWY 15 BUS.(ABERDEEN RD./N. MAIN ST.)	FROM BRIDGE AT US HWY 401 BY-PASS(MCCOLL RD.) TO US HWY. 74 BUS.(W. CHURCH ST.)	3,4,5	2	2WU	NO	NO	1.65	44	0.80	111	38,105				3,525	211	223	33	32	4,726	
TOTAL FOR PROJ NO. 2019CPT.08.06.10831										3.08		2.24	312	63,676				5,890	353	234	40	36	4,726		
2019CPT.08.06.20471	Hoke	7	SR 1209 (CHILTON DR.)	RD.) TO SR1244(W. PALMER ST.)	2	2	2WU	NO	NO	0.18	28	0.49	140		586		410		27	11		5			
			8	SR 1244 (W. PALMER ST.)	FROM SR 1311(MOCKINGBIRD HILL RD.) TO SR 1209(W. PALMER ST.)	2	2	2WU	NO	NO	0.84	28	1.61	225		618		1,430		96	212	4	1		
			9	SR 1311 (MOCKINGBIRD HILL RD.)	FROM NC 211(ABERDEEN DR) TO SR 1310(ALEX BAKER RD.)	2	2	2WU	NO	NO	1.12	20	2.16	302		1,193		1,325		88	161				
			10	SR 1413 (PITTMAN GROVE CHURCH RD.)	FROM SR 1422(PHILIP CH. RD.) TO SR 1103(N. MCPHATTER RD)	2	2	2WU	NO	NO	3.08	22	6.20	868		1,032		4,135		277	302				
			11	SR 1406 (ROCKFISH RD.)	1418(LINDSAY RD.) TO SR 1413(PITTMAN GROVE CHURCH RD.) RD)	2	2	2WU	NO	NO	2.83	22	5.77	808		1,477		4,680		313	273		12	468	28
TOTAL FOR PROJ NO. 2019CPT.08.06.20471										8.05		16.23	2,343		4,906		11,980		801	959	4	18	468	28	
2019CPT.08.06.20831	Scotland	12	SPRING HILL VFD	10 X 55	7	2	2WU	NO	NO	0.01	10					11	8		1						
			13	SR 1336 (BROADWELL RD.)	FROM SR 1323 (MCFARLAND RD.) TO SR 1323 (SNEADS GROVE RD.)	2	2	2WU	NO	NO	1.58	22	3.17	444		560		1,780		119	47				
			14	SR 1303 (FIELDCREST RD.)	FROM US HWY 74 BUS. TO NC HWY 144(OLD WIRE RD.)	2	2	2WU	NO	NO	3.11	24	6.37	892		1,664		4,640		311	197				
TOTAL FOR PROJ NO. 2019CPT.08.06.20831										4.7		9.54	1,336		2,224	11	6,428		431	244					
GRAND TOTAL										17.61		31.57	4,491	96,096	7,130	11	21,353	5,890	1,782	1,437	44	54	5,194	28	