PROJECT NO.	SHEET NO.	TOTAL NO.
2020CPT.05.13.10911.1, etc.	11	

THERMOPLASTIC AND PAINT QUANTITIES

									4413000000-E	4685000000-E	4686000000-E		4695000000-E		4700000000-E	4705000000-E	4710000000-E	4721000000-E								4725000000-E								4770000000-E		4810000000-E		4835000000-E	4845000000-N			4850000000-E	4905000000-N
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	4" X 90 M WHITE THERMO	4" X 120 M YELLOW THERMO	4" X 120 M WHITE THERMO	8" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	12" x 90 m Yellow Thermo	16" X 120 M WHITE THERMO	24" X 120 M WHITE THERMO	THERMO MSG ONLY 120 M	Thermo Msg SCHOOL 120 m	THERMO RXR 120 M	THERMO MSG KEEP 120 M	THERMO MSG CLEAR 120 M	THERMO MSG AHEAD 120 M	THERMO MSG STOP 120 M	THERMO STR & RT ARROW 90 M	THERMO LT ARROW 90 M	THERMO MERGE ARROW 90 M	THERMO STR & LT ARROW 90 M	THERMO STR ARROW 90 M	THERMO RT ARROW 90 M	THERMO LT STR RT ARROW 90 M	THERMO YIELD TRIANGLE 90 M	4" White Cold Applied Plastic, Type II	4" Yellow Cold Applied Plastic, Type II	4" WHITE PAINT	4" YELLOW PAINT	24" WHITE PAINT	PAINT MERGE ARROW	PAINT STR ARROW	PAINT LT ARROW	4" LINE REMOVAL	SNOW PLOWABLE MARKERS
							MI	FT	SF	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA	EA	EA	LF	EA
2020CPT.05.13.10911.1	Vance	1	NC 39	SR 1577 - LOOP RD TO .25 MI S. OF SR 1560 - GARLAND ST	1	2	2.01	24	225	20,172	21,113	467			279		88								4	5																168
		2	NC 39	.25 MI S. OF SR 1560 - GARLAND ST TO I-85	4	2	2.9	34	325	666	26,518	5,013	812			100	630	8		4					20	28	7	4	17	2			128	712							840	450
TOTAL FOR PROJ NO. 2020CPT.05.13.10911.1							**4.91**		**550**	**20,838**	**47,631**	**5,480**	**812**		**279**	**100**	**718**	**8**		**4**					**24**	**33**	**7**	**4**	**17**	**2**			**128**	**712**							**840**	**618**
											53,111		**812**					**12**						**87**								**840**									
2020CPT.05.13.10931.1	Warren	3	US 401	SR 1001 - W FRANKLIN ST TO TAR HEEL TIRE AVE	4	2	1.45	40	162	365	13,974	1,985		740			141				8	10				2	5		2						2,350	13,974	141	5	2	2		200
		4	US 401	TAR HEEL TIRE AVE TO US - 158 - BYP	1	2	1.78	24	126	18,548	14,182	175		412			28									2			2													127
TOTAL FOR PROJ NO. 2020CPT.05.13.10931.1							**3.23**		**288**	**18,913**	**28,156**	**2,160**		**1,152**			**169**				**8**	**10**				**4**	**5**		**4**						**2,350**	**13,974**	**141**	**5**	**2**	**2**		**327**
											30,316		**1,152**					**18**						**13**											**16,324**			**9**			
2020CPT.05.13.20911.1	Vance	5	SR 1371 - FLEMINGTOWN RD	US - 1 TO END MAINT	1	2	3.31	20	371	34,494	33,396	227	432	397			75																									
		6	SR 1444 - WILLOW CREEK RUN	SR 1326 - KELLY RD TO END MAINT	3	2	0.42	20	47																																	
		7	SR 1448 - W CREEK RD	US - 158 - BYP TO DEAD END	3	2	0.34	20	38																																	
		8	SR 1519 - CAREY CHAPEL RD/ ROCK MILL RD/ GILLBURG RD	SR 1001 - W FRANKLIN ST TO SR 1549 - BOBBITT RD	1	2	9.86	20	1,104	100,288	84,593	792			174		80		24				10	16		4					2	18										
		9	SR 1562 - CARDINAL DR	NC 39 TO PAVMT JOINT	2	2	0.21	20	24	2,260	2,166						48																									
		10	SR 1574 - MARTIN CREEK RD	SR 1115 - BEARPOND RD TO SR 1148 - VANCO MILL RD	1	2	1.55	20	174	15,190	16,234	131																														
		11	SR 1619 - FRIAR LN	SR 1549 - BOBBITT RD TO SR 1620 - S CHAUCER WAY	3	2	0.14	20	16																																	
		12	SR 1620 - S CHAUCER WAY	CUL-DE-SAC TO CUL-DE-SAC	3	2	0.38	20	43																																	
TOTAL FOR PROJ NO. 2020CPT.05.13.20911.1							**16.21**		**1,817**	**152,232**	**136,389**	**1,150**	**432**	**397**	**174**		**203**		**24**				**10**	**16**		**4**					**2**	**18**										
											137,539		**829**					**50**						**24**																	
2020CPT.05.13.20931.1	Warren	14	SR 1337 - FLEMING MILL RD	SR 1344 - EATON FERRY RD TO SR 1335 - CHURCH HILL RD	2	2	3.88	20	435	40,472	37,101																														1,000	
TOTAL FOR PROJ NO. 2020CPT.05.13.20931.1							**3.88**		**435**	**40,472**	**37,101**																														**1,000**	
											37,101																															
GRAND TOTAL							**28.23**		**3,090**	**232,455**	**249,277**	**8,790**	**1,244**	**1,549**	**453**	**100**	**1,090**	**8**	**24**	**4**	**8**	**10**	**10**	**16**	**24**	**41**	**12**	**4**	**21**	**2**	**2**	**18**	**128**	**712**	**2,350**	**13,974**	**141**	**5**	**2**	**2**	**1,840**	**945**
											258,067		**2,793**					**80**						**124**								**840**		**16,324**			**9**			