





































































**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**




























**This file or an individual page
shall not be considered a certified document.**

-  1 INSTALL REA, PE - 22, SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE
-  2 INSTALL COAXIAL CABLE
-  3 INSTALL CATEGORY 5E CABLE
-  4 INSTALL SMFO CABLE
-  5 BACK-PULL/REMOVE EXISTING COMMUNICATIONS CABLE
-  6 INSTALL FIBER OPTIC DROP CABLE
-  7 INSTALL TRACER WIRE
-  8 TRENCH
-  9 INSTALL PVC CONDUIT
-  10 INSTALL RIGID, GALVANIZED STEEL CONDUIT
-  11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
-  12 INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC SEAL
-  13 INSTALL OUTER-DUCT POLYETHYLENE CONDUIT
-  14 INSTALL POLYETHYLENE CONDUIT
-  15 DIRECTIONAL DRILL CONDUIT
-  16 BORE AND JACK CONDUIT
-  17 INSTALL CABLE(S) IN EXISTING CONDUIT
-  18 INSTALL CABLE(S) IN NEW CONDUIT
-  19 INSTALL CABLE(S) IN EXISTING RISER(S)
-  20 INSTALL CABLE(S) IN NEW RISER(S)
-  21 INSTALL CABLE(S) IN EXISTING CONDUIT STUBOUTS
-  22 INSTALL NEW CONDUIT INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
-  23 INSTALL NEW RISER INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
-  24 INSTALL NEW CONDUIT INTO POLE MOUNTED CABINET
-  25 INSTALL NEW RISER INTO POLE MOUNTED CABINET
-  26 MODIFY EXISTING INTERCONNECT CENTER/ SPLICE ENCLOSURE
-  27 INSTALL NEW FIBER OPTIC TRANSCEIVER
-  28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPLICE CABLE IN CABINET
- 29 INSTALL UNDERGROUND SPLICE ENCLOSURE
- 30 INSTALL AERIAL SPLICE ENCLOSURE





-  31 INSTALL POLE MOUNTED SPLICE CABINET
-  32 INSTALL BASE MOUNTED SPLICE CABINET
-  33 REMOVE EXISTING SPLICE CABINET
-  34 INSTALL CABINET FOUNDATION
-  35 INSTALL CCTV CAMERA POLE MOUNTED CABINET
-  36 INSTALL CCTV CAMERA ASSEMBLY
-  37 INSTALL CCTV CAMERA WOOD POLE
-  38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION
-  39 INSTALL JUNCTION BOX
-  40A INSTALL OVERSIZED JUNCTION BOX
-  40B INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" x 36" x 24")
-  41 REMOVE EXISTING JUNCTION BOX
-  42 INSTALL WOOD POLE
-  43 REMOVE EXISTING WOOD POLE
-  44 INSTALL AERIAL GUY ASSEMBLY
-  45 INSTALL STANDARD GUY ASSEMBLY
-  46 INSTALL SIDEWALK GUY ASSEMBLY
-  47 INSTALL MESSENGER CABLE
-  48A REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE
-  48B REMOVE EXISTING COMMUNICATIONS CABLE
-  48C REMOVE EXISTING MESSENGER CABLE
-  49 BACK-PULL EXISTING COMMUNICATIONS CABLE
-  50 REMOVE EXISTING COMMUNICATIONS CABLE MOUNTING HARDWARE
-  51 INSTALL CABLE STORAGE RACK(S) [SNOW SHOE(S)] AND STORE 100 FEET OF CABLE
-  52A INSTALL DELINEATOR MARKER
-  52B INSTALL JUNCTION BOX MARKER
-  53 STORE 20 FEET OF COMMUNICATIONS CABLE
-  54 REINSTALL BACKPULLED CABLE(S)
- 55 LASH CABLE(S) TO EXISTING MESSENGER CABLE


-  56 STORE BACKPULLED FIBER OPTIC CABLE ON STORAGE RACKS
-  57 MODIFY EXISTING ELECTRICAL SERVICE
-  58 INSTALL NEW ELECTRICAL SERVICE
-  59 INSTALL NEW ETHERNET EDGE SWITCH
-  60 BOND TRACER WIRE TO EQUIPMENT GROUND BUS
-  61 DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS
-  62 BOND RISER AND MESSENGER CABLE TO POLE GROUND
-  63 BOND RISER TO POLE GROUND
-  64 BOND MESSENGER CABLE TO POLE GROUND
-  65 INSTALL HEAT SHRINK TUBING RETROFIT KIT
-  66 INSTALL MOLDABLE DUCT SEAL
-  67 SLACK SPAN

LEGEND



-  NEW FIBER OPTIC COMMUNICATIONS CABLE
-  NEW TWISTED PAIR COMMUNICATIONS CABLE
-  EXISTING COMMUNICATIONS CABLE
-  EXISTING COMMUNICATIONS CABLE TO BE REMOVED
-  NEW AERIAL GUY ASSEMBLY
-  NEW CONDUIT
-  EXISTING CONDUIT
-  NEW DIRECTIONAL DRILLED CONDUIT
-  NEW BORED AND JACKED CONDUIT
-  NEW JUNCTION BOX
-  EXISTING JUNCTION BOX
-  NEW WOOD POLE
-  EXISTING WOOD POLE
-  NEW AERIAL SPLICE ENCLOSURE
-  NEW METAL POLE
-  EXISTING METAL POLE
-  NEW CCTV CAMERA ASSEMBLY
-  NEW STANDARD GUY ASSEMBLY
-  NEW STANDARD GUY USING EXISTING ANCHOR
-  NEW SIDEWALK GUY ASSEMBLY
-  NEW CABLE STORAGE RACKS (SNOW SHOES)
-  EXISTING CABLE STORAGE RACKS (SNOW SHOES)
-  EXISTING CONTROLLER AND CABINET
-  EXISTING SPLICE CABINET
-  NEW SPLICE CABINET
-  SIGNAL POLE
-  SIGNAL INVENTORY NUMBER

CONSTRUCTION NOTE SYMBOLY KEY

-  INDICATES NUMBER OF CABLES, LOOPS, ETC.
-  INDICATES NUMBER OF FIBERS PER CABLE, TWISTED PAIRS PER CABLE, ETC.
-  INDICATES NUMBER OF RISER(S)/CONDUIT(S)
-  INDICATES DIAMETER OF RISER(S)/CONDUIT(S) (INCH)








ATTACHMENT POINT:

-  DISTANCE ABOVE INCHES REFERENCE POINT
-  REFERENCE POINT DISTANCE BELOW INCHES

8:53:37 AM U:\F01\F01\F01\sg\gnals\des\sgn\ITS and SCP Des\sgn\Des\scd2\Legend.dgn User: rfrincey

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

 Stantec Consulting Services Inc. 801 Jones Franklin Road-Suite 300 Raleigh, NC 27606 Tel. (919) 851-6866 Fax. (919) 851-7024 www.stantec.com License No. F-0672	Prepared for the Offices of:  750 N. Greenfield Pkwy, Garner, NC 27529 SCALE N.T.S.	SR 1001 (Sugar Hill Road) Construction Notes and Legend Division 13 McDowell County Marion PLAN DATE: February 2019 REVIEWED BY: E D Harris PREPARED BY: G B Spell REVIEWED BY: L Overn	SEAL  E. D. HARRIS ENGINEER SEAL 045933 DATE: 2/6/2019	
	REVISIONS _____ INIT. DATE	_____ INIT. DATE	_____ INIT. DATE	_____ DATE
	_____ _____ _____ _____ _____	_____ _____ _____ _____ _____	_____ _____ _____ _____ _____	_____ _____ _____ _____ _____



- GENERAL NOTES:**
- NOTIFY THE NCDOT DIVISION 13 TRAFFIC ENGINEER, ANNA HENDERSON PE, AT 828-251-6171 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE CLOSED LOOP SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE CLOSED LOOP SYSTEM IS BACK UP AND OPERATIONAL.
 - CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
 - CONTRACTOR MUST DISCONNECT THE EXISTING 12 SMFO CABLE FROM SPLICE TRAY IN SIGNAL CABINET AND PULL BACK TO THE CABLE STORAGE RACKS AS SHOWN BEFORE REINSTALLING AND RESPLICING THE CABLE.

1 INSTALL RIGID, GALVANIZED STEEL CONDUIT	13 INSTALL OUTER-DUCT POLYETHYLENE CONDUIT	25 INSTALL NEW RISER INTO POLE MOUNTED CABINET	37 INSTALL CCTV CAMERA WOOD POLE	48A REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE	57 MODIFY EXISTING ELECTRICAL SERVICE
2 INSTALL COAXIAL CABLE	14 INSTALL POLYETHYLENE CONDUIT	26 MODIFY EXISTING INTERCONNECT CENTER/ SPLICE ENCLOSURE	38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION	48B REMOVE EXISTING COMMUNICATIONS CABLE	58 INSTALL NEW ELECTRICAL SERVICE
3 INSTALL CATEGORY 5E CABLE	15 DIRECTIONAL DRILL CONDUIT	27 INSTALL NEW FIBER OPTIC TRANSCEIVER	39 INSTALL JUNCTION BOX	48C REMOVE EXISTING MESSENGER CABLE	59 INSTALL NEW ETHERNET EDGE SWITCH
4 INSTALL SMFO CABLE	16 BORE AND JACK CONDUIT	28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPLICE CABLE IN CABINET	40A INSTALL OVERSIZED JUNCTION BOX	49 BACK-PULL EXISTING COMMUNICATIONS CABLE	60 BOND TRACER WIRE TO EQUIPMENT GROUND BUS
5 BACK-PULL/REMOVE EXISTING COMMUNICATIONS CABLE	17 INSTALL CABLE(S) IN EXISTING CONDUIT	29 INSTALL UNDERGROUND SPLICE ENCLOSURE	40B INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" x 36" x 24")	50 REMOVE EXISTING COMMUNICATIONS CABLE MOUNTING HARDWARE	61 DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS
6 INSTALL FIBER OPTIC DROP CABLE	18 INSTALL CABLE(S) IN NEW CONDUIT	30 INSTALL AERIAL SPLICE ENCLOSURE	41 REMOVE EXISTING JUNCTION BOX	51 INSTALL CABLE STORAGE RACK(S) [SNOW SHOE(S)] AND STORE 100 FEET OF CABLE	62 BOND RISER AND MESSENGER CABLE TO POLE GROUND
7 INSTALL TRACER WIRE	19 INSTALL CABLE(S) IN EXISTING RISER(S)	31 INSTALL POLE MOUNTED SPLICE CABINET	42 INSTALL WOOD POLE	52A INSTALL DELINEATOR MARKER	63 BOND RISER TO POLE GROUND
8 TRENCH	20 INSTALL CABLE(S) IN NEW RISER(S)	32 INSTALL BASE MOUNTED SPLICE CABINET	43 REMOVE EXISTING WOOD POLE	52B INSTALL JUNCTION BOX MARKER	64 BOND MESSENGER CABLE TO POLE GROUND
9 INSTALL PVC CONDUIT	21 INSTALL CABLE(S) IN EXISTING CONDUIT STUBOUTS	33 REMOVE EXISTING SPLICE CABINET	44 INSTALL AERIAL GUY ASSEMBLY	53 STORE 20 FEET OF COMMUNICATIONS CABLE	65 INSTALL HEAT SHRINK TUBING RETROFIT KIT
10 INSTALL RIGID, GALVANIZED STEEL CONDUIT	22 INSTALL NEW CONDUIT INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	34 INSTALL CABINET FOUNDATION	45 INSTALL STANDARD GUY ASSEMBLY	54 REINSTALL BACKPULLED CABLE(S)	66 INSTALL MOLDABLE DUCT SEAL
11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD	23 INSTALL NEW RISER INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	35 INSTALL CCTV CAMERA POLE MOUNTED CABINET	46 INSTALL SIDEWALK GUY ASSEMBLY	55 LASH CABLE(S) TO EXISTING MESSENGER CABLE	67 SLACK SPAN
12 INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC SEAL	24 INSTALL NEW CONDUIT INTO POLE MOUNTED CABINET	36 INSTALL CCTV CAMERA ASSEMBLY	47 INSTALL MESSENGER CABLE	56 STORE BACKPULLED FIBER OPTIC CABLE ON STORAGE RACKS	

TMP Phase I

Stantec Consulting Services Inc. Tel. (919) 851-6866
801 Jones Franklin Road Fax. (919) 851-7024
Suite 300 www.stantec.com
Raleigh, NC 27606 License No. F-0672

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

NORTH CAROLINA PROFESSIONAL ENGINEER

LAURENCE E. OVERTON

045933

Prepared for the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

SR 1001 (Sugar Hill Road)

Cable Routing Plans

Division 13 McDowell County Marion

PLAN DATE: February 2019 REVIEWED BY: E D Harris

PREPARED BY: G B Spell REVIEWED BY: L Overn

REVISIONS	INIT.	DATE

SCALE



0 40

1" = 40'

8:48:17 AM U:\Projects\Signal\Design\ITS and SCP Design\Cable Routing\U-5818_scp3_cr_tmp.dgn User: rmuoney

2/6/2019

CADD Filename: _____



- GENERAL NOTES:**
1. NOTIFY THE NCDOT DIVISION 13 TRAFFIC ENGINEER, ANNA HENDERSON PE, AT 828-251-6171 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE CLOSED LOOP SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE CLOSED LOOP SYSTEM IS BACK UP AND OPERATIONAL.
 2. CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.

1 INSTALL REAL PE - 22, SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE	13 INSTALL OUTER-DUCT POLYETHYLENE CONDUIT	25 INSTALL NEW RISER INTO POLE MOUNTED CABINET	37 INSTALL CCTV CAMERA WOOD POLE	48A REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE	57 MODIFY EXISTING ELECTRICAL SERVICE
2 INSTALL COAXIAL CABLE	14 INSTALL POLYETHYLENE CONDUIT	26 MODIFY EXISTING INTERCONNECT CENTER/ SPLICE ENCLOSURE	38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION	48B REMOVE EXISTING COMMUNICATIONS CABLE	58 INSTALL NEW ELECTRICAL SERVICE
3 INSTALL CATEGORY 5E CABLE	15 DIRECTIONAL DRILL CONDUIT	27 INSTALL NEW FIBER OPTIC TRANSCEIVER	39 INSTALL JUNCTION BOX	48C REMOVE EXISTING MESSENGER CABLE	59 INSTALL NEW ETHERNET EDGE SWITCH
4 INSTALL SMFO CABLE	16 BORE AND JACK CONDUIT	28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPLICE CABLE IN CABINET	40A INSTALL OVERSIZED JUNCTION BOX	49 BACK-PULL EXISTING COMMUNICATIONS CABLE	60 BOND TRACER WIRE TO EQUIPMENT GROUND BUS
5 BACK-PULL/REMOVE EXISTING COMMUNICATIONS CABLE	17 INSTALL CABLE(S) IN EXISTING CONDUIT	29 INSTALL UNDERGROUND SPLICE ENCLOSURE	40B INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" x 36" x 24")	50 REMOVE EXISTING COMMUNICATIONS CABLE MOUNTING HARDWARE	61 DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS
6 INSTALL FIBER OPTIC DROP CABLE	18 INSTALL CABLE(S) IN NEW CONDUIT	30 INSTALL AERIAL SPLICE ENCLOSURE	41 REMOVE EXISTING JUNCTION BOX	51 INSTALL CABLE STORAGE RACK(S) [SNOW SHOE(S)] AND STORE 100 FEET OF CABLE	62 BOND RISER AND MESSENGER CABLE TO POLE GROUND
7 INSTALL TRACER WIRE	19 INSTALL CABLE(S) IN EXISTING RISER(S)	31 INSTALL POLE MOUNTED SPLICE CABINET	42 INSTALL WOOD POLE	52A INSTALL DELINEATOR MARKER	63 BOND RISER TO POLE GROUND
8 TRENCH	20 INSTALL CABLE(S) IN NEW RISER(S)	32 INSTALL BASE MOUNTED SPLICE CABINET	43 REMOVE EXISTING WOOD POLE	52B INSTALL JUNCTION BOX MARKER	64 BOND MESSENGER CABLE TO POLE GROUND
9 INSTALL PVC CONDUIT	21 INSTALL CABLE(S) IN EXISTING CONDUIT STUBOUTS	33 REMOVE EXISTING SPLICE CABINET	44 INSTALL AERIAL GUY ASSEMBLY	53 STORE 20 FEET OF COMMUNICATIONS CABLE	65 INSTALL HEAT SHRINK TUBING RETROFIT KIT
10 INSTALL RIGID, GALVANIZED STEEL CONDUIT	22 INSTALL NEW CONDUIT INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	34 INSTALL CABINET FOUNDATION	45 INSTALL STANDARD GUY ASSEMBLY	54 REINSTALL BACKPULLED CABLE(S)	66 INSTALL MOLDABLE DUCT SEAL
11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD	23 INSTALL NEW RISER INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	35 INSTALL CCTV CAMERA POLE MOUNTED CABINET	46 INSTALL SIDEWALK GUY ASSEMBLY	55 LASH CABLE(S) TO EXISTING MESSENGER CABLE	67 SLACK SPAN
12 INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC SEAL	24 INSTALL NEW CONDUIT INTO POLE MOUNTED CABINET	36 INSTALL CCTV CAMERA ASSEMBLY	47 INSTALL MESSENGER CABLE		

TMP Phase I

Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27606

Tel. (919) 851-6866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672

SR 1001 (Sugar Hill Road)

Cable Routing Plans

Division 13 McDowell County Marion

PLAN DATE: February 2019 REVIEWED BY: E D Harris

PREPARED BY: G B Spell REVIEWED BY: L Overn

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

NORTH CAROLINA PROFESSIONAL ENGINEER



LAURENCE E. OVERTON

2/6/2019

750 N. Greenfield Hwy, Garner, NC 27529

SCALE: 0 40
1" = 40'

8:48:18 AM U:\Projects\Signal\Design\ITS and SCP Design\Cable Routing\U-5818_scp4_cr_tmp.dgn User:lrincey



TMP Phase I

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

LEGEND

COLOR CODE TIA/EIA 598-B		E =	EXISTING FUSION SPLICE INDIVIDUAL FIBER TO REMAIN
(1) BLUE	(7) RED	X =	FUSION SPLICE INDIVIDUAL FIBER
(2) ORANGE	(8) BLACK	C =	CAP AND SEAL
(3) GREEN	(9) YELLOW	EXPRESS =	EXPRESS ENTIRE BUFFER TUBE/FIBERS THROUGH WITHOUT CUTTING
(4) BROWN	(10) VIOLET	BUFFER SPLICE =	SPLICE ALL FIBERS IN BUFFER TUBE COLOR TO COLOR
(5) SLATE	(11) ROSE		
(6) WHITE	(12) AQUA		
(13-XXXX) =	PROPOSED		
(13-XXXX) =	CABINET/CONTROLLER EXISTING		
(13-XXXX) =	CABINET/CONTROLLER		

- NOTES:**
- UNUSED FIBERS AND/OR BUFFER TUBES LEFT COILED AND STORED IN SPLICE TRAY.
 - CONTRACTOR TO FURNISH SELF HEALING RING TYPE TRANSCEIVERS.
 - TRANSCEIVER CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.
 - NOTIFY THE NCDOT DIVISION 13 TRAFFIC ENGINEER ANNA HENDERSON, PE AT 828-251-6171 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE CLOSED LOOP SYSTEM. COMMUNICATIONS CABLE NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE CLOSED LOOP SYSTEM IS BACK UP AND OPERATIONAL AFTER FINAL PHASE OF CONSTRUCTION.
 - CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
 - INCLUDE ON THE COVER OF SPLICE TRAY THE FOLLOWING INFORMATION (REFERENCE STANDARD SPECIFICATIONS SECTION 1731):
A. SPLICE LOCATION
B. DATE
C. COMPANY NAME
D. NAME OF INDIVIDUAL PERFORMING THE SPLICE
- PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY, TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (ITEMS A-D) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS

Stantec Consulting Services Inc.
801 Jones Franklin Road-Suite 300
Raleigh, NC 27606
Tel. (919) 851-6866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672

Prepared for the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

SCALE
N.T.S.

SR 1001 (Sugar Hill Road)
Fiber Optic Splice Details


Division 13	McDowell County	Marion
PLAN DATE: February 2019	REVIEWED BY: E D Harris	
PREPARED BY: G B Spell	REVIEWED BY: L Overn	
REVISIONS	INIT.	DATE

SEAL

2/6/2019

CADD Filename:

8:51:17 AM U:\Projects\Signal\Design\ITS and SCP Design\Fiber Splicing Detail\U-5818_scp5_fs.dgn User: rmcnee



CONSTRUCTION NOTE SYMBOLOLOGY KEY

NUMBER OF CABLE(S)/LOOPS, DETECTOR AMPLIFIERS, GUYS, ANTENNAS: XX

NUMBER OF FIBERS/TWISTED PAIRS: XX

NUMBER OF RISER(S)/CONDUIT(S): XX

DIAMETER OF RISER(S)/CONDUIT(S) (IN): XX

ATTACHMENT POINT:

XXX
YYY DISTANCE ABOVE INCHES REFERENCE POINT

YYY
XXX REFERENCE POINT DISTANCE BELOW INCHES

- GENERAL NOTES:**
1. NOTIFY THE NCDOT DIVISION 13 TRAFFIC ENGINEER, ANNA HENDERSON PE, AT 828-251-6171 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE CLOSED LOOP SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE CLOSED LOOP SYSTEM IS BACK UP AND OPERATIONAL.
 2. CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
 3. CONTRACTOR MUST REINSTALL THE EXISTING FIBER-OPTIC CABLE AND RESPLICE IN THE NEW SIGNAL CABINET. CONTRACTOR SHALL RESPLICE THE CABLE IN ACCORDANCE WITH RECORDS OF EXISTING SPLICE CONFIGURATION TAKEN DURING TMP PHASE I.

1. INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD	13. INSTALL OUTER-DUCT POLYETHYLENE CONDUIT	25. INSTALL NEW RISER INTO POLE MOUNTED CABINET	37. INSTALL CCTV CAMERA WOOD POLE	48A. REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE	57. MODIFY EXISTING ELECTRICAL SERVICE
2. INSTALL COAXIAL CABLE	14. INSTALL POLYETHYLENE CONDUIT	26. MODIFY EXISTING INTERCONNECT CENTER/ SPLICE ENCLOSURE	38. INSTALL CCTV CAMERA METAL POLE AND FOUNDATION	48B. REMOVE EXISTING COMMUNICATIONS CABLE	58. INSTALL NEW ELECTRICAL SERVICE
3. INSTALL CATEGORY 5E CABLE	15. DIRECTIONAL DRILL CONDUIT	27. INSTALL NEW FIBER OPTIC TRANSCIVER	39. INSTALL JUNCTION BOX	48C. REMOVE EXISTING MESSENGER CABLE	59. INSTALL NEW ETHERNET EDGE SWITCH
4. INSTALL SMFO CABLE	16. BORE AND JACK CONDUIT	28. INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPLICE CABLE IN CABINET	40A. INSTALL OVERSIZED JUNCTION BOX	49. BACK-PULL EXISTING COMMUNICATIONS CABLE	60. BOND TRACER WIRE TO EQUIPMENT GROUND BUS
5. BACK-PULL/REMOVE EXISTING COMMUNICATIONS CABLE	17. INSTALL CABLE(S) IN EXISTING CONDUIT	29. INSTALL UNDERGROUND SPLICE ENCLOSURE	40B. INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" x 36" x 24")	50. REMOVE EXISTING COMMUNICATIONS CABLE MOUNTING HARDWARE	61. DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS
6. INSTALL FIBER OPTIC DROP CABLE	18. INSTALL CABLE(S) IN NEW CONDUIT	30. INSTALL AERIAL SPLICE ENCLOSURE	41. REMOVE EXISTING JUNCTION BOX	51. INSTALL CABLE STORAGE RACK(S) [SNOW SHOE(S)] AND STORE 100 FEET OF CABLE	62. BOND RISER AND MESSENGER CABLE TO POLE GROUND
7. INSTALL TRACER WIRE	19. INSTALL CABLE(S) IN EXISTING RISER(S)	31. INSTALL POLE MOUNTED SPLICE CABINET	42. INSTALL WOOD POLE	52A. INSTALL DELINEATOR MARKER	63. BOND RISER TO POLE GROUND
8. TRENCH	20. INSTALL CABLE(S) IN NEW RISER(S)	32. INSTALL BASE MOUNTED SPLICE CABINET	43. REMOVE EXISTING WOOD POLE	52B. INSTALL JUNCTION BOX MARKER	64. BOND MESSENGER CABLE TO POLE GROUND
9. INSTALL PVC CONDUIT	21. INSTALL CABLE(S) IN EXISTING CONDUIT STUBOUTS	33. REMOVE EXISTING SPLICE CABINET	44. INSTALL AERIAL GUY ASSEMBLY	53. STORE 20 FEET OF COMMUNICATIONS CABLE	65. INSTALL HEAT SHRINK TUBING RETROFIT KIT
10. INSTALL RIGID, GALVANIZED STEEL CONDUIT	22. INSTALL NEW CONDUIT INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	34. INSTALL CABINET FOUNDATION	45. INSTALL STANDARD GUY ASSEMBLY	54. REINSTALL BACKPULLED CABLE(S)	66. INSTALL MOLDABLE DUCT SEAL
11. INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD	23. INSTALL NEW RISER INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	35. INSTALL CCTV CAMERA POLE MOUNTED CABINET	46. INSTALL SIDEWALK GUY ASSEMBLY	55. LASH CABLE(S) TO EXISTING MESSENGER CABLE	67. SLACK SPAN
12. INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC SEAL	24. INSTALL NEW CONDUIT INTO POLE MOUNTED CABINET	36. INSTALL CCTV CAMERA ASSEMBLY	47. INSTALL MESSENGER CABLE	56. STORE BACKPULLED FIBER OPTIC CABLE ON STORAGE RACKS	

FINAL DESIGN

Stantec Consulting Services Inc. Tel. (919) 851-6866
801 Jones Franklin Road Fax. (919) 851-7024
Suite 300 www.stantec.com
Raleigh, NC 27606 License No. F-0672

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

LAURENCE E. OVERTON
ENGINEER
045933

SR 1001 (Sugar Hill Road)

Cable Routing Plans

Division 13 McDowell County Marion

PLAN DATE: February 2019 REVIEWED BY: E D Harris

PREPARED BY: G B Spell REVIEWED BY: L Overn

750 N. Greenfield Pkwy, Garner, NC 27529

0 SCALE 40
1" = 40'

Prepared for the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

REVISIONS



NO.	DESCRIPTION	INIT.	DATE

2/6/2019

DATE

CADD Filename:

8:48:20 AM U:\Projects\Signal\Design\ITS and SCP Design\Cable Routing\U-5818_scp6_cr_Final.dgn User:lrincey



- GENERAL NOTES:**
- NOTIFY THE NCDOT DIVISION 13 TRAFFIC ENGINEER, ANNA HENDERSON PE, AT 828-251-6171 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE CLOSED LOOP SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE CLOSED LOOP SYSTEM IS BACK UP AND OPERATIONAL.
 - CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.

1 INSTALL RIA PE - 22, SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE	13 INSTALL OUTER-DUCT POLYETHYLENE CONDUIT	25 INSTALL NEW RISER INTO POLE MOUNTED CABINET	37 INSTALL CCTV CAMERA WOOD POLE	48A REMOVE EXISTING COMMUNICATIONS AND MESSENGER CABLE	57 MODIFY EXISTING ELECTRICAL SERVICE
2 INSTALL COAXIAL CABLE	14 INSTALL POLYETHYLENE CONDUIT	26 MODIFY EXISTING INTERCONNECT CENTER/ SPLICE ENCLOSURE	38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION	48B REMOVE EXISTING COMMUNICATIONS CABLE	58 INSTALL NEW ELECTRICAL SERVICE
3 INSTALL CATEGORY 5E CABLE	15 DIRECTIONAL DRILL CONDUIT	27 INSTALL NEW FIBER OPTIC TRANSCEIVER	39 INSTALL JUNCTION BOX	48C REMOVE EXISTING MESSENGER CABLE	59 INSTALL NEW ETHERNET EDGE SWITCH
4 INSTALL SMFO CABLE	16 BORE AND JACK CONDUIT	28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPLICE CABLE IN CABINET	40A INSTALL OVERSIZED JUNCTION BOX	49 BACK-PULL EXISTING COMMUNICATIONS CABLE	60 BOND TRACER WIRE TO EQUIPMENT GROUND BUS
5 BACK-PULL/REMOVE EXISTING COMMUNICATIONS CABLE	17 INSTALL CABLE(S) IN EXISTING CONDUIT	29 INSTALL UNDERGROUND SPLICE ENCLOSURE	40B INSTALL SPECIAL OVERSIZED JUNCTION BOX (36" x 36" x 24")	50 REMOVE EXISTING COMMUNICATIONS CABLE MOUNTING HARDWARE	61 DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS
6 INSTALL FIBER OPTIC DROP CABLE	18 INSTALL CABLE(S) IN NEW CONDUIT	30 INSTALL AERIAL SPLICE ENCLOSURE	41 REMOVE EXISTING JUNCTION BOX	51 INSTALL CABLE STORAGE RACK(S) [SNOW SHOE(S)] AND STORE 100 FEET OF CABLE	62 BOND RISER AND MESSENGER CABLE TO POLE GROUND
7 INSTALL TRACER WIRE	19 INSTALL CABLE(S) IN EXISTING RISER(S)	31 INSTALL POLE MOUNTED SPLICE CABINET	42 INSTALL WOOD POLE	52A INSTALL DELINEATOR MARKER	63 BOND RISER TO POLE GROUND
8 TRENCH	20 INSTALL CABLE(S) IN NEW RISER(S)	32 INSTALL BASE MOUNTED SPLICE CABINET	43 REMOVE EXISTING WOOD POLE	52B INSTALL JUNCTION BOX MARKER	64 BOND MESSENGER CABLE TO POLE GROUND
9 INSTALL PVC CONDUIT	21 INSTALL CABLE(S) IN EXISTING CONDUIT STUB-OUTS	33 REMOVE EXISTING SPLICE CABINET	44 INSTALL AERIAL GUY ASSEMBLY	53 STORE 20 FEET OF COMMUNICATIONS CABLE	65 INSTALL HEAT SHRINK TUBING RETROFIT KIT
10 INSTALL RIGID, GALVANIZED STEEL CONDUIT	22 INSTALL NEW CONDUIT INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	34 INSTALL CABINET FOUNDATION	45 INSTALL STANDARD GUY ASSEMBLY	54 REINSTALL BACKPULLED CABLE(S)	66 INSTALL MOLDABLE DUCT SEAL
11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD	23 INSTALL NEW RISER INTO CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)	35 INSTALL CCTV CAMERA POLE MOUNTED CABINET	46 INSTALL SIDEWALK GUY ASSEMBLY	55 LASH CABLE(S) TO EXISTING MESSENGER CABLE	67 SLACK SPAN
12 INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC SEAL	24 INSTALL NEW CONDUIT INTO POLE MOUNTED CABINET	36 INSTALL CCTV CAMERA ASSEMBLY	47 INSTALL MESSENGER CABLE	56 STORE BACKPULLED FIBER OPTIC CABLE ON STORAGE RACKS	

FINAL DESIGN

Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27606

Tel. (919) 851-6866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672

SR 1001 (Sugar Hill Road)

Cable Routing Plans

Division 13 McDowell County Marion

PLAN DATE: February 2019 REVIEWED BY: E D Harris



PREPARED BY: G B Spell REVIEWED BY: L Overn

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

2/6/2019

8:48:21 AM
 U:\Projects\Signal\Design\ITS and SCP Design\Cable Routing\U-5818_scp7_cr_Final.dgn
 User:lrincey



8:51:18 AM
 U:\Projects\Signal\Design\ITS and SCP Design\Fiber Splicing Detail\U-5818_scp8_fs.dgn
 User: rrmoney

LEGEND

[COLOR CODE TABLE]		E = EXISTING FUSION SPLICE INDIVIDUAL FIBER TO REMAIN
(1) BLUE	(7) RED	X = FUSION SPLICE INDIVIDUAL FIBER
(2) ORANGE	(8) BLACK	C = CAP AND SEAL
(3) GREEN	(9) YELLOW	EXPRESS = EXPRESS ENTIRE BUFFER TUBE/FIBERS THROUGH WITHOUT CUTTING
(4) BROWN	(10) VIOLET	BUFFER SPLICE = SPLICE ALL FIBERS IN BUFFER TUBE COLOR TO COLOR
(5) SLATE	(11) ROSE	SM FIBER PATCH CORD WITH CONNECTORS
(6) WHITE	(12) AQUA	
13-XXXX = PROPOSED CABINET/CONTROLLER EXISTING		
13-XXXX = CABINET/CONTROLLER		

NOTES:

- UNUSED FIBERS AND/OR BUFFER TUBES LEFT COILED AND STORED IN SPLICE TRAY.
- CONTRACTOR TO FURNISH SELF HEALING RING TYPE TRANSCEIVERS.
- TRANSCEIVER CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.
- NOTIFY THE NCDOT DIVISION 13 TRAFFIC ENGINEER ANNA HENDERSON, PE, AT 828-251-6171 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE CLOSED LOOP SYSTEM COMMUNICATIONS CABLE. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE CLOSED LOOP SYSTEM IS BACK UP AND OPERATIONAL AFTER FINAL PHASE OF CONSTRUCTION.
- CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
- INCLUDE ON THE COVER OF SPLICE TRAY THE FOLLOWING INFORMATION (REFERENCE STANDARD SPECIFICATIONS SECTION 1731):
 - A. SPLICE LOCATION
 - B. DATE
 - C. COMPANY NAME
 - D. NAME OF INDIVIDUAL PERFORMING THE SPLICE
 PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY, TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (ITEMS A-D) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS

Stantec Consulting Services Inc.
 801 Jones Franklin Road-Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672

Prepared for the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

SCALE: N.T.S.

SR 1001 (Sugar Hill Road)
Fiber Optic Splice Details

Division 13	McDowell County	Marion
PLAN DATE: February 2019	REVIEWED BY: E D Harris	
PREPARED BY: G B Spell	REVIEWED BY: L Overn	
REVISIONS	INIT.	DATE


DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

2/6/2019

CADD Filename:

FINAL DESIGN



EXISTING
CONTROLLER
CABINET

SPLICE NO. 5
13-1227
SR 1001 (SUGAR HILL ROAD)
AT I-40 WB RAMP

8:51:19 AM U:\Projects\Signal\Design\ITS and SCP Design\Fiber Splicing Detail\13-1227-SCP-9.fs.dgn User: rrmoney

LEGEND

COLOR CODE TIA/EIA 598-B		
(1) BLUE	(7) RED	E = EXISTING FUSION SPLICE INDIVIDUAL FIBER TO REMAIN
(2) ORANGE	(8) BLACK	X = FUSION SPLICE INDIVIDUAL FIBER
(3) GREEN	(9) YELLOW	C = CAP AND SEAL
(4) BROWN	(10) VIOLET	EXPRESS = EXPRESS ENTIRE BUFFER TUBE/FIBERS THROUGH WITHOUT CUTTING
(5) SLATE	(11) ROSE	BUFFER SPLICE = SPLICE ALL FIBERS IN BUFFER TUBE COLOR TO COLOR
(6) WHITE	(12) AQUA	SM FIBER PATCH CORD WITH CONNECTORS
13-XXXX = PROPOSED		
13-XXXX = CABINET/CONTROLLER EXISTING		
13-XXXX = CABINET/CONTROLLER		

NOTES:

- UNUSED FIBERS AND/OR BUFFER TUBES LEFT COILED AND STORED IN SPLICE TRAY.
- CONTRACTOR TO FURNISH SELF HEALING RING TYPE TRANSCEIVERS.
- TRANSCEIVER CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.
- NOTIFY THE NCDOT DIVISION 13 TRAFFIC ENGINEER ANNA HENDERSON, PE, AT 828-251-6171 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE CLOSED LOOP SYSTEM. COMMUNICATIONS CABLE NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE CLOSED LOOP SYSTEM IS BACK UP AND OPERATIONAL AFTER FINAL PHASE OF CONSTRUCTION.
- CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
- INCLUDE ON THE COVER OF SPLICE TRAY THE FOLLOWING INFORMATION (REFERENCE STANDARD SPECIFICATIONS SECTION 1731):
 A. SPLICE LOCATION
 B. DATE
 C. COMPANY NAME
 D. NAME OF INDIVIDUAL PERFORMING THE SPLICE
 PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY, TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (ITEMS A-D) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS

Stantec Consulting Services Inc.
801 Jones Franklin Road-Suite 300
Raleigh, NC 27606
Tel. (919) 851-6866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672

Prepared for the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

SCALE
N.T.S.

FINAL DESIGN

SR 1001 (Sugar Hill Road)
Fiber Optic Splice Details

Division 13	McDowell County	Marion
PLAN DATE: February 2019	REVIEWED BY: E D Harris	
PREPARED BY: G B Spell	REVIEWED BY: L Overn	
REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

2/6/2019

CADD Filename: