

**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**

REFERENCE: R-1015

PROJECT: 34360

CONTENTS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND (SOIL & ROCK)
3-5	SITE PLAN
6-9	PROFILES
10-16	CROSS SECTIONS
17-42	BORE LOGS
43	SOIL TEST RESULTS
44	SITE PHOTOGRAPHS

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY CRAVEN

PROJECT DESCRIPTION US 70 (HAVELOCK BYPASS)
FROM NORTH OF CARTERET/CRAVEN COUNTY
LINE TO NORTH OF PINE GROVE ROAD

SITE DESCRIPTION SITE 3 - DUAL BRIDGES NO. 276
AND NO. 277 ON -L- (US 70 - HAVELOCK BYPASS)
OVER EAST PRONG OF SLOCUM CREEK
-L- STATION 177+67.00

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	R-1015	1	44

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

M. JOHNSON

P. GRAINGER

J.K. CRENSHAW

MID ATLANTIC INC.


INVESTIGATED BY J. K. CRENSHAW

DRAWN BY T. LYNN

CHECKED BY B. HOWEY

SUBMITTED BY B. D. KEANEY

DATE JULY, 2018



DocuSigned by:
Jared Crenshaw 7/31/2018
 3AB1C06A82EE4E1...
 SIGNATURE DATE



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

SOIL DESCRIPTION	GRADATION	ROCK DESCRIPTION	TERMS AND DEFINITIONS																																																																																																																																																																																																																																																																																																																																																																																																																															
<p>SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, <i>VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6</i></p>																																																																																																																																																																																																																																																																																																																																																																																																																																		
SOIL LEGEND AND AASHTO CLASSIFICATION																																																																																																																																																																																																																																																																																																																																																																																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th rowspan="2">GENERAL CLASS.</th> <th colspan="6">GRANULAR MATERIALS (≤ 35% PASSING #200)</th> <th colspan="6">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="3">ORGANIC MATERIALS</th> </tr> <tr> <th>A-1</th> <th>A-3</th> <th>A-2</th> <th>A-2-4</th> <th>A-2-5</th> <th>A-2-6</th> <th>A-2-7</th> <th>A-4</th> <th>A-5</th> <th>A-6</th> <th>A-7</th> <th>A-1, A-2</th> <th>A-3</th> <th>A-4, A-5</th> <th>A-6, A-7</th> <th></th> </tr> <tr> <td>GROUP CLASS.</td> <td>A-1-a</td> <td>A-1-b</td> <td>A-2-4</td> <td>A-2-5</td> <td>A-2-6</td> <td>A-2-7</td> <td></td> <td></td> <td></td> <td></td> <td>A-7-5</td> <td>A-7-6</td> <td></td> <td></td> <td></td> </tr> <tr> <td>SYMBOL</td> <td colspan="6">[Pattern]</td> <td colspan="6">[Pattern]</td> <td colspan="3">[Pattern]</td> </tr> <tr> <td>% PASSING #10 #40 #200</td> <td>50 MX 30 MX 15 MX</td> <td>50 MX 25 MX</td> <td>51 MN 35 MX</td> <td>35 MX 35 MX</td> <td>35 MX 35 MX</td> <td>35 MX 35 MX</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td>36 MN 36 MN</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>MATERIAL PASSING #40 LL PI</td> <td colspan="6">[Values]</td> <td colspan="6">[Values]</td> <td colspan="3">[Values]</td> </tr> <tr> <td>GROUP INDEX</td> <td colspan="6">[Values]</td> <td colspan="6">[Values]</td> <td colspan="3">[Values]</td> </tr> <tr> <td>USUAL TYPES OF MAJOR MATERIALS</td> <td colspan="2">STONE FRAGS. GRAVEL, AND SAND</td> <td colspan="2">FINE SAND</td> <td colspan="2">SILTY OR CLAYEY GRAVEL AND SAND</td> <td colspan="2">SILTY SOILS</td> <td colspan="2">CLAYEY SOILS</td> <td colspan="3">SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER</td> <td colspan="3">HIGHLY ORGANIC SOILS</td> </tr> <tr> <td>GEN. RATING AS SUBGRADE</td> <td colspan="6">EXCELLENT TO GOOD</td> <td colspan="6">FAIR TO POOR</td> <td colspan="3">FAIR TO POOR POOR UNSUITABLE</td> </tr> <tr> <td colspan="4" style="text-align: center;">PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30</td> </tr> <tr> <td colspan="4" style="text-align: center;">CONSISTENCY OR DENSENESS</td> </tr> <tr> <td>PRIMARY SOIL TYPE</td> <td>COMPACTNESS OR CONSISTENCY</td> <td>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</td> <td>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT²)</td> </tr> <tr> <td>GENERALLY GRANULAR MATERIAL (NON-COHESSIVE)</td> <td>VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE</td> <td>< 4 4 TO 10 10 TO 30 30 TO 50 > 50</td> <td>N/A</td> </tr> <tr> <td>GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD</td> <td>< 2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 > 30</td> <td>< 0.25 0.25 TO 0.5 0.5 TO 1.0 1 TO 2 2 TO 4 > 4</td> </tr> <tr> <td colspan="4" style="text-align: center;">TEXTURE OR GRAIN SIZE</td> </tr> <tr> <td>U.S. STD. SIEVE SIZE OPENING (MM)</td> <td>4 4.76</td> <td>10 2.00</td> <td>40 0.42</td> <td>60 0.25</td> <td>200 0.075</td> <td>270 0.053</td> </tr> <tr> <td>BOULDER (BLDR.)</td> <td>COBBLE (COB.)</td> <td>GRAVEL (GR.)</td> <td>COARSE SAND (CSE. SD.)</td> <td>FINE SAND (F SD.)</td> <td>SILT (SL.)</td> <td>CLAY (CL.)</td> </tr> <tr> <td>GRAIN SIZE</td> <td>MM 305 IN. 12</td> <td>75 3</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> </tr> <tr> <td colspan="4" style="text-align: center;">SOIL MOISTURE - CORRELATION OF TERMS</td> </tr> <tr> <td>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</td> <td>FIELD MOISTURE DESCRIPTION</td> <td>GUIDE FOR FIELD MOISTURE DESCRIPTION</td> </tr> <tr> <td>LL - LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>PLASTIC RANGE (PI)</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>PL - PLASTIC LIMIT</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>OM - OPTIMUM MOISTURE SHRINKAGE LIMIT</td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td colspan="4" style="text-align: center;">PLASTICITY</td> </tr> <tr> <td>NON PLASTIC</td> <td>PLASTICITY INDEX (PI) 0-5</td> <td>DRY STRENGTH VERY LOW</td> </tr> <tr> <td>SLIGHTLY PLASTIC</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>MODERATELY PLASTIC</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td>HIGHLY PLASTIC</td> <td>26 OR MORE</td> <td>HIGH</td> </tr> <tr> <td colspan="4" style="text-align: center;">COLOR</td> </tr> <tr> <td colspan="4">DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</td> </tr> <tr> <td colspan="4"> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="3">EQUIPMENT USED ON SUBJECT PROJECT</th> </tr> <tr> <td>DRILL UNITS:</td> <td>ADVANCING TOOLS:</td> <td>HAMMER TYPE:</td> </tr> <tr> <td><input type="checkbox"/> CME-45C</td> <td><input type="checkbox"/> CLAY BITS</td> <td><input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</td> </tr> <tr> <td><input type="checkbox"/> CME-55</td> <td><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</td> <td>CORE SIZE:</td> </tr> <tr> <td><input type="checkbox"/> CME-550</td> <td><input checked="" type="checkbox"/> 8" HOLLOW AUGERS</td> <td><input type="checkbox"/> -B <input type="checkbox"/> -H</td> </tr> <tr> <td><input type="checkbox"/> VANE SHEAR TEST</td> <td><input type="checkbox"/> HARD FACED FINGER BITS</td> <td><input type="checkbox"/> -N</td> </tr> <tr> <td><input type="checkbox"/> PORTABLE HOIST</td> <td><input type="checkbox"/> TUNG-CARBIDE INSERTS</td> <td>HAND TOOLS:</td> </tr> <tr> <td><input checked="" type="checkbox"/> D-25</td> <td><input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER</td> <td><input type="checkbox"/> POST HOLE DIGGER</td> </tr> <tr> <td><input checked="" type="checkbox"/> CME-45B</td> <td><input checked="" type="checkbox"/> TRICONE <input type="checkbox"/> 2 1/16" STEEL TEETH</td> <td><input type="checkbox"/> HAND AUGER</td> </tr> <tr> <td></td> <td><input type="checkbox"/> TRICONE <input type="checkbox"/> TUNG-CARB.</td> <td><input type="checkbox"/> SOUNDING ROD</td> </tr> <tr> <td></td> <td><input type="checkbox"/> CORE BIT</td> <td><input type="checkbox"/> VANE SHEAR TEST</td> </tr> <tr> <td></td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table> </td> </tr> <tr> <td colspan="4"> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">RECOMMENDATION SYMBOLS</th> </tr> <tr> <td></td> <td>UNDERCUT</td> </tr> <tr> <td></td> <td>SHALLOW UNDERCUT</td> </tr> <tr> <td></td> <td>UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE</td> </tr> <tr> <td></td> <td>UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK</td> </tr> </table> </td> </tr> <tr> <td colspan="4"> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="3">ABBREVIATIONS</th> </tr> <tr> <td>AR - AUGER REFUSAL</td> <td>MED. - MEDIUM MICA - MICACEOUS</td> <td>VST - VANE SHEAR TEST</td> </tr> <tr> <td>BT - BORING TERMINATED</td> <td>MOD. - MODERATELY NP - NON PLASTIC</td> <td>WEA. - WEATHERED</td> </tr> <tr> <td>CL - CLAY</td> <td>ORG. - ORGANIC</td> <td>UW - UNIT WEIGHT</td> </tr> <tr> <td>CPT - CONE PENETRATION TEST</td> <td>PMT - PRESSUREMETER TEST</td> <td>UDW - DRY UNIT WEIGHT</td> </tr> <tr> <td>CSE - COARSE</td> <td>SAP. - SAPROLITIC</td> <td>SAMPLE ABBREVIATIONS</td> </tr> <tr> <td>DMT - DILATOMETER TEST</td> <td>SD. - SAND, SANDY</td> <td>S - BULK</td> </tr> <tr> <td>DPT - DYNAMIC PENETRATION TEST</td> <td>SL. - SILTY, SILTY</td> <td>SS - SPLIT SPOON</td> </tr> <tr> <td>e - VOID RATIO</td> <td>SLI. - SLIGHTLY</td> <td>ST - SHELBY TUBE</td> </tr> <tr> <td>F - FINE</td> <td>TCR - TRICONE REFUSAL</td> <td>RS - ROCK</td> </tr> <tr> <td>FOSS. - FOSSILIFEROUS</td> <td>w - MOISTURE CONTENT</td> <td>RT - RECOMPACTED TRIAXIAL</td> </tr> <tr> <td>FRAC. - FRACTURED, FRACTURES</td> <td></td> <td>CBR - CALIFORNIA BEARING RATIO</td> </tr> <tr> <td>FRAGS. - FRAGMENTS</td> <td></td> <td></td> </tr> <tr> <td>HI. - HIGHLY</td> <td></td> <td></td> </tr> </table> </td> </tr> <tr> <td colspan="4"> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">ROCK HARDNESS</th> </tr> <tr> <td>VERY HARD</td> <td>CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.</td> </tr> <tr> <td>HARD</td> <td>CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.</td> </tr> <tr> <td>MODERATELY HARD</td> <td>CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.</td> </tr> <tr> <td>MEDIUM HARD</td> <td>CAN BE GROUDED OR GOUGED 0.25 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.</td> </tr> <tr> <td>SOFT</td> <td>CAN BE GROUDED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.</td> </tr> <tr> <td>VERY SOFT</td> <td>CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.</td> </tr> </table> </td> </tr> <tr> <td colspan="4"> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">FRACTURE SPACING</th> <th colspan="2">BEDDING</th> </tr> <tr> <td>TERM</td> <td>SPACING</td> <td>TERM</td> <td>THICKNESS</td> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> <td>VERY THICKLY BEDDED</td> <td>4 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FOOT</td> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td></td> <td></td> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </table> </td> </tr> <tr> <td colspan="4"> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">INDURATION</th> </tr> <tr> <td>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</td> <td></td> </tr> <tr> <td>FRIABLE</td> <td>RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</td> </tr> <tr> <td>MODERATELY INDURATED</td> <td>GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</td> </tr> <tr> <td>INDURATED</td> <td>GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</td> </tr> <tr> <td>EXTREMELY INDURATED</td> <td>SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</td> </tr> </table> </td> </tr> <tr> <td colspan="4"> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;">BENCH MARK: N/A</td> <td colspan="2" style="text-align: center;">ELEVATION: N/A FEET</td> </tr> <tr> <td colspan="4"> <p>NOTES: BORING LOCATIONS AND ELEVATIONS OBTAINED FROM MCKIM & CREED, INC. - 6/28/18</p> <p>UCP - UNDIVIDED COASTAL PLAIN FIAD - FILLED IMMEDIATELY AFTER DRILLING</p> </td> </tr> </table> </td> </tr> </table>				GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)						SILT-CLAY MATERIALS (> 35% PASSING #200)						ORGANIC MATERIALS			A-1	A-3	A-2	A-2-4	A-2-5	A-2-6	A-2-7	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7		GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7					A-7-5	A-7-6				SYMBOL	[Pattern]						[Pattern]						[Pattern]			% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX	51 MN 35 MX	35 MX 35 MX	35 MX 35 MX	35 MX 35 MX	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN						MATERIAL PASSING #40 LL PI	[Values]						[Values]						[Values]			GROUP INDEX	[Values]						[Values]						[Values]			USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS		SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER			HIGHLY ORGANIC SOILS			GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD						FAIR TO POOR						FAIR TO POOR POOR UNSUITABLE			PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30				CONSISTENCY OR DENSENESS				PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)	GENERALLY GRANULAR MATERIAL (NON-COHESSIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 4 4 TO 10 10 TO 30 30 TO 50 > 50	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	< 2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 > 30	< 0.25 0.25 TO 0.5 0.5 TO 1.0 1 TO 2 2 TO 4 > 4	TEXTURE OR GRAIN SIZE				U.S. STD. SIEVE SIZE OPENING (MM)	4 4.76	10 2.00	40 0.42	60 0.25	200 0.075	270 0.053	BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)	GRAIN SIZE	MM 305 IN. 12	75 3	2.0	0.25	0.05	0.005	SOIL MOISTURE - CORRELATION OF TERMS				SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	PLASTIC RANGE (PI)	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	PL - PLASTIC LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	PLASTICITY				NON PLASTIC	PLASTICITY INDEX (PI) 0-5	DRY STRENGTH VERY LOW	SLIGHTLY PLASTIC	6-15	SLIGHT	MODERATELY PLASTIC	16-25	MEDIUM	HIGHLY PLASTIC	26 OR MORE	HIGH	COLOR				DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.				<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="3">EQUIPMENT USED ON SUBJECT PROJECT</th> </tr> <tr> <td>DRILL UNITS:</td> <td>ADVANCING TOOLS:</td> <td>HAMMER TYPE:</td> </tr> <tr> <td><input type="checkbox"/> CME-45C</td> <td><input type="checkbox"/> CLAY BITS</td> <td><input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</td> </tr> <tr> <td><input type="checkbox"/> CME-55</td> <td><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</td> <td>CORE SIZE:</td> </tr> <tr> <td><input type="checkbox"/> CME-550</td> <td><input checked="" type="checkbox"/> 8" HOLLOW AUGERS</td> <td><input type="checkbox"/> -B <input type="checkbox"/> -H</td> </tr> <tr> <td><input type="checkbox"/> VANE SHEAR TEST</td> <td><input type="checkbox"/> HARD FACED FINGER BITS</td> <td><input type="checkbox"/> -N</td> </tr> <tr> <td><input type="checkbox"/> PORTABLE HOIST</td> <td><input type="checkbox"/> TUNG-CARBIDE INSERTS</td> <td>HAND TOOLS:</td> </tr> <tr> <td><input checked="" type="checkbox"/> D-25</td> <td><input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER</td> <td><input type="checkbox"/> POST HOLE DIGGER</td> </tr> <tr> <td><input checked="" type="checkbox"/> CME-45B</td> <td><input checked="" type="checkbox"/> TRICONE <input type="checkbox"/> 2 1/16" STEEL TEETH</td> <td><input type="checkbox"/> HAND AUGER</td> </tr> <tr> <td></td> <td><input type="checkbox"/> TRICONE <input type="checkbox"/> TUNG-CARB.</td> <td><input type="checkbox"/> SOUNDING ROD</td> </tr> <tr> <td></td> <td><input type="checkbox"/> CORE BIT</td> <td><input type="checkbox"/> VANE SHEAR TEST</td> </tr> <tr> <td></td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table>				EQUIPMENT USED ON SUBJECT PROJECT			DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:	<input type="checkbox"/> CME-45C	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL	<input type="checkbox"/> CME-55	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE:	<input type="checkbox"/> CME-550	<input checked="" type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> -B <input type="checkbox"/> -H	<input type="checkbox"/> VANE SHEAR TEST	<input type="checkbox"/> HARD FACED FINGER BITS	<input type="checkbox"/> -N	<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS	HAND TOOLS:	<input checked="" type="checkbox"/> D-25	<input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	<input type="checkbox"/> POST HOLE DIGGER	<input checked="" type="checkbox"/> CME-45B	<input checked="" type="checkbox"/> TRICONE <input type="checkbox"/> 2 1/16" STEEL TEETH	<input type="checkbox"/> HAND AUGER		<input type="checkbox"/> TRICONE <input type="checkbox"/> TUNG-CARB.	<input type="checkbox"/> SOUNDING ROD		<input type="checkbox"/> CORE BIT	<input type="checkbox"/> VANE SHEAR TEST		<input type="checkbox"/>	<input type="checkbox"/>	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">RECOMMENDATION SYMBOLS</th> </tr> <tr> <td></td> <td>UNDERCUT</td> </tr> <tr> <td></td> <td>SHALLOW UNDERCUT</td> </tr> <tr> <td></td> <td>UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE</td> </tr> <tr> <td></td> <td>UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK</td> </tr> </table>				RECOMMENDATION SYMBOLS			UNDERCUT		SHALLOW UNDERCUT		UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE		UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="3">ABBREVIATIONS</th> </tr> <tr> <td>AR - AUGER REFUSAL</td> <td>MED. - MEDIUM MICA - MICACEOUS</td> <td>VST - VANE SHEAR TEST</td> </tr> <tr> <td>BT - BORING TERMINATED</td> <td>MOD. - MODERATELY NP - NON PLASTIC</td> <td>WEA. - WEATHERED</td> </tr> <tr> <td>CL - CLAY</td> <td>ORG. - ORGANIC</td> <td>UW - UNIT WEIGHT</td> </tr> <tr> <td>CPT - CONE PENETRATION TEST</td> <td>PMT - PRESSUREMETER TEST</td> <td>UDW - DRY UNIT WEIGHT</td> </tr> <tr> <td>CSE - COARSE</td> <td>SAP. - SAPROLITIC</td> <td>SAMPLE ABBREVIATIONS</td> </tr> <tr> <td>DMT - DILATOMETER TEST</td> <td>SD. - SAND, SANDY</td> <td>S - BULK</td> </tr> <tr> <td>DPT - DYNAMIC PENETRATION TEST</td> <td>SL. - SILTY, SILTY</td> <td>SS - SPLIT SPOON</td> </tr> <tr> <td>e - VOID RATIO</td> <td>SLI. - SLIGHTLY</td> <td>ST - SHELBY TUBE</td> </tr> <tr> <td>F - FINE</td> <td>TCR - TRICONE REFUSAL</td> <td>RS - ROCK</td> </tr> <tr> <td>FOSS. - FOSSILIFEROUS</td> <td>w - MOISTURE CONTENT</td> <td>RT - RECOMPACTED TRIAXIAL</td> </tr> <tr> <td>FRAC. - FRACTURED, FRACTURES</td> <td></td> <td>CBR - CALIFORNIA BEARING RATIO</td> </tr> <tr> <td>FRAGS. - FRAGMENTS</td> <td></td> <td></td> </tr> <tr> <td>HI. - HIGHLY</td> <td></td> <td></td> </tr> </table>				ABBREVIATIONS			AR - AUGER REFUSAL	MED. - MEDIUM MICA - MICACEOUS	VST - VANE SHEAR TEST	BT - BORING TERMINATED	MOD. - MODERATELY NP - NON PLASTIC	WEA. - WEATHERED	CL - CLAY	ORG. - ORGANIC	UW - UNIT WEIGHT	CPT - CONE PENETRATION TEST	PMT - PRESSUREMETER TEST	UDW - DRY UNIT WEIGHT	CSE - COARSE	SAP. - SAPROLITIC	SAMPLE ABBREVIATIONS	DMT - DILATOMETER TEST	SD. - SAND, SANDY	S - BULK	DPT - DYNAMIC PENETRATION TEST	SL. - SILTY, SILTY	SS - SPLIT SPOON	e - VOID RATIO	SLI. - SLIGHTLY	ST - SHELBY TUBE	F - FINE	TCR - TRICONE REFUSAL	RS - ROCK	FOSS. - FOSSILIFEROUS	w - MOISTURE CONTENT	RT - RECOMPACTED TRIAXIAL	FRAC. - FRACTURED, FRACTURES		CBR - CALIFORNIA BEARING RATIO	FRAGS. - FRAGMENTS			HI. - HIGHLY			<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">ROCK HARDNESS</th> </tr> <tr> <td>VERY HARD</td> <td>CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.</td> </tr> <tr> <td>HARD</td> <td>CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.</td> </tr> <tr> <td>MODERATELY HARD</td> <td>CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.</td> </tr> <tr> <td>MEDIUM HARD</td> <td>CAN BE GROUDED OR GOUGED 0.25 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.</td> </tr> <tr> <td>SOFT</td> <td>CAN BE GROUDED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.</td> </tr> <tr> <td>VERY SOFT</td> <td>CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.</td> </tr> </table>				ROCK HARDNESS		VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.	HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.	MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.	MEDIUM HARD	CAN BE GROUDED OR GOUGED 0.25 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.	SOFT	CAN BE GROUDED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.	VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">FRACTURE SPACING</th> <th colspan="2">BEDDING</th> </tr> <tr> <td>TERM</td> <td>SPACING</td> <td>TERM</td> <td>THICKNESS</td> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> <td>VERY THICKLY BEDDED</td> <td>4 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FOOT</td> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td></td> <td></td> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </table>				FRACTURE SPACING		BEDDING		TERM	SPACING	TERM	THICKNESS	VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET	WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET	MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET	CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET	VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET			THINLY LAMINATED	< 0.008 FEET	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">INDURATION</th> </tr> <tr> <td>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</td> <td></td> </tr> <tr> <td>FRIABLE</td> <td>RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</td> </tr> <tr> <td>MODERATELY INDURATED</td> <td>GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</td> </tr> <tr> <td>INDURATED</td> <td>GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</td> </tr> <tr> <td>EXTREMELY INDURATED</td> <td>SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</td> </tr> </table>				INDURATION		FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.		FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.	MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.	INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.	EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;">BENCH MARK: N/A</td> <td colspan="2" style="text-align: center;">ELEVATION: N/A FEET</td> </tr> <tr> <td colspan="4"> <p>NOTES: BORING LOCATIONS AND ELEVATIONS OBTAINED FROM MCKIM & CREED, INC. - 6/28/18</p> <p>UCP - UNDIVIDED COASTAL PLAIN FIAD - FILLED IMMEDIATELY AFTER DRILLING</p> </td> </tr> </table>				BENCH MARK: N/A		ELEVATION: N/A FEET		<p>NOTES: BORING LOCATIONS AND ELEVATIONS OBTAINED FROM MCKIM & CREED, INC. - 6/28/18</p> <p>UCP - UNDIVIDED COASTAL PLAIN FIAD - FILLED IMMEDIATELY AFTER DRILLING</p>			
GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)						SILT-CLAY MATERIALS (> 35% PASSING #200)						ORGANIC MATERIALS																																																																																																																																																																																																																																																																																																																																																																																																																					
	A-1	A-3	A-2	A-2-4	A-2-5	A-2-6	A-2-7	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7																																																																																																																																																																																																																																																																																																																																																																																																																			
GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7					A-7-5	A-7-6																																																																																																																																																																																																																																																																																																																																																																																																																						
SYMBOL	[Pattern]						[Pattern]						[Pattern]																																																																																																																																																																																																																																																																																																																																																																																																																					
% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX	51 MN 35 MX	35 MX 35 MX	35 MX 35 MX	35 MX 35 MX	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN	36 MN 36 MN																																																																																																																																																																																																																																																																																																																																																																																																																								
MATERIAL PASSING #40 LL PI	[Values]						[Values]						[Values]																																																																																																																																																																																																																																																																																																																																																																																																																					
GROUP INDEX	[Values]						[Values]						[Values]																																																																																																																																																																																																																																																																																																																																																																																																																					
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND		FINE SAND		SILTY OR CLAYEY GRAVEL AND SAND		SILTY SOILS		CLAYEY SOILS		SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER			HIGHLY ORGANIC SOILS																																																																																																																																																																																																																																																																																																																																																																																																																				
GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD						FAIR TO POOR						FAIR TO POOR POOR UNSUITABLE																																																																																																																																																																																																																																																																																																																																																																																																																					
PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30																																																																																																																																																																																																																																																																																																																																																																																																																																		
CONSISTENCY OR DENSENESS																																																																																																																																																																																																																																																																																																																																																																																																																																		
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)																																																																																																																																																																																																																																																																																																																																																																																																																															
GENERALLY GRANULAR MATERIAL (NON-COHESSIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 4 4 TO 10 10 TO 30 30 TO 50 > 50	N/A																																																																																																																																																																																																																																																																																																																																																																																																																															
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	< 2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 > 30	< 0.25 0.25 TO 0.5 0.5 TO 1.0 1 TO 2 2 TO 4 > 4																																																																																																																																																																																																																																																																																																																																																																																																																															
TEXTURE OR GRAIN SIZE																																																																																																																																																																																																																																																																																																																																																																																																																																		
U.S. STD. SIEVE SIZE OPENING (MM)	4 4.76	10 2.00	40 0.42	60 0.25	200 0.075	270 0.053																																																																																																																																																																																																																																																																																																																																																																																																																												
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)																																																																																																																																																																																																																																																																																																																																																																																																																												
GRAIN SIZE	MM 305 IN. 12	75 3	2.0	0.25	0.05	0.005																																																																																																																																																																																																																																																																																																																																																																																																																												
SOIL MOISTURE - CORRELATION OF TERMS																																																																																																																																																																																																																																																																																																																																																																																																																																		
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																																																																																																																																																																																																																																																																
PLASTIC RANGE (PI)	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																																																																																																																																																																																																																
PL - PLASTIC LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																																																																																																																																																																																																																																																																
OM - OPTIMUM MOISTURE SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																																																																																																																																																																																																																
PLASTICITY																																																																																																																																																																																																																																																																																																																																																																																																																																		
NON PLASTIC	PLASTICITY INDEX (PI) 0-5	DRY STRENGTH VERY LOW																																																																																																																																																																																																																																																																																																																																																																																																																																
SLIGHTLY PLASTIC	6-15	SLIGHT																																																																																																																																																																																																																																																																																																																																																																																																																																
MODERATELY PLASTIC	16-25	MEDIUM																																																																																																																																																																																																																																																																																																																																																																																																																																
HIGHLY PLASTIC	26 OR MORE	HIGH																																																																																																																																																																																																																																																																																																																																																																																																																																
COLOR																																																																																																																																																																																																																																																																																																																																																																																																																																		
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																																																																																																																																																																																																																																																																																																																																																																																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="3">EQUIPMENT USED ON SUBJECT PROJECT</th> </tr> <tr> <td>DRILL UNITS:</td> <td>ADVANCING TOOLS:</td> <td>HAMMER TYPE:</td> </tr> <tr> <td><input type="checkbox"/> CME-45C</td> <td><input type="checkbox"/> CLAY BITS</td> <td><input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</td> </tr> <tr> <td><input type="checkbox"/> CME-55</td> <td><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</td> <td>CORE SIZE:</td> </tr> <tr> <td><input type="checkbox"/> CME-550</td> <td><input checked="" type="checkbox"/> 8" HOLLOW AUGERS</td> <td><input type="checkbox"/> -B <input type="checkbox"/> -H</td> </tr> <tr> <td><input type="checkbox"/> VANE SHEAR TEST</td> <td><input type="checkbox"/> HARD FACED FINGER BITS</td> <td><input type="checkbox"/> -N</td> </tr> <tr> <td><input type="checkbox"/> PORTABLE HOIST</td> <td><input type="checkbox"/> TUNG-CARBIDE INSERTS</td> <td>HAND TOOLS:</td> </tr> <tr> <td><input checked="" type="checkbox"/> D-25</td> <td><input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER</td> <td><input type="checkbox"/> POST HOLE DIGGER</td> </tr> <tr> <td><input checked="" type="checkbox"/> CME-45B</td> <td><input checked="" type="checkbox"/> TRICONE <input type="checkbox"/> 2 1/16" STEEL TEETH</td> <td><input type="checkbox"/> HAND AUGER</td> </tr> <tr> <td></td> <td><input type="checkbox"/> TRICONE <input type="checkbox"/> TUNG-CARB.</td> <td><input type="checkbox"/> SOUNDING ROD</td> </tr> <tr> <td></td> <td><input type="checkbox"/> CORE BIT</td> <td><input type="checkbox"/> VANE SHEAR TEST</td> </tr> <tr> <td></td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table>				EQUIPMENT USED ON SUBJECT PROJECT			DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:	<input type="checkbox"/> CME-45C	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL	<input type="checkbox"/> CME-55	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE:	<input type="checkbox"/> CME-550	<input checked="" type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> -B <input type="checkbox"/> -H	<input type="checkbox"/> VANE SHEAR TEST	<input type="checkbox"/> HARD FACED FINGER BITS	<input type="checkbox"/> -N	<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS	HAND TOOLS:	<input checked="" type="checkbox"/> D-25	<input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	<input type="checkbox"/> POST HOLE DIGGER	<input checked="" type="checkbox"/> CME-45B	<input checked="" type="checkbox"/> TRICONE <input type="checkbox"/> 2 1/16" STEEL TEETH	<input type="checkbox"/> HAND AUGER		<input type="checkbox"/> TRICONE <input type="checkbox"/> TUNG-CARB.	<input type="checkbox"/> SOUNDING ROD		<input type="checkbox"/> CORE BIT	<input type="checkbox"/> VANE SHEAR TEST		<input type="checkbox"/>	<input type="checkbox"/>																																																																																																																																																																																																																																																																																																																																																																																											
EQUIPMENT USED ON SUBJECT PROJECT																																																																																																																																																																																																																																																																																																																																																																																																																																		
DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:																																																																																																																																																																																																																																																																																																																																																																																																																																
<input type="checkbox"/> CME-45C	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL																																																																																																																																																																																																																																																																																																																																																																																																																																
<input type="checkbox"/> CME-55	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE:																																																																																																																																																																																																																																																																																																																																																																																																																																
<input type="checkbox"/> CME-550	<input checked="" type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> -B <input type="checkbox"/> -H																																																																																																																																																																																																																																																																																																																																																																																																																																
<input type="checkbox"/> VANE SHEAR TEST	<input type="checkbox"/> HARD FACED FINGER BITS	<input type="checkbox"/> -N																																																																																																																																																																																																																																																																																																																																																																																																																																
<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS	HAND TOOLS:																																																																																																																																																																																																																																																																																																																																																																																																																																
<input checked="" type="checkbox"/> D-25	<input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	<input type="checkbox"/> POST HOLE DIGGER																																																																																																																																																																																																																																																																																																																																																																																																																																
<input checked="" type="checkbox"/> CME-45B	<input checked="" type="checkbox"/> TRICONE <input type="checkbox"/> 2 1/16" STEEL TEETH	<input type="checkbox"/> HAND AUGER																																																																																																																																																																																																																																																																																																																																																																																																																																
	<input type="checkbox"/> TRICONE <input type="checkbox"/> TUNG-CARB.	<input type="checkbox"/> SOUNDING ROD																																																																																																																																																																																																																																																																																																																																																																																																																																
	<input type="checkbox"/> CORE BIT	<input type="checkbox"/> VANE SHEAR TEST																																																																																																																																																																																																																																																																																																																																																																																																																																
	<input type="checkbox"/>	<input type="checkbox"/>																																																																																																																																																																																																																																																																																																																																																																																																																																
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">RECOMMENDATION SYMBOLS</th> </tr> <tr> <td></td> <td>UNDERCUT</td> </tr> <tr> <td></td> <td>SHALLOW UNDERCUT</td> </tr> <tr> <td></td> <td>UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE</td> </tr> <tr> <td></td> <td>UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK</td> </tr> </table>				RECOMMENDATION SYMBOLS			UNDERCUT		SHALLOW UNDERCUT		UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE		UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK																																																																																																																																																																																																																																																																																																																																																																																																																					
RECOMMENDATION SYMBOLS																																																																																																																																																																																																																																																																																																																																																																																																																																		
	UNDERCUT																																																																																																																																																																																																																																																																																																																																																																																																																																	
	SHALLOW UNDERCUT																																																																																																																																																																																																																																																																																																																																																																																																																																	
	UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE																																																																																																																																																																																																																																																																																																																																																																																																																																	
	UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK																																																																																																																																																																																																																																																																																																																																																																																																																																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="3">ABBREVIATIONS</th> </tr> <tr> <td>AR - AUGER REFUSAL</td> <td>MED. - MEDIUM MICA - MICACEOUS</td> <td>VST - VANE SHEAR TEST</td> </tr> <tr> <td>BT - BORING TERMINATED</td> <td>MOD. - MODERATELY NP - NON PLASTIC</td> <td>WEA. - WEATHERED</td> </tr> <tr> <td>CL - CLAY</td> <td>ORG. - ORGANIC</td> <td>UW - UNIT WEIGHT</td> </tr> <tr> <td>CPT - CONE PENETRATION TEST</td> <td>PMT - PRESSUREMETER TEST</td> <td>UDW - DRY UNIT WEIGHT</td> </tr> <tr> <td>CSE - COARSE</td> <td>SAP. - SAPROLITIC</td> <td>SAMPLE ABBREVIATIONS</td> </tr> <tr> <td>DMT - DILATOMETER TEST</td> <td>SD. - SAND, SANDY</td> <td>S - BULK</td> </tr> <tr> <td>DPT - DYNAMIC PENETRATION TEST</td> <td>SL. - SILTY, SILTY</td> <td>SS - SPLIT SPOON</td> </tr> <tr> <td>e - VOID RATIO</td> <td>SLI. - SLIGHTLY</td> <td>ST - SHELBY TUBE</td> </tr> <tr> <td>F - FINE</td> <td>TCR - TRICONE REFUSAL</td> <td>RS - ROCK</td> </tr> <tr> <td>FOSS. - FOSSILIFEROUS</td> <td>w - MOISTURE CONTENT</td> <td>RT - RECOMPACTED TRIAXIAL</td> </tr> <tr> <td>FRAC. - FRACTURED, FRACTURES</td> <td></td> <td>CBR - CALIFORNIA BEARING RATIO</td> </tr> <tr> <td>FRAGS. - FRAGMENTS</td> <td></td> <td></td> </tr> <tr> <td>HI. - HIGHLY</td> <td></td> <td></td> </tr> </table>				ABBREVIATIONS			AR - AUGER REFUSAL	MED. - MEDIUM MICA - MICACEOUS	VST - VANE SHEAR TEST	BT - BORING TERMINATED	MOD. - MODERATELY NP - NON PLASTIC	WEA. - WEATHERED	CL - CLAY	ORG. - ORGANIC	UW - UNIT WEIGHT	CPT - CONE PENETRATION TEST	PMT - PRESSUREMETER TEST	UDW - DRY UNIT WEIGHT	CSE - COARSE	SAP. - SAPROLITIC	SAMPLE ABBREVIATIONS	DMT - DILATOMETER TEST	SD. - SAND, SANDY	S - BULK	DPT - DYNAMIC PENETRATION TEST	SL. - SILTY, SILTY	SS - SPLIT SPOON	e - VOID RATIO	SLI. - SLIGHTLY	ST - SHELBY TUBE	F - FINE	TCR - TRICONE REFUSAL	RS - ROCK	FOSS. - FOSSILIFEROUS	w - MOISTURE CONTENT	RT - RECOMPACTED TRIAXIAL	FRAC. - FRACTURED, FRACTURES		CBR - CALIFORNIA BEARING RATIO	FRAGS. - FRAGMENTS			HI. - HIGHLY																																																																																																																																																																																																																																																																																																																																																																																							
ABBREVIATIONS																																																																																																																																																																																																																																																																																																																																																																																																																																		
AR - AUGER REFUSAL	MED. - MEDIUM MICA - MICACEOUS	VST - VANE SHEAR TEST																																																																																																																																																																																																																																																																																																																																																																																																																																
BT - BORING TERMINATED	MOD. - MODERATELY NP - NON PLASTIC	WEA. - WEATHERED																																																																																																																																																																																																																																																																																																																																																																																																																																
CL - CLAY	ORG. - ORGANIC	UW - UNIT WEIGHT																																																																																																																																																																																																																																																																																																																																																																																																																																
CPT - CONE PENETRATION TEST	PMT - PRESSUREMETER TEST	UDW - DRY UNIT WEIGHT																																																																																																																																																																																																																																																																																																																																																																																																																																
CSE - COARSE	SAP. - SAPROLITIC	SAMPLE ABBREVIATIONS																																																																																																																																																																																																																																																																																																																																																																																																																																
DMT - DILATOMETER TEST	SD. - SAND, SANDY	S - BULK																																																																																																																																																																																																																																																																																																																																																																																																																																
DPT - DYNAMIC PENETRATION TEST	SL. - SILTY, SILTY	SS - SPLIT SPOON																																																																																																																																																																																																																																																																																																																																																																																																																																
e - VOID RATIO	SLI. - SLIGHTLY	ST - SHELBY TUBE																																																																																																																																																																																																																																																																																																																																																																																																																																
F - FINE	TCR - TRICONE REFUSAL	RS - ROCK																																																																																																																																																																																																																																																																																																																																																																																																																																
FOSS. - FOSSILIFEROUS	w - MOISTURE CONTENT	RT - RECOMPACTED TRIAXIAL																																																																																																																																																																																																																																																																																																																																																																																																																																
FRAC. - FRACTURED, FRACTURES		CBR - CALIFORNIA BEARING RATIO																																																																																																																																																																																																																																																																																																																																																																																																																																
FRAGS. - FRAGMENTS																																																																																																																																																																																																																																																																																																																																																																																																																																		
HI. - HIGHLY																																																																																																																																																																																																																																																																																																																																																																																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">ROCK HARDNESS</th> </tr> <tr> <td>VERY HARD</td> <td>CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.</td> </tr> <tr> <td>HARD</td> <td>CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.</td> </tr> <tr> <td>MODERATELY HARD</td> <td>CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.</td> </tr> <tr> <td>MEDIUM HARD</td> <td>CAN BE GROUDED OR GOUGED 0.25 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.</td> </tr> <tr> <td>SOFT</td> <td>CAN BE GROUDED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.</td> </tr> <tr> <td>VERY SOFT</td> <td>CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.</td> </tr> </table>				ROCK HARDNESS		VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.	HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.	MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.	MEDIUM HARD	CAN BE GROUDED OR GOUGED 0.25 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.	SOFT	CAN BE GROUDED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.	VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.																																																																																																																																																																																																																																																																																																																																																																																																																	
ROCK HARDNESS																																																																																																																																																																																																																																																																																																																																																																																																																																		
VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.																																																																																																																																																																																																																																																																																																																																																																																																																																	
HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.																																																																																																																																																																																																																																																																																																																																																																																																																																	
MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.																																																																																																																																																																																																																																																																																																																																																																																																																																	
MEDIUM HARD	CAN BE GROUDED OR GOUGED 0.25 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.																																																																																																																																																																																																																																																																																																																																																																																																																																	
SOFT	CAN BE GROUDED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.																																																																																																																																																																																																																																																																																																																																																																																																																																	
VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.																																																																																																																																																																																																																																																																																																																																																																																																																																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">FRACTURE SPACING</th> <th colspan="2">BEDDING</th> </tr> <tr> <td>TERM</td> <td>SPACING</td> <td>TERM</td> <td>THICKNESS</td> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> <td>VERY THICKLY BEDDED</td> <td>4 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FOOT</td> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td></td> <td></td> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> </tr> </table>				FRACTURE SPACING		BEDDING		TERM	SPACING	TERM	THICKNESS	VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET	WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET	MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET	CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET	VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET			THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																																																																																																																																																																																																																															
FRACTURE SPACING		BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																
TERM	SPACING	TERM	THICKNESS																																																																																																																																																																																																																																																																																																																																																																																																																															
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET																																																																																																																																																																																																																																																																																																																																																																																																																															
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET																																																																																																																																																																																																																																																																																																																																																																																																																															
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET																																																																																																																																																																																																																																																																																																																																																																																																																															
CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET																																																																																																																																																																																																																																																																																																																																																																																																																															
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET																																																																																																																																																																																																																																																																																																																																																																																																																															
		THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																																																																																																																																																																																																																																																															
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">INDURATION</th> </tr> <tr> <td>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</td> <td></td> </tr> <tr> <td>FRIABLE</td> <td>RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</td> </tr> <tr> <td>MODERATELY INDURATED</td> <td>GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</td> </tr> <tr> <td>INDURATED</td> <td>GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</td> </tr> <tr> <td>EXTREMELY INDURATED</td> <td>SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</td> </tr> </table>				INDURATION		FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.		FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.	MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.	INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.	EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																																																																																																																																																																																																																																																																																																																																																																																																																			
INDURATION																																																																																																																																																																																																																																																																																																																																																																																																																																		
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.																																																																																																																																																																																																																																																																																																																																																																																																																																		
FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.																																																																																																																																																																																																																																																																																																																																																																																																																																	
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.																																																																																																																																																																																																																																																																																																																																																																																																																																	
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.																																																																																																																																																																																																																																																																																																																																																																																																																																	
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																																																																																																																																																																																																																																																																																																																																																																																																																																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2" style="text-align: center;">BENCH MARK: N/A</td> <td colspan="2" style="text-align: center;">ELEVATION: N/A FEET</td> </tr> <tr> <td colspan="4"> <p>NOTES: BORING LOCATIONS AND ELEVATIONS OBTAINED FROM MCKIM & CREED, INC. - 6/28/18</p> <p>UCP - UNDIVIDED COASTAL PLAIN FIAD - FILLED IMMEDIATELY AFTER DRILLING</p> </td> </tr> </table>				BENCH MARK: N/A		ELEVATION: N/A FEET		<p>NOTES: BORING LOCATIONS AND ELEVATIONS OBTAINED FROM MCKIM & CREED, INC. - 6/28/18</p> <p>UCP - UNDIVIDED COASTAL PLAIN FIAD - FILLED IMMEDIATELY AFTER DRILLING</p>																																																																																																																																																																																																																																																																																																																																																																																																																										
BENCH MARK: N/A		ELEVATION: N/A FEET																																																																																																																																																																																																																																																																																																																																																																																																																																
<p>NOTES: BORING LOCATIONS AND ELEVATIONS OBTAINED FROM MCKIM & CREED, INC. - 6/28/18</p> <p>UCP - UNDIVIDED COASTAL PLAIN FIAD - FILLED IMMEDIATELY AFTER DRILLING</p>																																																																																																																																																																																																																																																																																																																																																																																																																																		

PROJECT REFERENCE NO.	SHEET NO.
R-1015	3
SITE PLAN	


SKEW = 90°





MATCH LINE STA 170+000 SEE SHEET 4

SEE SHEETS 6-9 FOR PROFILE -L-

SITE PLAN




SKREW = 90°



SEE SHEETS 6-9 FOR PROFILE -L-

PROJECT REFERENCE NO.	SHEET NO.
R-1015	5
SITE PLAN	
 0 100 200 FEET	

SKEW = 90°



185

190

195

← TO MOREHEAD CITY

MATCH LINE STA 184+00 SEE SHEET 4

ALLUVIAL SOILS

BII-A LL

EB2-A LL

WOODS

WOODS

-L-

N 63°29'33.7"W

BII-B RL

EB2-B RL


WOODS

WOODS

ALLUVIAL SOILS


TO NEW BERN →

SEE SHEETS 6-9 FOR PROFILE -L-




PROJECT REFERENCE NO.	SHEET NO.
R-1015	6
PROFILE - BRIDGE NO. 276 BORINGS PROJECTED ONTO -L-	

NOTES:
 1. BORINGS AND INFERRED STRATIGRAPHY ARE PROJECTED ONTO -L-
 2. GROUNDLINE TAKEN FROM ROADWAY DESIGN FILE DATED 1-30-2018




- (A) ALLUVIAL: Very soft, dark brown, MUCK, contains wood fragments, wet
- (B) ALLUVIAL: Very loose to loose, dark brown, SAND (A-2-4), contains moderate organics, moist
- (C) UCP: Very loose to loose, brown, tan, orange and gray, SAND and clayey SAND (A-2-4, A-2-6, A-3), contains wood fragments, moist to saturated
- (D) UCP: Very soft to soft, green, tan, orange and gray, SILT and sandy CLAY (A-4, A-6), wet

- (E) COASTAL PLAIN: Very soft, gray, sandy SILT and CLAY (A-4, A-7-6), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Very loose to dense, gray and green, SAND, and clayey SAND (A-2-6, A-2-4, A-3), contains shell fragments, phosphatic, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Very soft to medium stiff, gray and green, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Very loose to very dense, gray, green and tan, SAND (A-2-4, A-2-6, A-3, A-1-b), phosphatic, contains shell and limestone fragments, saturated (RIVER BEND FORMATION)
- (I) COASTAL PLAIN: Stiff to hard, gray and green, sandy SILT (A-4), contains shell fragments, wet (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray and brown, poorly indurated, moderately hard, LIMESTONE (RIVER BEND FORMATION)



PROJECT REFERENCE NO.	SHEET NO.
R-1015	7
PROFILE - BRIDGE NO. 276 BORINGS PROJECTED ONTO -L-	


NOTES:
 1. BORINGS AND INFERRED STRATIGRAPHY ARE PROJECTED ONTO -L-
 2. GROUNDLINE TAKEN FROM ROADWAY DESIGN FILE DATED 1-30-2018




- (B) ALLUVIAL: Very loose, brown, SAND (A-2-4), contains trace to moderate organics, moist
- (C) UCP: Loose, gray and orange, SAND (A-2-4, A-3), with trace clay saturated
- (E) COASTAL PLAIN: Very soft to soft, gray, silty and sandy CLAY (A-6, A-7-6), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Very loose to dense, gray and green, SAND (A-2-4, A-3), contains shell fragments, phosphatic, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Soft to medium stiff, gray and green, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Medium dense to very dense, gray, green and tan, SAND (A-2-4, A-3, A-1-b), phosphatic, contains shell and limestone fragments, saturated (RIVER BEND FORMATION)

NOTES:

1. BORINGS AND INFERRED STRATIGRAPHY ARE PROJECTED ONTO -L-
2. GROUNDLINE TAKEN FROM ROADWAY DESIGN FILE DATED T-30-2018




PROJECT REFERENCE NO.	SHEET NO.
R-1015	8
PROFILE - BRIDGE NO. 277	
BORINGS PROJECTED ONTO -L-	




- (A) **ALLUVIAL:** Very soft to soft, dark brown, MUCK, contains wood fragments, moist to wet.
- (B) **ALLUVIAL:** Very loose to loose, dark brown, SAND (A-2-4), contains moderate organics, saturated.
- (C) **UCP:** Very loose to loose, brown, tan, orange and gray, SAND, and clayey SAND (A-2-4, A-2-6, A-3), contains wood fragments, moist to saturated.
- (D) **UCP:** Medium stiff, tan, orange and gray, sandy CLAY (A-6), wet.
- (E) **COASTAL PLAIN:** Very soft to medium stiff, gray, sandy SILT and CLAY (A-4, A-6, A-7-6), wet (DUPLIN FORMATION).

- (F) **COASTAL PLAIN:** Very loose to dense, gray and green, SAND and clayey SAND (A-2-4, A-3), contains shell fragments, phosphatic, saturated (DUPLIN FORMATION).
- (G) **COASTAL PLAIN:** Soft to medium stiff, gray and green, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION).
- (H) **COASTAL PLAIN:** Very loose to very dense, gray, green and tan, SAND (A-2-4, A-2-6, A-3, A-1-b), phosphatic, contains shell and limestone fragments, saturated (RIVER BEND FORMATION).
- (I) **COASTAL PLAIN:** Medium stiff to very stiff, gray and green, sandy SILT and CLAY (A-4, A-6), wet (RIVER BEND FORMATION).
- (J) **COASTAL PLAIN:** Gray and brown, poorly indurated, moderately hard, LIMESTONE (RIVER BEND FORMATION).



PROJECT REFERENCE NO.	SHEET NO.
R-1015	9
PROFILE - BRIDGE NO. 277	
BORINGS PROJECTED ONTO -L-	


NOTES:
 1. BORINGS AND INFERRED STRATIGRAPHY ARE PROJECTED ONTO -L-
 2. GROUNDLINE TAKEN FROM ROADWAY DESIGN FILE DATED 1-30-2018



- (B) ALLUVIAL: Very loose, brown, SAND (A-2-4), contains trace organics, moist
- (C) UCP: Loose, gray, tan and orange, SAND (A-2-4), with trace clay, contains trace organics, saturated
- (E) COASTAL PLAIN: Very soft to medium stiff, green and gray, sandy SILT and CLAY (A-4, A-6, A-7-6), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Very loose to medium dense, gray and green, SAND (A-2-4, A-3), contains shell fragments, phosphatic, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Very soft to medium stiff, gray and green, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to very dense, gray, green and tan, SAND (A-2-4, A-3), phosphatic, contains shell and limestone fragments, saturated. (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray, moderately hard, sandy LIMESTONE (RIVER BEND FORMATION)

NOTE: INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE SECTION


- (C) UCP: Very loose to loose, tan, orange and light gray, SAND and clayey SAND (A-2-4, A-2-6), moist to saturated
- (D) UCP: Medium stiff, gray and orange, fine sandy and silty CLAY (A-6), moist to wet
- (E) COASTAL PLAIN: Very soft, gray, sandy CLAY (A-6), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Loose to dense, gray, brown and tan, fine to coarse SAND (A-2-4, A-3), with silt and clay interbeds, contains shell fragments, saturated (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to very dense, tan and gray, SAND (A-2-4, A-2-6), contains cemented shell fragments, saturated (RIVER BEND FORMATION)



HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - END BENT 1
-L- STA 169+55.33

- (A) ALLUVIAL: Very soft, dark brown, MUCK, moist
- (C) UCP: Very loose to loose, gray and tan, clayey and silty SAND (A-3, A-2-4), contains wood fragments, moist to saturated
- (F) COASTAL PLAIN: Very loose to dense, gray, tan and brown, SAND and clayey SAND (A-2-6, A-2-4, A-3), phosphatic, contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Very soft to medium stiff, green and gray, CLAY and sandy CLAY (A-6, A-7-6), micaceous, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to very dense, tan and gray, fine to coarse SAND (A-2-4, A-3), with trace silt and clay, contains shell fragments, saturated (RIVER BEND FORMATION)




HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 1
-L- STA 170+91.50

NOTE: CROSS SECTIONS
CREATED FROM
r1015-Ls_tin.tin FILE
DATED 1-30-2018
90° SKEW


- (A) ALLUVIAL: Very soft, dark brown, MUCK, wet
- (C) UCP: Very loose, brown, gray and tan, SAND (A-3), contains wood fragments, saturated
- (E) COASTAL PLAIN: Medium stiff, gray and green, silty CLAY (A-7-6), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Loose to dense, gray and brown, SAND (A-2-4, A-3), phosphatic, contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Soft to stiff, gray, sandy CLAY (A-6), wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to medium dense, green and gray, SAND (A-1-b, A-2-4, A-3), saturated (RIVER BEND FORMATION)
- (I) COASTAL PLAIN: Medium stiff to very stiff, gray and green, SILT and sandy CLAY (A-4, A-6), wet (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray, sandy, moderately hard, LIMESTONE (RIVER BEND FORMATION)

- (A) ALLUVIAL: Soft to stiff, dark brown, MUCK, contains wood fragments, moist to wet
- (C) UCP: Very loose, tan, SAND (A-3), contains wood fragments, saturated
- (F) COASTAL PLAIN: Loose to medium dense, gray and green, SAND (A-2-4, A-3), phosphatic, contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Medium stiff, gray and green, sandy CLAY (A-6), contains shell fragments (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Very loose to dense, gray and green, SAND (A-1-b, A-2-4, A-3), contains shell and limestone fragments, saturated (RIVER BEND FORMATION)
- (I) COASTAL PLAIN: Stiff, gray and green, sandy SILT (A-4), contains shell fragments, wet (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray, sandy, moderately hard, LIMESTONE (RIVER BEND FORMATION)



HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 2
-L- STA 172+26+75




HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 3
-L- STA 173+61+75

NOTE: INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE SECTION


- (A) ALLUVIAL: Very soft, dark brown, MUCK, wet
- (C) UCP: Loose, tan and brown, SAND (A-2-4, A-3), contains wood fragments, saturated
- (F) COASTAL PLAIN: Very loose to medium dense, gray and green, SAND (A-2-4, A-3), contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Soft to medium stiff, gray and green, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to dense, gray and green, SAND (A-2-4, A-3, A-1-b), with trace clay, contains shell and limestone fragments, saturated (RIVER BEND FORMATION)
- (I) COASTAL PLAIN: Stiff to hard, green, sandy SILT and sandy CLAY (A-4, A-6), contains shell fragments, wet (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Brown and gray, moderately hard, LIMESTONE (RIVER BEND FORMATION)

- (A) ALLUVIAL: Very soft, dark brown, MUCK, wet
- (C) UCP: Loose to medium dense, tan, SAND (A-3), contains wood fragments, saturated
- (D) UCP: Very soft, green, SILT (A-4), wet
- (F) COASTAL PLAIN: Loose to medium dense, gray and green, SAND (A-3), contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Medium stiff, gray and green, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, saturated (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Very loose to dense, gray and green, SAND (A-2-4, A-3, A-1-b), with trace clay, contains shell and limestone fragments, saturated (RIVER BEND FORMATION)
- (I) COASTAL PLAIN: Stiff, gray and green, sandy SILT (A-4), wet (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray and brown, moderately hard, LIMESTONE (RIVER BEND FORMATION)



HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 4
-L- STA 174+96.75





HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 5
-L- STA 176+32.00

NOTE: CROSS SECTIONS
CREATED FROM
r1015_Ls_tin.tin FILE
DATED 1-30-2018
90° SKEW

- (A) ALLUVIAL: Very soft, brown, MUCK, wet
- (B) ALLUVIAL: Loose, dark brown, SAND (A-2-4), moist to saturated
- (C) UCP: Loose, gray and tan, SAND (A-2-4), saturated
- (D) UCP: Soft, tan, orange and gray, fine sandy, silty CLAY (A-6), wet
- (E) COASTAL PLAIN: Very loose to medium dense, gray, SAND and clayey SAND (A-2-6, A-2-4, A-3), phosphatic, contains shell fragments, saturated (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Loose to medium dense, gray and green, SAND (A-3), contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Medium stiff, green and gray, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to very dense, gray, green and tan, SAND (A-2-6, A-2-4, A-3, A-1-b), contains shell and limestone fragments, saturated (RIVER BEND FORMATION)
- (I) COASTAL PLAIN: Stiff to hard, gray and green, sandy SILT (A-4), contains shell fragments, wet (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray, sandy, moderately hard, LIMESTONE (RIVER BEND FORMATION)

- (B) ALLUVIAL: Very loose, brown and gray, SAND (A-2-4), moist
- (C) UCP: Very loose to loose, tan and orange, SAND and clayey SAND (A-2-4, A-2-6), saturated
- (E) COASTAL PLAIN: Very soft, gray, sandy SILT (A-4), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Loose to medium dense, gray and green, SAND (A-3), contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Soft to medium stiff, gray, sandy CLAY (A-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Medium dense to very dense, gray, SAND (A-3, A-1-b, A-2-4), phosphatic, contains shell fragments, saturated (RIVER BEND FORMATION)
- (I) COASTAL PLAIN: Stiff to very stiff green, sandy SILT (A-4), contains shell fragments, wet (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray, poorly indurated, moderately hard, LIMESTONE (RIVER BEND FORMATION)




HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 6
-L- STA 177+67.00

HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 7
-L- STA 179+02.00


- (A) ALLUVIAL: Very soft, dark brown, MUCK, moist
- (B) ALLUVIAL: Very loose, dark brown, SAND (A-2-4), contains moderate organics, moist
- (C) UCP: Very loose, brown, tan and orange, clayey SAND (A-2-6), saturated
- (E) COASTAL PLAIN: Very soft, gray, sandy and silty CLAY (A-6, A-7-6), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Very loose to dense, gray, SAND (A-2-4, A-3) with clay interbeds, phosphatic, contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Very soft to medium stiff, gray, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to very dense, gray and green, SAND and clayey SAND (A-1-b, A-2-6, A-2-4, A-3), phosphatic, contains shell and limestone fragments, saturated (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray, moderately hard, LIMESTONE (RIVER BEND FORMATION)



HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 8
-L- STA 180+37.25


- (B) ALLUVIAL: Very loose, dark brown, SAND (A-2-4), contains moderate organics, moist
- (C) UCP: Very loose, gray, tan and orange, SAND (A-3, A-2-4), saturated
- (E) COASTAL PLAIN: Very soft, gray, SILT, CLAY and sandy CLAY (A-4, A-6, A-7-6), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Very loose to medium dense, gray, SAND (A-3) contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Soft to medium stiff, gray, CLAY and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to very dense, gray and green, SAND and silty to clayey SAND (A-2-6, A-2-4, A-3), phosphatic, contains shell fragments (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray, moderately hard, LIMESTONE (RIVER BEND FORMATION)



HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 9
-L- 181+72.25


- (B) ALLUVIAL: Very loose, brown, silty SAND (A-2-4), contains trace organics, moist
- (C) UCP: Loose, gray, SAND and silty SAND (A-3, A-2-4), saturated
- (E) COASTAL PLAIN: Very soft to medium stiff, gray, sandy and silty CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Very loose to dense, gray, SAND (A-3), with trace clay, contains shell fragments, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Soft to stiff, gray, silty and sandy CLAY (A-6, A-7-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to very dense, gray and green, SAND (A-2-4, A-3, A-1-b), contains shell fragments, saturated (RIVER BEND FORMATION)
- (J) COASTAL PLAIN: Gray, moderately hard, LIMESTONE (RIVER BEND FORMATION)



HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 10
-L- STA 183+07.25

- (B) ALLUVIAL: Very loose, dark brown, silty and clayey SAND (A-2-4), moist
- (C) UCP: Loose, gray and orange, SAND (A-2-4), with trace clay, saturated
- (E) COASTAL PLAIN: Very soft to soft, gray, clay and sandy CLAY (A-6, A-7-6), wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Loose to medium dense, gray, SAND (A-2-4, A-3), with trace clay, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Very soft to medium stiff, sandy CLAY (A-6), contains shell fragments, wet (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Medium dense to very dense, gray, tan and green, SAND (A-2-4, A-3), contains shell and limestone fragments, saturated (RIVER BEND FORMATION)




HORIZ. SCALE 0 50 100 (FEET) VE = 2.5

CROSS SECTION - BENT 11
-L- STA 184+42.50

90° SKEW


NOTE: INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE SECTION

- (B) ALLUVIAL: Very loose, brown, silty SAND (A-2-4), some moderately organic, moist
- (C) UCP: Loose, gray, tan and orange, SAND (A-2-4), with silt and clay, some with trace organics, saturated
- (E) COASTAL PLAIN: Very soft to medium stiff, gray, CLAY (A-6, A-7-6), with fine sand and silt, wet (DUPLIN FORMATION)
- (F) COASTAL PLAIN: Very loose to medium dense, gray, SAND (A-2-4, A-3), with trace clay, saturated (DUPLIN FORMATION)
- (G) COASTAL PLAIN: Soft to medium stiff, gray, silty and sandy CLAY (A-6, A-7-6), contains shell fragments (DUPLIN FORMATION)
- (H) COASTAL PLAIN: Loose to very dense, green and gray, silty SAND (A-2-4, A-3), phosphatic, contains shell fragments, saturated (RIVER BEND FORMATION)



NOTE: INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE SECTION

NOTE: CROSS SECTIONS CREATED FROM r1015 Ls tin.tin FILE DATED 1-30-2018 90° SKEW



VE = 2.5

CROSS SECTION - END BENT 2
-L- STA 185+78.67

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Johnson, M.									
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. EB1-A LL		STATION 169+52		OFFSET 60 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 18.8 ft		TOTAL DEPTH 120.1 ft		NORTHING 409,756		EASTING 2,625,695									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Fowler, B.		START DATE 04/10/18		COMP. DATE 04/10/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
30															
25															
20	18.8	0.0	1	1	2	3									
15	15.2	3.6	5	5	4	9									
10	10.2	8.6	2	1	1	2									
5	5.2	13.6	1	2	3	5									
0	0.2	18.6	3	3	7	10									
-5	-4.8	23.6	9	8	9	17									
-10	-9.8	28.6	4	6	5	11									
-15	-14.8	33.6	7	7	7	14									
-20	-19.8	38.6	8	6	7	13									
-25	-24.8	43.6	6	7	9	16									
-30	-29.8	48.6	9	11	16	27									
-35	-34.8	53.6	8	12	15	27									
-40	-39.8	58.6	6	10	11	21									
-45	-44.8	63.6	9	11	14	25									
-50	-49.8	68.6													

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Johnson, M.									
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. EB1-A LL		STATION 169+52		OFFSET 60 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 18.8 ft		TOTAL DEPTH 120.1 ft		NORTHING 409,756		EASTING 2,625,695									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Fowler, B.		START DATE 04/10/18		COMP. DATE 04/10/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-50															
-55	-54.8	73.6	13	17	22	20									
-60	-59.8	78.6	7	5	6	11									
-65	-64.8	83.6	13	21	27	48									
-70	-69.8	88.6	8	12	19	31									
-75	-74.8	93.6	9	9	7	16									
-80	-79.8	98.6	8	13	20	33									
-85	-84.8	103.6	15	21	32	53									
-90	-89.8	108.6	17	20	27	47									
-95	-94.8	113.6	14	23	36	59									
-100	-99.8	118.6	8	12	17	29									

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Johnson, M.	
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)
BORING NO. EB1-B RL		STATION 169+51		OFFSET 63 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 21.0 ft		TOTAL DEPTH 119.8 ft		NORTHING 409,866		EASTING 2,625,752	
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic	
DRILLER Fowler, B.		START DATE 04/11/18		COMP. DATE 04/11/18		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
30																
25																
20	21.0	0.0	2	2	1										21.0	0.0
	17.7	3.3	2	3	3										18.0	3.0
15																
	12.7	8.3	WOH	2	3										12.3	8.7
10																
	7.7	13.3	1	2	2											
5																
	2.7	18.3	1	0	1										5.0	16.0
0																
	-2.3	23.3	4	3	4										0.0	21.0
-5																
	-7.3	28.3	4	6	7											
-10																
	-12.3	33.3	4	7	8											
-15																
	-17.3	38.3	8	7	8											
-20																
	-22.3	43.3	1	2	3											
-25																
	-27.3	48.3	7	7	14											
-30																
	-32.3	53.3	7	7	11											
-35																
	-37.3	58.3	8	11	17											
-40																
	-42.3	63.3	8	14	22											
-45																
	-47.3	68.3	9	13	14											
-50																

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Johnson, M.	
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)
BORING NO. EB1-B RL		STATION 169+51		OFFSET 63 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 21.0 ft		TOTAL DEPTH 119.8 ft		NORTHING 409,866		EASTING 2,625,752	
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic	
DRILLER Fowler, B.		START DATE 04/11/18		COMP. DATE 04/11/18		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
-50																
	-52.3	73.3	3	7	13											
-55																
	-57.3	78.3	10	16	20											
-60																
	-62.3	83.3	6	5	5											
-65																
	-67.3	88.3	6	6	10											
-70																
	-72.3	93.3	13	20	36											
-75																
	-77.3	98.3	4	4	4											
-80																
	-82.3	103.3	12	14	16											
-85																
	-87.3	108.3	11	17	24											
-90																
	-92.3	113.3	12	20	26											
-95																
	-97.3	118.3	10	13	23											

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18

76.0

97.0

102.0

119.8

Boring Terminated at Elevation -98.8 ft in SAND (River Bend Formation)

Drill chatter from 111.0' to 113.0'
Strata break in split spoon at a depth of 8.7'
ST 1 taken in offset boring at STA 169+54 58' RT

Other Samples:
ST-1 (4.5 - 6.5)


GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.									
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B1-A LL		STATION 170+73		OFFSET 43 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 13.7 ft		TOTAL DEPTH 119.3 ft		NORTHING 409,825		EASTING 2,625,595									
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017				DRILL METHOD Mud Rotary		HAMMER TYPE Automatic									
DRILLER Fowler, B.		START DATE 03/28/18		COMP. DATE 03/29/18		SURFACE WATER DEPTH 1.7ft									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
20															
15	13.7	0.0													
10	9.9	3.8	2	1	5										
5	5.9	7.8	2	1	2										
0	0.9	12.8	4	3	4										
-5	-4.1	17.8	3	5	6										
-10	-9.1	22.8	3	3	3										
-15	-14.1	27.8	5	4	5										
-20	-19.1	32.8	7	12	16										
-25	-24.1	37.8	7	9	14										
-30	-29.1	42.8	7	10	13										
-35	-34.1	47.8	7	8	11										
-40	-39.1	52.8	4	5	13										
-45	-44.1	57.8	7	11	14										
-50	-49.1	62.8	4	4	4										
-55	-54.1	67.8	8	12	16										
-60	-59.1	72.8	4	3	3										



WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.									
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B1-A LL		STATION 170+73		OFFSET 43 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 13.7 ft		TOTAL DEPTH 119.3 ft		NORTHING 409,825		EASTING 2,625,595									
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017				DRILL METHOD Mud Rotary		HAMMER TYPE Automatic									
DRILLER Fowler, B.		START DATE 03/28/18		COMP. DATE 03/29/18		SURFACE WATER DEPTH 1.7ft									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-60															
-65	-64.1	77.8	4	3	3										
-70	-69.1	82.8	2	2	4										
-75	-74.1	87.8	5	4	4										
-80	-79.1	92.8	12	14	22										
-85	-84.1	97.8	11	14	17										
-90	-89.1	102.8	9	12	13										
-95	-94.1	107.8	8	10	12										
-100	-99.1	112.8	7	9	12										
-105	-104.1	117.8	8	13	20										

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT

BORE LOG



NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18

GEOTECHNICAL BORING REPORT

BORE LOG


WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.	
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)
BORING NO. B2-A LL		STATION 172+47		OFFSET 66 ft LT		ALIGNMENT -L-	
COLLAR ELEV. 11.1 ft		TOTAL DEPTH 121.1 ft		NORTHING 409,882		EASTING 2,625,429	
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic	
DRILLER Fowler, B.		START DATE 03/28/18		COMP. DATE 03/28/18		SURFACE WATER DEPTH 0.6ft	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
15															
10	11.1	0.0													
5	6.1	5.0	2	1	2										
0	1.5	9.6	2	2	6										
-5	-3.5	14.6	4	6	7										
-10	-8.5	19.6	3	4	4										
-15	-13.5	24.6	2	1	3										
-20	-18.5	29.6	3	5	5										
-25	-23.5	34.6	5	8	9										
-30	-28.5	39.6	4	5	5										
-35	-33.5	44.6	4	4	3										
-40	-38.5	49.6	5	7	12										
-45	-43.5	54.6	4	4	5										
-50	-48.5	59.6	4	5	8										
-55	-53.5	64.6	5	11	14										
-60	-58.5	69.6	12	19	25										
-65	-63.5	74.6	4	5	6										

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.	
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)
BORING NO. B2-A LL		STATION 172+47		OFFSET 66 ft LT		ALIGNMENT -L-	
COLLAR ELEV. 11.1 ft		TOTAL DEPTH 121.1 ft		NORTHING 409,882		EASTING 2,625,429	
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic	
DRILLER Fowler, B.		START DATE 03/28/18		COMP. DATE 03/28/18		SURFACE WATER DEPTH 0.6ft	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-65															
-70	-68.5	79.6	7	10	13										
-75	-73.5	84.6	4	6	8										
-80	-78.5	89.6	5	4	7										
-85	-83.5	94.6	4	4	6										
-90	-88.5	99.6	9	10	13										
-95	-93.5	104.6	18	28	19										
-100	-98.5	109.6	13	20	14										
-105	-103.5	114.6	9	9	10										
-110	-108.5	119.6	12	11	14										

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B2-B RL		STATION 172+22		OFFSET 61 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 12.2 ft		TOTAL DEPTH 126.1 ft		NORTHING 409,985		EASTING 2,625,508									
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017				DRILL METHOD Mud Rotary		HAMMER TYPE Automatic									
DRILLER Fowler, B.		START DATE 03/13/18		COMP. DATE 03/15/18		SURFACE WATER DEPTH 0.9ft									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
15															
	12.2	0.0													
10			WOH	WOH	WOH										
	7.2	5.0													
5			1	2	2										
	2.6	9.6													
0			3	7	9										
	-2.4	14.6													
-5			4	4	4										
	-7.4	19.6													
-10			4	2	3										
	-12.4	24.6													
-15			3	6	6										
	-17.4	29.6													
-20			6	6	6										
	-22.4	34.6													
-25			7	12	14										
	-27.4	39.6													
-30			6	13	20										
	-32.4	44.6													
-35			8	11	15										
	-37.4	49.6													
-40			6	5	6										
	-42.4	54.6													
-45			7	13	14										
	-47.4	59.6													
-50			4	3	3										
	-52.4	64.6													
-55			1	2	1										
	-57.4	69.6													
-60			6	9	12										
	-62.4	74.6													
-65			8	8	16										

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B2-B RL		STATION 172+22		OFFSET 61 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 12.2 ft		TOTAL DEPTH 126.1 ft		NORTHING 409,985		EASTING 2,625,508									
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017				DRILL METHOD Mud Rotary		HAMMER TYPE Automatic									
DRILLER Fowler, B.		START DATE 03/13/18		COMP. DATE 03/15/18		SURFACE WATER DEPTH 0.9ft									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-65															
	-67.4	79.6													
-70			7	10	11										
	-72.4	84.6													
-75			8	9	9										
	-77.4	89.6													
-80			5	5	8										
	-82.4	94.6													
-85			4	5	9										
	-87.4	99.6													
-90			7	13	9										
	-95.0	107.2													
-95			2	2	4										
	-102.4	114.6													
-100			WOH	3	4										
	-107.4	119.6													
-105			2	2	3										
	-107.4	119.6													
-110			2	2	3										
	-112.4	124.6													
			2	5	4										

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.										
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)									
BORING NO. B3-A LL		STATION 173+67		OFFSET 69 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 12.0 ft		TOTAL DEPTH 119.9 ft		NORTHING 409,933		EASTING 2,625,320										
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER Fowler, B.		START DATE 03/27/18		COMP. DATE 03/27/18		SURFACE WATER DEPTH 2.5ft										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
15																
	12.0	0.0	2	7	4											
10	7.5	4.5	4	2	2											
5	3.6	8.4	WOH	2	4											
0	-1.4	13.4	5	5	5											
-5	-6.4	18.4	4	5	4											
-10	-11.4	23.4	6	5	7											
-15	-16.4	28.4	4	5	4											
-20	-21.4	33.4	3	3	3											
-25	-26.4	38.4	5	5	6											
-30	-31.4	43.4	5	4	4											
-35	-36.4	48.4	WOH	3	4											
-40	-41.4	53.4	3	5	8											
-45	-46.4	58.4	5	8	8											
-50	-51.4	63.4	5	7	8											
-55	-56.4	68.4	2	1	2											
-60	-61.4	73.4	2	2	3											
-65																

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.										
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)									
BORING NO. B3-A LL		STATION 173+67		OFFSET 69 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 12.0 ft		TOTAL DEPTH 119.9 ft		NORTHING 409,933		EASTING 2,625,320										
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER Fowler, B.		START DATE 03/27/18		COMP. DATE 03/27/18		SURFACE WATER DEPTH 2.5ft										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
-65																
	-66.4	78.4	2	3	5											
-70	-71.4	83.4	4	5	10											
-75	-76.4	88.4	5	4	8											
-80	-81.4	93.4	6	8	12											
-85	-86.4	98.4	7	7	13											
-90	-91.4	103.4	7	9	11											
-95	-96.4	108.4	5	9	12											
-100	-101.4	113.4	10	11	12											
-105	-106.4	118.4	23	11	19											

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.										
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)									
BORING NO. B3-B RL		STATION 174+02		OFFSET 50 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 12.5 ft		TOTAL DEPTH 119.9 ft		NORTHING 410,056		EASTING 2,625,342										
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER Fowler, B.		START DATE 03/15/18		COMP. DATE 03/16/18		SURFACE WATER DEPTH 3.4ft										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	L O G	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
15																
	12.5	0.0														
10	8.2	4.3	2	2	1											
5	4.1	8.4	1	3	5											
0	-0.9	13.4	3	5	6											
-5	-5.9	18.4	5	4	4											
-10	-10.9	23.4	4	3	5											
-15	-15.9	28.4	4	5	6											
-20	-20.9	33.4	3	2	2											
-25	-25.9	38.4	3	3	3											
-30	-30.9	43.4	5	4	4											
-35	-35.9	48.4	2	2	4											
-40	-40.9	53.4	4	4	7											
-45	-45.9	58.4	5	6	9											
-50	-50.9	63.4	7	9	12											
-55	-55.9	68.4	2	1	2											
-60	-60.9	73.4	2	1	3											
-65																

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.										
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)									
BORING NO. B3-B RL		STATION 174+02		OFFSET 50 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 12.5 ft		TOTAL DEPTH 119.9 ft		NORTHING 410,056		EASTING 2,625,342										
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER Fowler, B.		START DATE 03/15/18		COMP. DATE 03/16/18		SURFACE WATER DEPTH 3.4ft										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	L O G	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
-65	-65.9	78.4	11	10	11											
-70	-70.9	83.4	4	4	6											
-75	-75.9	88.4	4	4	6											
-80	-80.9	93.4	6	3	6											
-85	-85.9	98.4	10	9	8											
-90	-90.9	103.4	10	12	9											
-95	-95.9	108.4	4	8	23											
	-97.4	109.9	10	11	8											
-100	-100.9	113.4	7	11	9											
-105	-105.9	118.4	6	17	31											

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.										
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)									
BORING NO. B4-A LL		STATION 174+87		OFFSET 72 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 12.5 ft		TOTAL DEPTH 120.1 ft		NORTHING 409,984		EASTING 2,625,211										
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER Powell, B.		START DATE 03/23/18		COMP. DATE 03/26/18		SURFACE WATER DEPTH 1.2ft										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
20																
15																
10	12.5	0.0	WOH	WOH	WOH											
5	8.3	4.2	6	4	2											
0	3.9	8.6	1	2	3											
-5	-1.1	13.6	3	3	4											
-10	-6.1	18.6	3	4	5											
-15	-11.1	23.6	4	5	5											
-20	-16.1	28.6	5	4	4											
-25	-21.1	33.6	2	1	2											
-30	-26.1	38.6	4	2	2											
-35	-31.1	43.6	4	3	3											
-40	-36.1	48.6	3	4	5											
-45	-41.1	53.6	4	5	7											
-50	-46.1	58.6	8	7	4											
-55	-51.1	63.6	1	2	2											
-60	-56.1	68.6	4	4	3											



WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.										
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)									
BORING NO. B4-A LL		STATION 174+87		OFFSET 72 ft LT		ALIGNMENT -L-										
COLLAR ELEV. 12.5 ft		TOTAL DEPTH 120.1 ft		NORTHING 409,984		EASTING 2,625,211										
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER Powell, B.		START DATE 03/23/18		COMP. DATE 03/26/18		SURFACE WATER DEPTH 1.2ft										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
-60																
-65	-61.1	73.6	5	3	5											
-70	-66.1	78.6	85	100	0.1											
-75	-71.1	83.6	5	5	9											
-80	-76.1	88.6	7	5	7											
-85	-81.1	93.6	6	7	9											
-90	-86.1	98.6	7	7	8											
-95	-91.1	103.6	8	8	17											
-100	-96.1	108.6	12	11	15											
-105	-101.1	113.6	13	15	22											
-107.6	-106.1	118.6	13	14	19											

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18

GEOTECHNICAL BORING REPORT BORE LOG

WBS 34360.1.1	TIP R-1015	COUNTY CRAVEN	GEOLOGIST Crenshaw, J. K.
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)			GROUND WTR (ft)
BORING NO. B4-B RL	STATION 174+86	OFFSET 87 ft RT	ALIGNMENT -L-
COLLAR ELEV. 12.6 ft	TOTAL DEPTH 119.5 ft	NORTHING 410,126	EASTING 2,625,283
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Fowler, B.		START DATE 03/19/18	COMP. DATE 03/20/18
SURFACE WATER DEPTH 1.5ft			

WBS 34360.1.1	TIP R-1015	COUNTY CRAVEN	GEOLOGIST Crenshaw, J. K.
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)			GROUND WTR (ft)
BORING NO. B4-B RL	STATION 174+86	OFFSET 87 ft RT	ALIGNMENT -L-
COLLAR ELEV. 12.6 ft	TOTAL DEPTH 119.5 ft	NORTHING 410,126	EASTING 2,625,283
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Fowler, B.		START DATE 03/19/18	COMP. DATE 03/20/18
SURFACE WATER DEPTH 1.5ft			



NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.									
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B5-A LL		STATION 176+29		OFFSET 55 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 14.6 ft		TOTAL DEPTH 120.0 ft		NORTHING 410,063		EASTING 2,625,092									
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Fowler, B.		START DATE 03/21/18		COMP. DATE 03/22/18		SURFACE WATER DEPTH 0.2ft									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
20															
15	14.6	0.0	WOH	WOH	WOH										
10	10.3	4.3	6	6	4										
5	6.1	8.5	4	4	5										
0	1.1	13.5	2	4	6										
-5	-3.9	18.5	4	6	6										
-10	-8.9	23.5	4	7	8										
-15	-13.9	28.5	5	4	6										
-20	-18.9	33.5	4	6	4										
-25	-23.9	38.5	1	3	2										
-30	-28.9	43.5	3	2	3										
-35	-33.9	48.5	3	4	4										
-40	-38.9	53.5	5	5	5										
-45	-43.9	58.5	2	3	4										
-50	-48.9	63.5	2	1	0										
-55	-53.9	68.5	3	2	5										
-60	-58.9	73.5	3	4	7										

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J. K.									
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B5-A LL		STATION 176+29		OFFSET 55 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 14.6 ft		TOTAL DEPTH 120.0 ft		NORTHING 410,063		EASTING 2,625,092									
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Fowler, B.		START DATE 03/21/18		COMP. DATE 03/22/18		SURFACE WATER DEPTH 0.2ft									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-60															
-65	-63.9	78.5	4	14	40										
-70	-68.9	83.5	6	5	21										
-75	-73.9	88.5	10	5	8										
-80	-78.9	93.5	6	8	9										
-85	-83.9	98.5	6	9	11										
-90	-88.9	103.5	6	5	15										
-95	-93.9	108.5	8	8	10										
-100	-98.9	113.5	10	8	14										
-105	-103.9	118.5	24	17	21										

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT BORE LOG


WBS 34360.1.1	TIP R-1015	COUNTY CRAVEN	GEOLOGIST Crenshaw, J. K.
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)			GROUND WTR (ft)
BORING NO. B5-B RL	STATION 176+04	OFFSET 61 ft RT	ALIGNMENT -L-
COLLAR ELEV. 13.1 ft	TOTAL DEPTH 118.9 ft	NORTHING 410,156	EASTING 2,625,166
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Fowler, B.	START DATE 03/20/18	COMP. DATE 03/21/18	SURFACE WATER DEPTH 0.5ft

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
15															
	13.1	0.0													
			WOH	WOH	WOH										
10	9.6	3.5	6	6	4										
5	5.7	7.4	3	3	5										
0	0.7	12.4	4	6	8										
-5	-4.3	17.4	6	7	8										
-10	-9.3	22.4	3	5	4										
-15	-14.3	27.4	7	6	7										
-20	-19.3	32.4	5	7	6										
-25	-24.3	37.4	WOH	2	3										
-30	-29.3	42.4	2	2	4										
-35	-34.3	47.4	3	5	7										
-40	-39.3	52.4	5	8	11										
-45	-44.3	57.4	4	5	5										
-50	-49.3	62.4	3	2	2										
-55	-54.3	67.4	1	2	2										
-60	-59.3	72.4	1	4	8										
-65	-64.3	77.4													

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18

WBS 34360.1.1	TIP R-1015	COUNTY CRAVEN	GEOLOGIST Crenshaw, J. K.
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)			GROUND WTR (ft)
BORING NO. B5-B RL	STATION 176+04	OFFSET 61 ft RT	ALIGNMENT -L-
COLLAR ELEV. 13.1 ft	TOTAL DEPTH 118.9 ft	NORTHING 410,156	EASTING 2,625,166
DRILL RIG/HAMMER EFF./DATE MD0314 D-25 84% 09/05/2017		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Fowler, B.	START DATE 03/20/18	COMP. DATE 03/21/18	SURFACE WATER DEPTH 0.5ft

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-65															
-70	-69.3	82.4	5	7	9										
-75	-74.3	87.4	4	5	6										
-80	-79.3	92.4	8	10	13										
-85	-84.3	97.4	8	10	10										
-90	-89.3	102.4	4	6	12										
-95	-94.3	107.4	8	8	9										
-100	-99.3	112.4	7	11	11										
-105	-104.3	117.4	22	23	26										



GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1	TIP R-1015	COUNTY CRAVEN	GEOLOGIST Johnson, M.
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)			GROUND WTR (ft)
BORING NO. B6-A LL	STATION 177+76	OFFSET 59 ft LT	ALIGNMENT -L-
COLLAR ELEV. 17.6 ft	TOTAL DEPTH 99.9 ft	NORTHING 410,125	EASTING 2,624,959
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 04/13/18	COMP. DATE 04/16/18	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
20	17.6	0.0											GROUND SURFACE
15	14.4	3.2											ALLUVIAL Dark brown, MUCK UNDIVIDED COASTAL PLAIN Tan, orange and gray, fine sandy, silty CLAY (A-6)
10	9.4	8.2											COASTAL PLAIN Gray, phosphatic, clayey, fine to coarse SAND (A-2-6, A-2-4), contains shell fragments, with silt and clay (DUPLIN FORMATION)
5	4.4	13.2											
0	-0.6	18.2											
-5	-5.6	23.2											
-10	-10.6	28.2											
-15	-15.6	33.2											
-20	-20.6	38.2											
-25	-25.6	43.2											
-30	-30.6	48.2											
-35	-35.6	53.2											
-40	-40.8	58.4											
-45	-45.8	63.4											
-50	-50.8	68.4											
-55	-55.8	73.4											
-60													

WBS 34360.1.1	TIP R-1015	COUNTY CRAVEN	GEOLOGIST Johnson, M.
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)			GROUND WTR (ft)
BORING NO. B6-A LL	STATION 177+76	OFFSET 59 ft LT	ALIGNMENT -L-
COLLAR ELEV. 17.6 ft	TOTAL DEPTH 99.9 ft	NORTHING 410,125	EASTING 2,624,959
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 04/13/18	COMP. DATE 04/16/18	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
-60	-60.8	78.4											Match Line
-65	-65.8	83.4											Green and gray, phosphatic, fine to coarse, SAND (A-2-4, A-3), with silt and clay, contains shell fragments (RIVER BEND FORMATION) (continued)
-70	-70.8	88.4											COASTAL PLAIN SEDIMENTARY ROCK Gray, moderately hard, sandy LIMESTONE (RIVER BEND FORMATION)
-75	-75.8	93.4											COASTAL PLAIN Green, sandy SILT (A-4), contains shell fragments (RIVER BEND FORMATION)
-80	-80.8	98.4											Brown, clayey SAND (A-2-6), contains shell fragments (RIVER BEND FORMATION)
													Gray, sandy SILT (A-4) (RIVER BEND FORMATION)
													Boring Terminated at Elevation -82.3 ft in SILT (River Bend Formation) Strata break in split spoon at depths 9.0' and 78.9'

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J.K.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B6-B RL		STATION 177+86		OFFSET 44 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 17.3 ft		TOTAL DEPTH 120.1 ft		NORTHING 410,221		EASTING 2,624,996									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Wiggins, M.		START DATE 04/17/18		COMP. DATE 04/17/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
20															
	17.3	0.0													17.3
			WOH	2	2										
15	13.7	3.6		4	1	3									14.3
10	8.7	8.6		2	2	5									10.3
5	3.7	13.6		5	4	7									
0	-1.3	18.6		4	5	6									
-5	-6.3	23.6		6	7	8									
-10	-11.3	28.6		3	2	7									
-15	-16.3	33.6		5	5	4									
-20	-21.3	38.6		2	2	3									
-25	-26.3	43.6		3	3	4									
-30	-31.3	48.6		11	19	20									
-35	-36.3	53.6		15	20	28									
-40	-41.3	58.6		11	10	11									
-45	-46.3	63.6		5	8	9									
-50	-51.3	68.6		16	8	6									
-55	-56.3	73.6		5	4	5									
-60															

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Crenshaw, J.K.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B6-B RL		STATION 177+86		OFFSET 44 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 17.3 ft		TOTAL DEPTH 120.1 ft		NORTHING 410,221		EASTING 2,624,996									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Wiggins, M.		START DATE 04/17/18		COMP. DATE 04/17/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-60															
	-61.3	78.6		10	8	8									
-65	-66.3	83.6		13	13	9									
-70	-71.3	88.6		8	10	12									
-75	-76.3	93.6		7	7	9									
-80	-81.3	98.6		4	4	6									
-85	-86.3	103.6		10	10	9									
-90	-91.3	108.6		13	11	11									
-95	-96.3	113.6		9	14	14									
-100	-101.3	118.6		30	53	31									

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18


GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1			TIP R-1015			COUNTY CRAVEN			GEOLOGIST Crenshaw, J.K.		
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)									GROUND WTR (ft)		
BORING NO. B7-B RL			STATION 179+00			OFFSET 59 ft RT			ALIGNMENT -L-		
COLLAR ELEV. 19.4 ft			TOTAL DEPTH 100.1 ft			NORTHING 410,286			EASTING 2,624,901		
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic					
DRILLER Wiggins, M.			START DATE 04/18/18			COMP. DATE 04/18/18			SURFACE WATER DEPTH N/A		

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
35														
30														
25														
20	19.4	0.0	1	2	1									
15	15.8	3.6	2	3	2									
10	10.8	8.6	WOH	WOH	WOH									
5	5.8	13.6	4	4	5									
0	0.8	18.6	3	5	6									
-5	-4.2	23.6	5	9	12									
-10	-9.2	28.6	4	7	7									
-15	-14.2	33.6	5	8	9									
-20	-19.2	38.6	5	6	6									
-25	-24.2	43.6	1	3	3									
-30	-29.2	48.6	12	23	22									
-35	-34.2	53.6	12	13	24									
-40	-39.2	58.6	7	13	21									
-45	-44.2	63.6	15	21	23									


NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18




WBS 34360.1.1			TIP R-1015			COUNTY CRAVEN			GEOLOGIST Crenshaw, J.K.		
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)									GROUND WTR (ft)		
BORING NO. B7-B RL			STATION 179+00			OFFSET 59 ft RT			ALIGNMENT -L-		
COLLAR ELEV. 19.4 ft			TOTAL DEPTH 100.1 ft			NORTHING 410,286			EASTING 2,624,901		
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic					
DRILLER Wiggins, M.			START DATE 04/18/18			COMP. DATE 04/18/18			SURFACE WATER DEPTH N/A		

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
-45														
-50	-49.2	68.6	5	6	21									
-55	-54.2	73.6	7	10	14									
-60	-59.2	78.6	18	12	7									
-65	-64.2	83.6	5	7	9									
-70	-69.2	88.6	9	9	16									
-75	-74.2	93.6	5	5	7									
-80	-79.2	98.6	3	6	10									


Match Line



GEOTECHNICAL BORING REPORT BORE LOG



NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18





GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B8-B RL		STATION 180+39		OFFSET 52 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 22.0 ft		TOTAL DEPTH 114.9 ft		NORTHING 410,248		EASTING 2,624,726									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Wiggins, M.		START DATE 04/23/18		COMP. DATE 04/25/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
35															
30															
25															
20	22.0	0.0	1	2	2	4									
15	18.6	3.4	2	2	2										
10	13.6	8.4	WOH	WOH	WOH										
5	8.6	13.4	WOH	WOH	WOH										
0	3.6	18.4	4	4	9										
-5	-1.4	23.4	3	3	3										
-10	-6.4	28.4	5	6	8										
-15	-11.4	33.4	5	6	6										
-20	-16.4	38.4	3	3	3										
-25	-21.4	43.4	WOH	2	2										
-30	-26.4	48.4	2	2	3										
-35	-31.4	53.4	2	3	6										
-40	-36.4	58.4	10	18	25										
-45	-41.4	63.4	12	14	15										

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B8-B RL		STATION 180+39		OFFSET 52 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 22.0 ft		TOTAL DEPTH 114.9 ft		NORTHING 410,248		EASTING 2,624,726									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Wiggins, M.		START DATE 04/23/18		COMP. DATE 04/25/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-45															
-50	-46.4	68.4	10	8	12										
-55	-51.4	73.4	41	23	38										
-60	-56.4	78.4	5	5	8										
-65	-61.4	83.4	5	8	31										
-70	-66.4	88.4	7	7	6										
-75	-71.4	93.4	5	60	13										
-80	-76.4	98.4	7	7	16										
-85	-81.4	103.4	3	4	7										
-90	-86.4	108.4	3	3	4										
-92.9	-91.4	113.4	3	3	4										

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.											
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)						GROUND WTR (ft)											
BORING NO. B9-A LL		STATION 181+77		OFFSET 52 ft LT		ALIGNMENT -L-											
COLLAR ELEV. 21.9 ft		TOTAL DEPTH 98.5 ft		NORTHING 410,310		EASTING 2,624,603											
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017		DRILL METHOD Mud Rotary		HAMMER TYPE Automatic													
DRILLER Wiggins, M.		START DATE 04/26/18		COMP. DATE 04/26/18		SURFACE WATER DEPTH N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100							
25	21.9	0.0	1	1	0											21.9	0.0
20	18.5	3.4	2	2	1											18.9	3.0
15	13.5	8.4	WOH	WOH	WOH											15.9	6.0
10	8.5	13.4	WOH	WOH	WOH												
5	3.5	18.4	1	2	3											2.6	19.3
0	-1.5	23.4	1	1	1												
-5	-6.5	28.4	2	0	2												
-10	-11.5	33.4	2	3	4												
-15	-16.5	38.4	4	4	5												
-20	-21.5	43.4	2	2	2											-19.1	41.0
-25	-26.5	48.4	1	2	2						SS-536	56%					
-30	-31.5	53.4	WOH	1	3												
-35	-36.5	58.4	1	1	3											-37.5	59.4
-40	-41.5	63.4	8	8	13											-39.1	61.0
-45	-46.5	68.4	14	15	15												
-50	-51.5	73.4	7	10	12												
-55																-54.1	76.0

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/25/18

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.											
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)						GROUND WTR (ft)											
BORING NO. B9-A LL		STATION 181+77		OFFSET 52 ft LT		ALIGNMENT -L-											
COLLAR ELEV. 21.9 ft		TOTAL DEPTH 98.5 ft		NORTHING 410,310		EASTING 2,624,603											
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017		DRILL METHOD Mud Rotary		HAMMER TYPE Automatic													
DRILLER Wiggins, M.		START DATE 04/26/18		COMP. DATE 04/26/18		SURFACE WATER DEPTH N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100							
-55																	
-60	-56.5	78.4	20	63	37/0.1											100/0.6	
-65	-61.5	83.4	4	4	8												
-70	-66.5	88.4	6	8	9												
-75	-71.5	93.4	4	15	12												
-80	-76.5	98.4			60/0.1											60/0.1	

Match Line

Gray and green, clayey SAND (A-2-4, A-3), contains shell fragments and trace limestone fragments (RIVER BEND FORMATION) (continued)

Sat.

Sat.

Sat.

Sat.

Gray, SAND (A-1-b), with limestone fragments

Gray, moderately hard, sandy LIMESTONE (RIVER BEND FORMATION)

Boring Terminated at Elevation -76.6 ft in Moderately Hard Limestone (River Bend Formation)

Drill chatter at 90.1'

Split spoon from 98.4' to 98.5' resulted in no recovery

Strata break in split spoon at depths 19.3' and 59.4'

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B9-B RL		STATION 181+72		OFFSET 62 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 21.5 ft		TOTAL DEPTH 104.9 ft		NORTHING 410,410		EASTING 2,624,658									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Wiggins, M.		START DATE 04/25/18		COMP. DATE 04/26/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
25															
20	21.5	0.0	1	1	1										
15	18.1	3.4	1	1	0										
10	13.1	8.4	WOH	WOH	WOH										
5	8.1	13.4	WOH	WOH	WOH										
0	3.1	18.4	5	5	8										
-5	-1.9	23.4	3	4	4										
-10	-6.9	28.4	1	0	1										
-15	-11.9	33.4	5	5	5										
-20	-16.9	38.4	4	2	2										
-25	-21.9	43.4	2	2	1										
-30	-26.9	48.4	1	1	1										
-35	-31.9	53.4	3	2	2										
-40	-36.9	58.4	11	14	18										
-45	-41.9	63.4	9	12	12										
-50	-46.9	68.4	8	15	18										
-55	-51.9	73.4	14	13	20										

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B9-B RL		STATION 181+72		OFFSET 62 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 21.5 ft		TOTAL DEPTH 104.9 ft		NORTHING 410,410		EASTING 2,624,658									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Wiggins, M.		START DATE 04/25/18		COMP. DATE 04/26/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-55															
-60	-56.9	78.4	17	17	17										
-65	-61.9	83.4	5	4	11										
-70	-66.9	88.4	8	5	11										
-75	-71.9	93.4	23	7	12										
-80	-76.9	98.4	10	8	8										
	-81.9	103.4	5	5	4										

NCDOT BORE DOUBLE R1015_SITE 3.GPJ_NC_DOT.GDT 7/13/18

SS-511 42%


Match Line

Gray and green, phosphatic, silty SAND (A-1-b, A-3, A-2-4, A-2-6), contains shell and limestone fragments (RIVER BEND FORMATION) (continued)


Boring Terminated at Elevation -83.4 ft in SAND (River Bend Formation)

GEOTECHNICAL BORING REPORT

BORE LOG



NCDOT BORE DOUBLE R1015_SITE 3.GPJ NC_DOT_GDT 7/13/18



Boring Terminated at Elevation -77.8 ft in SAND (River Bend Formation)
 Loss of circulation at 83.0' and from 84.9' to 88.4'
 Caving at 30.0'
 Drill chatter at 74.3' and from 89.9' to 90.9'
 Strata break in split spoon at depths 19.4', 74.4', 78.9' and 84.4'

GEOTECHNICAL BORING REPORT

BORE LOG



WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.	
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)
BORING NO. B10-B RL		STATION 183+09		OFFSET 59 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 21.2 ft		TOTAL DEPTH 99.9 ft		NORTHING 410,468		EASTING 2,624,534	
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER Powell, B.		START DATE 05/01/18		COMP. DATE 05/01/18		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
25															
	21.2	0.0													21.2
20			WOH	WOH	1										
	17.8	3.4													18.2
15			2	2	2										
	12.8	8.4													15.2
10			WOH	WOH	WOH										
	7.8	13.4													10.2
5			WOH	1	1										
	2.8	18.4													1.6
0			WOH	1	2										
	-2.2	23.4													
-5			1	1	1										
	-7.2	28.4													
-10			3	5	6										
	-12.2	33.4													
-15			WOH	3	5										
	-17.2	38.4													
-20			4	5	6										
	-22.2	43.4													
-25			1	1	2										
	-27.2	48.4													
-30			2	2	2										
	-32.2	53.4													
-35			2	2	3										
	-37.2	58.4													
-40			1	2	3										
	-42.2	63.4													
-45			2	1	2										
	-47.2	68.4													
-50			2	8	29										
	-52.2	73.4													
-55			11	12	15										

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.	
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)
BORING NO. B10-B RL		STATION 183+09		OFFSET 59 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 21.2 ft		TOTAL DEPTH 99.9 ft		NORTHING 410,468		EASTING 2,624,534	
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER Powell, B.		START DATE 05/01/18		COMP. DATE 05/01/18		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-55															
	-57.2	78.4													
-60			8	9	15										
	-62.2	83.4													
-65			4	3	5										
	-67.2	88.4													
-70			20	54	46/0.5										
	-72.2	93.4													
-75			65	35/0.5											
	-77.2	98.4													
			15	14	9										

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.1			TIP R-1015			COUNTY CRAVEN			GEOLOGIST Grainger, P.			
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)								GROUND WTR (ft)				
BORING NO. B11-A LL			STATION 184+39			OFFSET 61 ft LT			ALIGNMENT -L-			0 HR. N/A
COLLAR ELEV. 22.6 ft			TOTAL DEPTH 99.9 ft			NORTHING 410,419			EASTING 2,624,364			24 HR. 1.0
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017						DRILL METHOD Mud Rotary			HAMMER TYPE Automatic			
DRILLER Powell, B.			START DATE 05/01/18			COMP. DATE 05/01/18			SURFACE WATER DEPTH N/A			

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
30																	
		22.6	0.0												22.6	GROUND SURFACE	0.0
		19.2	3.4												19.6	ALLUVIAL Dark brown silty SAND (A-2-4)	3.0
		16.6													16.6	UNDIVIDED COASTAL PLAIN Gray and orange, silty SAND (A-2-4), with trace clay	6.0
		14.2	8.4													COASTAL PLAIN Gray, CLAY (A-7-6) (DUPLIN FORMATION)	
		9.2	13.4														
		4.2	18.4														
		-0.8	23.4														
		-5.8	28.4														
		-10.8	33.4														
		-15.8	38.4														
		-20.8	43.4														
		-25.8	48.4														
		-30.8	53.4														
		-35.8	58.4														
		-40.8	63.4														
		-45.8	68.4														

WBS 34360.1.1			TIP R-1015			COUNTY CRAVEN			GEOLOGIST Grainger, P.			
SITE DESCRIPTION Site 3 - Bridge No. 276 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)								GROUND WTR (ft)				
BORING NO. B11-A LL			STATION 184+39			OFFSET 61 ft LT			ALIGNMENT -L-			0 HR. N/A
COLLAR ELEV. 22.6 ft			TOTAL DEPTH 99.9 ft			NORTHING 410,419			EASTING 2,624,364			24 HR. 1.0
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017						DRILL METHOD Mud Rotary			HAMMER TYPE Automatic			
DRILLER Powell, B.			START DATE 05/01/18			COMP. DATE 05/01/18			SURFACE WATER DEPTH N/A			

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
		-50.8	73.4													
		-55.8	78.4													
		-60.8	83.4													
		-65.8	88.4													
		-70.8	93.4													
		-75.8	98.4													

Match Line

<div style="text-align: center;"> <p>Sat. -51.3</p> <p>Sat. -55</p> <p>Sat. -60</p> <p>Sat. -65</p> <p>Sat. -70</p> <p>Sat. -73.4</p> <p>Sat. -77.3</p> </div>	<div style="text-align: center;"> <p>Gray, silty CLAY (A-6), contains trace shell fragments (DUPLIN FORMATION) <i>(continued)</i></p> <p>COASTAL PLAIN Gray and tan, cemented, clayey, fine to coarse SAND (A-2-4, A-3), contains shell and limestone fragments (RIVER BEND FORMATION)</p> </div>				

Boring Terminated at Elevation -77.3 ft in SAND (River Bend Formation)
Strata breaks in split spoon at depths 19.4', 28.9', 33.9' and 73.9'

NCDOT BORE DOUBLE R1015_SITE 3.GPJ NC_DOT.GDT 7/13/18



GEOTECHNICAL BORING REPORT

BORE LOG


WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B11-B RL		STATION 184+38		OFFSET 61 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 21.5 ft		TOTAL DEPTH 109.9 ft		NORTHING 410,528		EASTING 2,624,420									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Powell, B.		START DATE 05/02/18		COMP. DATE 05/02/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
35															
30															
25															
20	21.5	0.0	WOH	WOH	WOH										
15	18.1	3.4	WOH	2	2										
10	13.1	8.4	WOH	WOH	WOH										
5	8.1	13.4	WOH	WOH	WOH										
0	3.1	18.4	1	1	1										
-5	-1.9	23.4	4	3	2										
-10	-6.9	28.4	2	2	7										
-15	-11.9	33.4	3	5	5										
-20	-16.9	38.4	7	9	10										
-25	-21.9	43.4	5	7	9										
-30	-26.9	48.4	2	2	3										
-35	-31.9	53.4	2	2	3										
-40	-36.9	58.4	2	1	3										
-45	-41.9	63.4	WOH	WOH	1										

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. B11-B RL		STATION 184+38		OFFSET 61 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 21.5 ft		TOTAL DEPTH 109.9 ft		NORTHING 410,528		EASTING 2,624,420									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Powell, B.		START DATE 05/02/18		COMP. DATE 05/02/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-45															
-50	-46.9	68.4	WOH	WOH	2										
-55	-51.9	73.4	10	11	14										
-60	-56.9	78.4	62	38/0.5											
-65	-61.9	83.4	9	5	5										
-70	-66.9	88.4	5	7	36										
-75	-71.9	93.4	19	60/0.1											
-80	-76.9	98.4	11	10	13										
-85	-81.9	103.4	6	7	11										
	-86.9	108.4	6	8	13										


NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



GEOTECHNICAL BORING REPORT BORE LOG



NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18




GEOTECHNICAL BORING REPORT

BORE LOG


WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. EB2-B RL		STATION 185+91		OFFSET 59 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 22.1 ft		TOTAL DEPTH 99.9 ft		NORTHING 410,594		EASTING 2,624,282									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Powell, B.		START DATE 05/03/18		COMP. DATE 05/04/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
35															
	22.1	0.0		WOH	WOH	1									
	18.7	3.4		WOH		3									
	13.7	8.4		WOH	WOH	WOH									
	8.7	13.4		WOH	WOH	1									
	3.7	18.4		WOH	WOH	WOH									
	-1.3	23.4													
	-6.3	28.4													
	-11.3	33.4													
	-16.3	38.4													
	-21.3	43.4													
	-26.3	48.4													
	-31.3	53.4													
	-36.3	58.4													
	-41.3	63.4													

WBS 34360.1.1		TIP R-1015		COUNTY CRAVEN		GEOLOGIST Grainger, P.									
SITE DESCRIPTION Site 3 - Bridge No. 277 Over East Prong of Slocum Creek on US 70 (Havelock Bypass)							GROUND WTR (ft)								
BORING NO. EB2-B RL		STATION 185+91		OFFSET 59 ft RT		ALIGNMENT -L-									
COLLAR ELEV. 22.1 ft		TOTAL DEPTH 99.9 ft		NORTHING 410,594		EASTING 2,624,282									
DRILL RIG/HAMMER EFF./DATE MD1904 CME-45B 78% 08/20/2017			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic									
DRILLER Powell, B.		START DATE 05/03/18		COMP. DATE 05/04/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-45															
	-46.3	68.4				1	1	3							
	-51.3	73.4				12	15	14							
	-56.3	78.4				7	6	11							
	-61.3	83.4				3	8	14							
	-66.3	88.4				4	2	6							
	-71.3	93.4				7	9	9							
	-76.3	98.4				14	15	13							

NCDOT BORE DOUBLE R1015_GEO_SITE 3.GPJ NC_DOT_GDT 7/13/18



Match Line



SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS- 327	60 LT	169+52	8.6- 10.1	A- 2- 4(0)	NP	NP	9.8	74.1	2.2	13.9	100	99	17.7	26.2	-
SS- 336	60 LT	169+52	53.6- 55.1	A- 3(0)	NP	NP	1.8	90.7	0	7.7	100	99.6	9	23.7	-
SS- 5	61 RT	172+22	19.6- 21.1	A- 3(0)	NP	NP	28.1	69.9	0.3	1.7	99.8	97.1	2.5	20.2	-
SS- 98	87 RT	174+86	38.0- 39.5	A- 7- 5(15)	50	29	14.9	31.8	19.5	33.8	92.5	81.5	59.4	37.5	-
SS- 99	87 RT	174+86	43.0- 44.5	A- 6 (1)	35	15	44.1	23.5	11.2	21.2	96.2	68.5	35.9	31.6	-
SS- 100	87 RT	174+86	48.0- 49.5	A- 1- b(0)	NP	NP	71.8	22.4	0.2	5.6	99	49	6.4	14.7	-
SS- 130	61 RT	176+04	72.4- 73.9	A- 2- 4(0)	NP	NP	40.6	38.2	9.6	11.3	88.8	64.9	20.9	16.2	-
SS- 471	65 LT	180+38	53.5- 55.0	A- 1- b(0)	NP	NP	82.3	12.6	0	5.7	98.5	43.6	6	19.4	-
SS- 536	52 LT	181+77	43.4- 44.9	A- 7- 6(26)	53	35	10.7	25	26.2	38.1	99.1	91.6	75.2	56.4	-
SS- 511	62 RT	181+72	28.4- 29.9	A- 4(0)	NP	NP	43	24.3	16.6	16.1	100	71.9	37.6	41.9	-
SS- 624	61 RT	184+38	63.4- 64.9	A- 6(8)	38	17	8.2	42.8	18	31	97.3	91.2	60.3	41.6	-
SS- 648	50 LT	185+78	68.4- 69.9	A- 6(9)	38	19	5.5	47.1	16.5	30.9	99.4	95.7	58.7	39.4	-
ST- 1	58 RT	169+54	4.5- 6.5	A- 6(3)	34	12	0.2	59.1	6	34.7	100	99.9	45.2	29.2	-
ST- 4	63 RT	185+90	16.1- 18.1	A- 7- 6(31)	61	37	0.2	22.9	22.7	54.2	100	99.9	80.5	60.7	-



Photo 1: Looking towards End Bent 2 and up station of -L-




Photo 2: Looking towards End Bent 1 and down station of -L-



Photo 3: Looking upstream at the East Prong of Slocum Creek



Photo 4: Looking downstream at the East Prong of Slocum Creek



REFERENCE: R-1015

PROJECT: 34360

CONTENTS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4-5	PROFILES
6-9	CROSS SECTIONS
10-17	BORE LOGS
18-19	SOIL TEST RESULTS
20-21	SITE PHOTOGRAPHS

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY CRAVEN
PROJECT DESCRIPTION US 70 (Havelock Bypass) from
North of Pine Grove to North of Carteret County Line

SITE DESCRIPTION Site No. 4 - Bridge Nos. 278 and 279 on
-L- (US 70 Havelock Bypass) over -RR EY2- (Camp Lejeune Railroad)
STA 227+57.02 -L- /22+70.14 -RR EY2-

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	R-1015	1	21

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTES:
1. THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
2. BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

GW Stalls

BR Spiro

MR English

BB Bahhur

KR Cullen

RM Bleifernich

INVESTIGATED BY GET SOLUTIONS

DRAWN BY BB Bahhur, KR Cullen

CHECKED BY GW Stalls

SUBMITTED BY GW Stalls

DATE June 2018




DocuSigned by:
Gerald W. Stalls, Jr. 3/6/2018
D9E3B27263A8414
SIGNATURE DATE

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS																			
SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6										WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.										HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:										ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (ROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (IN OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.																			
SOIL LEGEND AND AASHTO CLASSIFICATION										ANGULARITY OF GRAINS										WEATHERING																													
GENERAL CLASS. GRANULAR MATERIALS (<= 35% PASSING #200) SILT-CLAY MATERIALS (> 35% PASSING #200) ORGANIC MATERIALS										THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.										WEATHERED ROCK (WR) NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.																													
MINERALOGICAL COMPOSITION										COMPRESSION										CRYSTALLINE ROCK (CR)																													
MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.										SLIGHTLY COMPRESSIBLE LL < 31 MODERATELY COMPRESSIBLE LL = 31 - 50 HIGHLY COMPRESSIBLE LL > 50										FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.																													
PERCENTAGE OF MATERIAL										GROUND WATER										NON-CRYSTALLINE ROCK (NCR)																													
ORGANIC MATERIAL TRACE OF ORGANIC MATTER 2 - 3% LITTLE ORGANIC MATTER 3 - 5% MODERATELY ORGANIC 5 - 10% HIGHLY ORGANIC > 10%										WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING STATIC WATER LEVEL AFTER 24 HOURS PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA SPRING OR SEEP										FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.																													
MISCELLANEOUS SYMBOLS										RECOMMENDATION SYMBOLS										COASTAL PLAIN SEDIMENTARY ROCK (CPS)																													
ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION SOIL SYMBOL ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT INFERRED SOIL BOUNDARY INFERRED ROCK LINE ALLUVIAL SOIL BOUNDARY										UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK UNDERCUT SHALLOW UNDERCUT										COASTAL PLAIN SEDIMENTARY ROCK (CPS) ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.																													
TEXTURE OR GRAIN SIZE										ABBREVIATIONS										ROCK HARDNESS																													
U.S. STD. SIEVE SIZE OPENING (MM) 4 10 40 60 200 270 4.76 2.00 0.42 0.25 0.075 0.053										AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - CONE PENETRATION TEST CSE. - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F - FINE FOSS. - FOSSILIFEROUS FRAC. - FRACTURED, FRACTURES FRAGS. - FRAGMENTS HI. - HIGHLY										VERY HARD CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK. HARD CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN. MODERATELY HARD CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS. MEDIUM HARD CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK. SOFT CAN BE GROOVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE. VERY SOFT CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.																													
SOIL MOISTURE - CORRELATION OF TERMS										EQUIPMENT USED ON SUBJECT PROJECT										FRACTURE SPACING										BEDDING																			
SOIL MOISTURE SCALE (ATTERBERG LIMITS) FIELD MOISTURE DESCRIPTION GUIDE FOR FIELD MOISTURE DESCRIPTION										DRILL UNITS: [X] CME-45C [] CME-55 [] CME-550 [] VANE SHEAR TEST [] PORTABLE HOIST										TERM SPACING MORE THAN 10 FEET 3 TO 10 FEET 1 TO 3 FEET 0.16 TO 1 FOOT LESS THAN 0.16 FEET										TERM THICKNESS 4 FEET 1.5 - 4 FEET 0.16 - 1.5 FEET 0.03 - 0.16 FEET 0.008 - 0.03 FEET < 0.008 FEET										BENCH MARK: BM2 STA 228+71.03 -L-, 242.76' LT., RR SPIKE IN TREE. ELEVATION: 28.81 FEET									
LL - LIQUID LIMIT PL - PLASTIC LIMIT OM - OPTIMUM MOISTURE SHRINKAGE LIMIT										ADVANCING TOOLS: [] CLAY BITS [] 6" CONTINUOUS FLIGHT AUGER [] 8" HOLLOW AUGERS [] HARD FACED FINGER BITS [] TUNG.-CARBIDE INSERTS [X] CASING [] W/ ADVANCER [X] TRICONE 2.88" STEEL TEETH [X] TRICONE 3.25" STEEL TEETH [] CORE BIT										CORE SIZE: [] -B [] -H [] -N										HAND TOOLS: [] POST HOLE DIGGER [] HAND AUGER [] SOUNDING ROD [] VANE SHEAR TEST										NOTES:									
PLASTICITY										INDURATION																																							
NON PLASTIC 0-5 VERY LOW SLIGHTLY PLASTIC 6-15 SLIGHT MODERATELY PLASTIC 16-25 MEDIUM HIGHLY PLASTIC 26 OR MORE HIGH										FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC. FRIABLE RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE. MODERATELY INDURATED GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER. INDURATED GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER. EXTREMELY INDURATED SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																																							
COLOR																																																	
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																																																	


SITE PLAN




BENCH MARK: BM12 STA. 228+71.03 -L-, 242.76' LT., RR SPIKE IN TREE. EL. 28.81


IDENTIFICATION STATION
 STA. 227+57.02 -L-
 POC STA 22+70.14 -RR EY2-



-L- POT Sta. 229+00.00 =
 -Y3RPB- ST Sta. 0+00.00






PROJECT REFERENCE NO.	SHEET NO.
R-1015	4
BRIDGE 278 SUBSURFACE PROFILE ALONG CENTERLINE -L-	






8/23/99



CROSS SECTION THROUGH END BENT 1


VE = 1
SKEW = 97° -15' -41"



8/23/99

CROSS SECTION THROUGH BENT 1


VE = 1
SKEW = 97° -15' -41"



B/23/99

CROSS SECTION THROUGH BENT 2

VE = 1
SKEW = 97° -15' -41"




-100 -90 -80 -70 -60 -50 -40 -30 -20 -10 0 10 20 30 40 50 60 70 80 90 100

8/23/99



CROSS SECTION THROUGH END BENT 2

VE = 1
SKEW = 97° -15' -41"



GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.2	TIP R-1015	COUNTY CRAVEN	GEOLOGIST R. Bliefemich
SITE DESCRIPTION Site No. 4 - Bridge No. 278 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)			GROUND WTR (ft)
BORING NO. EB1-A LL	STATION 226+59	OFFSET 68 ft LT	ALIGNMENT -L-
COLLAR ELEV. 27.4 ft	TOTAL DEPTH 105.0 ft	NORTHING 412,296	EASTING 2,620,585
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER T. Donahue	START DATE 05/18/18	COMP. DATE 05/22/18	SURFACE WATER DEPTH N/A

WBS 34360.1.2	TIP R-1015	COUNTY CRAVEN	GEOLOGIST R. Bliefemich
SITE DESCRIPTION Site No. 4 - Bridge No. 278 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)			GROUND WTR (ft)
BORING NO. EB1-A LL	STATION 226+59	OFFSET 68 ft LT	ALIGNMENT -L-
COLLAR ELEV. 27.4 ft	TOTAL DEPTH 105.0 ft	NORTHING 412,296	EASTING 2,620,585
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER T. Donahue	START DATE 05/18/18	COMP. DATE 05/22/18	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
30																
	27.4	0.0	1	2	2									27.4	GROUND SURFACE	0.0
														24.4	UNDIVIDED COASTAL PLAIN Low Plasticity, Soft, Tan, Sandy, CLAY with Trace to Little Silt	3.0
	22.4	5.0	2	2	4									19.9	UNDIVIDED COASTAL PLAIN Non Plastic, Loose, Gray and Tan, Silty, Fine to Coarse SAND with Trace Clay	7.5
	18.9	8.5	2	2	3									10.9	UNDIVIDED COASTAL PLAIN Non Plastic, Loose, Gray, Fine to Medium SAND with Trace Silt	16.5
	13.9	13.5	3	3	4									0.9	UNDIVIDED COASTAL PLAIN Non Plastic, Loose, Gray or Tan, Silty, Fine to Medium SAND with Trace Clay	26.5
	8.9	18.5	3	3	4											
	3.9	23.5	3	5	3											
	-1.1	28.5	2	2	4											
	-6.1	33.5	4	4	6											
	-11.1	38.5	4	6	7											
	-16.1	43.5	4	4	4											
	-21.1	48.5	1	1	2											
	-26.1	53.5	2	2	3											
	-31.1	58.5	2	3	3											
	-36.1	63.5	2	4	5											
	-41.1	68.5	2	3	4											
	-46.1	73.5	3	6	7											

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
-50																
	-51.1	78.5	30	26	29											
	-56.1	83.5	14	10	18											
	-61.1	88.5	9	7	8											
	-66.1	93.5	9	11	12											
	-71.1	98.5	11	9	11											
	-76.1	103.5	9	11	8											

NCDOT BORE DOUBLE EC18-161G_R-1015_SITE 4.GPJ_NC_DOT.GDT 7/19/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.2		TIP R-1015		COUNTY CRAVEN		GEOLOGIST R. Bliefertich									
SITE DESCRIPTION Site No. 4 - Bridge No. 278 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)							GROUND WTR (ft)								
BORING NO. B1-A LL		STATION 227+07		OFFSET 67 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 24.1 ft		TOTAL DEPTH 100.0 ft		NORTHING 412,319		EASTING 2,620,542									
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018				DRILL METHOD Mud Rotary		HAMMER TYPE Automatic									
DRILLER T. Donahue		START DATE 05/16/18		COMP. DATE 05/17/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
25	24.1	0.0	1	2	3								24.1	GROUND SURFACE	0.0
													21.1	UNDIVIDED COASTAL PLAIN Low Plasticity, Loose, Mottled Gray-Tan, Clayey, Fine to Medium SAND with Trace Silt	3.0
20	19.1	5.0	2	2	1								16.6	UNDIVIDED COASTAL PLAIN Non Plastic, Very Loose, Tan or Gray, Silty, Fine to Medium SAND with Trace Clay	7.5
15	15.6	8.5	5	4	4								7.6	UNDIVIDED COASTAL PLAIN Non Plastic, Loose, Tan-Reddish Tan or Gray, Fine to Medium SAND with Trace Silt	16.5
10	10.6	13.5	3	2	3									UNDIVIDED COASTAL PLAIN Low Plasticity, Loose, Tan or Reddish Tan, Clayey, Silty, Fine to Coarse SAND	
5	5.6	18.5	1	2	3									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
0	0.6	23.5	2	3	3									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-5	-4.4	28.5	3	4	4									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-10	-9.4	33.5	3	6	13									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-15	-14.4	38.5	7	7	7									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-20	-19.4	43.5	2	2	3									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-25	-24.4	48.5	3	3	4									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-30	-29.4	53.5	3	3	3									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-35	-34.4	58.5	3	4	5									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-40	-39.4	63.5	2	4	5									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-45	-44.4	68.5	2	2	3									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-50	-49.4	73.5	4	5	48									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	
-55	-54.4	78.5												UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace to Little Silt and Clay	

WBS 34360.1.2		TIP R-1015		COUNTY CRAVEN		GEOLOGIST R. Bliefertich									
SITE DESCRIPTION Site No. 4 - Bridge No. 278 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)							GROUND WTR (ft)								
BORING NO. B1-A LL		STATION 227+07		OFFSET 67 ft LT		ALIGNMENT -L-									
COLLAR ELEV. 24.1 ft		TOTAL DEPTH 100.0 ft		NORTHING 412,319		EASTING 2,620,542									
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018				DRILL METHOD Mud Rotary		HAMMER TYPE Automatic									
DRILLER T. Donahue		START DATE 05/16/18		COMP. DATE 05/17/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-55			18	13	10								Match Line		
														COASTAL PLAIN Non Plastic, Medium Dense, Gray, Fine to Medium SAND with Trace Silt ("Duplin Formation")	81.5
-60	-59.4	83.5	8	7	6									COASTAL PLAIN Low Plasticity, Medium Dense, Dark Gray, Silty, Fine to Medium SAND with Trace Clay ("Duplin Formation")	86.5
-65	-64.4	88.5	5	4	6									COASTAL PLAIN Non Plastic, Medium Dense, Olive Green or Dark Gray, Calcareous, Silty, Fine to Medium SAND with Trace to Little Marine Shell Fragments, Trace Clay, Trace Fine Gravel, and Trace Cemented Sand Fragments ("Duplin Formation")	91.5
-70	-69.4	93.5	9	4	6									COASTAL PLAIN Soft, Gray, LIMESTONE with Trace to Little Marine Shell Fragments ("River Bend Formation")	96.5
-75	-74.4	98.5	7	8	8									COASTAL PLAIN SEDIMENTARY ROCK Soft, Gray, LIMESTONE with Trace to Little Marine Shell Fragments ("River Bend Formation")	100.0

NCDOT BORE DOUBLE EC18-161G_R-1015_SITE 4.GPJ_NC_DOT.GDT 7/19/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.2	TIP R-1015	COUNTY CRAVEN	GEOLOGIST R. Bliefemich
SITE DESCRIPTION Site No. 4 - Bridge No. 278 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)			GROUND WTR (ft)
BORING NO. B2-A LL	STATION 228+13	OFFSET 67 ft LT	ALIGNMENT -L-
COLLAR ELEV. 25.2 ft	TOTAL DEPTH 108.8 ft	NORTHING 412,366	EASTING 2,620,448
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER T. Donahue	START DATE 05/21/18	COMP. DATE 05/22/18	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
30													
25	25.2	0.0	2	1	2								25.2 GROUND SURFACE 0.0
20	20.2	5.0	5	5	4								22.2 UNDIVIDED COASTAL PLAIN Low Plasticity, Very Loose, Mottled Gray and Reddish Tan, Clayey, Fine to Medium SAND with Trace Silt 3.0
15	16.7	8.5	2	2	4								UNDIVIDED COASTAL PLAIN Low Plasticity, Loose, Gray, Silty, Fine to Medium SAND with Trace Clay
10	11.7	13.5	4	5	5								13.7 UNDIVIDED COASTAL PLAIN Non Plastic, Very Loose to Medium Dense, Tan or Gray, Fine to Coarse SAND with Trace Silt and Clay 11.5
5	6.7	18.5	1	1	2								3.7 UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Silty, Fine to Medium SAND with Trace to Little Clay 21.5
0	1.7	23.5	4	3	4								
-5	-3.3	28.5	2	3	5								
-10	-8.3	33.5	5	5	4								
-15	-13.3	38.5	3	5	8								
-20	-18.3	43.5	2	2	2								
-25	-23.3	48.5	1	2	2								
-30	-28.3	53.5	2	2	3								
-35	-33.3	58.5	2	3	2								
-40	-38.3	63.5	4	5	5								
-45	-43.3	68.5	2	3	4								
-50	-48.3	73.5	3	8	30								

WBS 34360.1.2	TIP R-1015	COUNTY CRAVEN	GEOLOGIST R. Bliefemich
SITE DESCRIPTION Site No. 4 - Bridge No. 278 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)			GROUND WTR (ft)
BORING NO. B2-A LL	STATION 228+13	OFFSET 67 ft LT	ALIGNMENT -L-
COLLAR ELEV. 25.2 ft	TOTAL DEPTH 108.8 ft	NORTHING 412,366	EASTING 2,620,448
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER T. Donahue	START DATE 05/21/18	COMP. DATE 05/22/18	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
-50													
-55	-53.3	78.5	10	12	13								Match Line
-60	-58.3	83.5	4	6	6								
-65	-63.3	88.5	22	12	100/0.2								
-70	-68.3	93.5	22	12	12								
-75	-73.3	98.5	42	11	13								
-80	-78.3	103.5	26	16	32								
	-83.3	108.5	100/0.3		100/0.3								

NCDOT BORE DOUBLE EC18-161G_R-1015_SITE 4.GPJ_NC_DOT.GDT 7/19/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.2	TIP R-1015	COUNTY CRAVEN	GEOLOGIST R. Bliefertich
SITE DESCRIPTION Site No. 4 - Bridge No. 278 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)			GROUND WTR (ft)
BORING NO. EB2-A LL	STATION 228+42	OFFSET 72 ft LT	ALIGNMENT -L-
COLLAR ELEV. 25.3 ft	TOTAL DEPTH 95.0 ft	NORTHING 412,374	EASTING 2,620,419
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER T. Donahue	START DATE 05/21/18	COMP. DATE 05/22/18	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
30													
25	25.3	0.0	1	2	2							M	GROUND SURFACE UNDIVIDED COASTAL PLAIN Medium Plasticity, Soft, Mottled Gray-Tan, CLAY, with Fine Sand
20	20.3	5.0	3	3	2							W	UNDIVIDED COASTAL PLAIN Non Plastic, Loose, Tan to Gray, Fine to Medium SAND with Trace Silt
15	16.8	8.5	1	2	2							W	UNDIVIDED COASTAL PLAIN Low Plasticity, Very Loose, Gray-Tan, Silty, Fine to Medium SAND with Trace Clay
10	11.8	13.5	3	3	4							W	UNDIVIDED COASTAL PLAIN Non Plastic, Loose, Tan, Fine to Medium SAND with Trace Silt
5	6.8	18.5	1	2	3							W	UNDIVIDED COASTAL PLAIN Low Plasticity, Loose, Dark Gray, Silty, Fine to Medium SAND with Trace Clay
0	1.8	23.5	1	3	3							W	
-5	-3.2	28.5	2	2	6							W	UNDIVIDED COASTAL PLAIN Non Plastic to Low Plasticity, Loose, Dark Gray, Fine to Coarse SAND with Little Clay and Trace Silt
-10	-8.2	33.5	3	4	3							W	
-15	-13.2	38.5	3	2	3							W	
-20	-18.2	43.5	1	1	3							W	COASTAL PLAIN Non Plastic to Low Plasticity, Loose, Dark Gray, Clayey, Fine to Coarse SAND with Trace to Little Silt and Trace to Little Marine Shell Fragments ("Duplin Formation")
-25	-23.2	48.5	2	2	3							W	
-30	-28.2	53.5	2	2	3							W	
-35	-33.2	58.5	3	3	3							W	COASTAL PLAIN High Plasticity, Medium Stiff to Stiff, Dark Gray, CLAY with Trace to Little Sand and Trace to Little Marine Shell Fragments ("Duplin Formation")
-40	-38.2	63.5	4	5	6							W	
-45	-43.2	68.5	1	2	3							W	COASTAL PLAIN Low Plasticity, Loose, Dark Gray, Clayey, Fine to Medium SAND with Little Silt and Trace to Little Marine Shell Fragments ("Duplin Formation")
-50	-48.2	73.5	4	8	100/0.2							W	

WBS 34360.1.2	TIP R-1015	COUNTY CRAVEN	GEOLOGIST R. Bliefertich
SITE DESCRIPTION Site No. 4 - Bridge No. 278 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)			GROUND WTR (ft)
BORING NO. EB2-A LL	STATION 228+42	OFFSET 72 ft LT	ALIGNMENT -L-
COLLAR ELEV. 25.3 ft	TOTAL DEPTH 95.0 ft	NORTHING 412,374	EASTING 2,620,419
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER T. Donahue	START DATE 05/21/18	COMP. DATE 05/22/18	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
-50													
-55	-53.2	78.5	5	6	7							W	Match Line
-60	-58.2	83.5	8	7	10							W	COASTAL PLAIN Non Plastic, Medium Dense to Very Dense, Olive Green or Gray, Calcareous, Silty, Fine SAND with Trace to Little Marine Shell Fragments, Trace Cemented Sand Fragments, and Trace Fine Gravel ("Duplin Formation") (continued)
-65	-63.2	88.5	14	13	11							W	COASTAL PLAIN SEDIMENTARY ROCK Soft, Gray, LIMESTONE with Trace Marine Shell Fragments ("River Bend Formation")
-69.7	-68.2	93.5	14	12	8							W	Boring Terminated at Elevation -69.7 ft in Soft, LIMESTONE with Trace Marine Shell Fragments ("River Bend Formation")

NCDOT BORE DOUBLE EC18-161G_R-1015_SITE 4.GPJ_NC_DOT.GDT 7/19/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34360.1.2	TIP R-1015	COUNTY CRAVEN	GEOLOGIST M. English
SITE DESCRIPTION Site No. 4 - Bridge No. 279 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)			GROUND WTR (ft)
BORING NO. EB1-B RL	STATION 226+46	OFFSET 73 ft RT	ALIGNMENT -L- 0 HR. 4.4
COLLAR ELEV. 26.6 ft	TOTAL DEPTH 100.0 ft	NORTHING 412,416	EASTING 2,620,659 24 HR. 2.4
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER T. Donahue		START DATE 05/17/18	COMP. DATE 05/18/18
SURFACE WATER DEPTH N/A			

WBS 34360.1.2	TIP R-1015	COUNTY CRAVEN	GEOLOGIST M. English
SITE DESCRIPTION Site No. 4 - Bridge No. 279 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)			GROUND WTR (ft)
BORING NO. EB1-B RL	STATION 226+46	OFFSET 73 ft RT	ALIGNMENT -L- 0 HR. 4.4
COLLAR ELEV. 26.6 ft	TOTAL DEPTH 100.0 ft	NORTHING 412,416	EASTING 2,620,659 24 HR. 2.4
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER T. Donahue		START DATE 05/17/18	COMP. DATE 05/18/18
SURFACE WATER DEPTH N/A			

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
30																
	26.6	0.0	2	2	2									GROUND SURFACE	0.0	
														UNDIVIDED COASTAL PLAIN Low Plasticity, Soft, Tan, Sandy, CLAY with Trace Organic Matter	3.0	
	21.6	5.0	2	3	5									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Tan and Gray, Fine to Medium SAND with Trace Silt and Trace Clay		
	18.1	8.5	3	5	5											
	13.1	13.5	1	2	3									UNDIVIDED COASTAL PLAIN Low Plasticity, Loose, Tan, Clayey, SAND with Trace Silt	11.5	
	8.1	18.5	3	3	3									UNDIVIDED COASTAL PLAIN Non Plastic, Loose, Tan, Fine to Medium SAND with Trace Silt	16.5	
	3.1	23.5	2	4	2											
	-1.9	28.5	4	4	5									UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Gray, Fine to Medium SAND with Trace Silt and Trace Clay	26.5	
	-6.9	33.5	3	5	6											
	-11.9	38.5	6	9	9											
	-16.9	43.5	6	8	8											
	-21.9	48.5	1	2	3									COASTAL PLAIN Non Plastic to Low Plasticity, Loose, Gray, Clayey Fine to Coarse SAND with Trace to Little Silt and Trace to Little Marine Shell Fragments ("Duplin Formation")	46.5	
	-26.9	53.5	1	2	3											
	-31.9	58.5	2	4	4									COASTAL PLAIN Non Plastic to Low Plasticity, Medium Stiff to Stiff, Gray, Sandy, Silty, CLAY with Trace to Little Marine Shell Fragments ("Duplin Formation")	56.5	
	-36.9	63.5	3	5	5											
	-41.9	68.5	2	2	3									COASTAL PLAIN Low Plasticity, Loose, Gray, Clayey, Fine to Coarse SAND with Little Silt and Little Marine Shell Fragments ("Duplin Formation")	66.5	
	-46.9	73.5	7	7	11									COASTAL PLAIN Non Plastic, Medium Dense to Very Dense, Gray, Silty Fine to Medium SAND with Trace Fine Gravel ("Duplin Formation")	71.5	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
														Match Line		
	-51.9	78.5	7	8	45									COASTAL PLAIN Non Plastic, Medium Dense to Very Dense, Gray, Silty Fine to Medium SAND with Trace Fine Gravel ("Duplin Formation") (continued)	81.5	
	-56.9	83.5	44	22	18									COASTAL PLAIN Non Plastic, Dense, Gray, Calcareous, Silty, Fine to Medium SAND with Trace to Little Marine Shell Fragments, Trace Cemented Sand Fragments, and Trace Fine Gravel ("Duplin Formation")		
	-61.9	88.5	27	15	22											
	-66.9	93.5	4	16	10									COASTAL PLAIN SEDIMENTARY ROCK Soft, Gray, LIMESTONE with Trace Marine Shell Fragments ("River Bend Formation")	91.5	
	-71.9	98.5	8	8	11											
														Boring Terminated at Elevation -73.4 ft in Soft, LIMESTONE with Trace Marine Shell Fragments ("River Bend Formation")	100.0	

NCDOT BORE DOUBLE EC:18-161G_R-1015_SITE 4.GPJ_NC_DOT.GDT 7/19/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.2		TIP R-1015		COUNTY CRAVEN		GEOLOGIST R. Bliefertich										
SITE DESCRIPTION Site No. 4 - Bridge No. 279 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)							GROUND WTR (ft)									
BORING NO. B1-B RL		STATION 226+88		OFFSET 74 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 24.0 ft		TOTAL DEPTH 110.0 ft		NORTHING 412,436		EASTING 2,620,622										
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER T. Donahue		START DATE 05/16/18		COMP. DATE 05/17/18		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
25	24.0	0.0	2	2	2									24.0	GROUND SURFACE	0.0
														21.0	UNDIVIDED COASTAL PLAIN Low Plasticity, Soft, Gray, Sandy, CLAY with Silt	3.0
20	19.0	5.0	3	5	5											
15	15.5	8.5	4	5	4											
10	10.5	13.5	3	3	3											
5	5.5	18.5	1	2	4											
0	0.5	23.5	1	2	3											
-5	-4.5	28.5	5	3	3											
-10	-9.5	33.5	4	4	6											
-15	-14.5	38.5	5	8	10											
-20	-19.5	43.5	1	1	2											
-25	-24.5	48.5	2	2	2											
-30	-29.5	53.5	2	3	3											
-35	-34.5	58.5	4	3	4											
-40	-39.5	63.5	2	3	3											
-45	-44.5	68.5	5	11	15											
-50	-49.5	73.5	4	4	6											
-55	-54.5	78.5														

WBS 34360.1.2		TIP R-1015		COUNTY CRAVEN		GEOLOGIST R. Bliefertich										
SITE DESCRIPTION Site No. 4 - Bridge No. 279 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)							GROUND WTR (ft)									
BORING NO. B1-B RL		STATION 226+88		OFFSET 74 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 24.0 ft		TOTAL DEPTH 110.0 ft		NORTHING 412,436		EASTING 2,620,622										
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER T. Donahue		START DATE 05/16/18		COMP. DATE 05/17/18		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
-55			17	11	14											
-60	-59.5	83.5	5	5	12											
-65	-64.5	88.5	20	18	19											
-70	-69.5	93.5	10	8	18											
-75	-74.5	98.5	10	11	14											
-80	-79.5	103.5	11	14	12											
-85	-84.5	108.5	17	23	24											

NCDOT BORE DOUBLE EC18-161G_R-1015_SITE 4.GPJ_NC_DOT.GDT 7/19/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.2		TIP R-1015		COUNTY CRAVEN		GEOLOGIST R. Bliefertich	
SITE DESCRIPTION Site No. 4 - Bridge No. 279 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)							GROUND WTR (ft)
BORING NO. B2-B RL		STATION 227+97		OFFSET 77 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 24.4 ft		TOTAL DEPTH 108.6 ft		NORTHING 412,487		EASTING 2,620,527	
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018				DRILL METHOD Mud Rotary		HAMMER TYPE Automatic	
DRILLER T. Donahue		START DATE 05/22/18		COMP. DATE 05/23/18		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
25	24.4	0.0												24.4	GROUND SURFACE	0.0
			1	2	1									21.4	UNDIVIDED COASTAL PLAIN Low Plasticity, Very Loose, Mottled Gray-Tan, Clayey, Fine SAND with Silt	3.0
	19.4	5.0	2	4	4									12.9	UNDIVIDED COASTAL PLAIN Non Plastic, Loose, Gray, Silty, Fine to Coarse SAND	11.5
	15.9	8.5	2	3	5									7.9	UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Dark Gray, Fine to Coarse SAND with Trace Silt and Trace Clay	16.5
	10.9	13.5	3	4	6											
	5.9	18.5	3	3	3											
	0.9	23.5	2	2	3											
	-4.1	28.5	2	3	5											
	-9.1	33.5	2	5	5											
	-14.1	38.5	5	6	8											
	-19.1	43.5	1	2	3											
	-24.1	48.5	1	2	2											
	-29.1	53.5	2	2	3											
	-34.1	58.5	2	3	4											
	-39.1	63.5	4	4	5											
	-44.1	68.5	2	3	5											
	-49.1	73.5	5	7	7											
	-54.1	78.5	10	12	13											

WBS 34360.1.2		TIP R-1015		COUNTY CRAVEN		GEOLOGIST R. Bliefertich	
SITE DESCRIPTION Site No. 4 - Bridge No. 279 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)							GROUND WTR (ft)
BORING NO. B2-B RL		STATION 227+97		OFFSET 77 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 24.4 ft		TOTAL DEPTH 108.6 ft		NORTHING 412,487		EASTING 2,620,527	
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018				DRILL METHOD Mud Rotary		HAMMER TYPE Automatic	
DRILLER T. Donahue		START DATE 05/22/18		COMP. DATE 05/23/18		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
-55																
	-59.1	83.5	7	6	9											
	-64.1	88.5	12	22	40											
	-69.1	93.5	8	5	11											
	-74.1	98.5	11	11	14											
	-79.1	103.5	22	10	36											
	-84.1	108.5	100/0.1													

NCDOT BORE DOUBLE EC18-161G_R-1015_SITE 4.GPJ_NC_DOT.GDT 7/19/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34360.1.2		TIP R-1015		COUNTY CRAVEN		GEOLOGIST R. Bliefertich	
SITE DESCRIPTION Site No. 4 - Bridge No. 279 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)							GROUND WTR (ft)
BORING NO. EB2-B RL		STATION 228+36		OFFSET 80 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 27.1 ft		TOTAL DEPTH 100.0 ft		NORTHING 412,508		EASTING 2,620,492	
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER T. Donahue		START DATE 05/22/18		COMP. DATE 05/23/18		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
30																
27.1	27.1	0.0	1	2	2									27.1	GROUND SURFACE	0.0
25														24.1	ARTIFICIAL FILL Low Plasticity, Soft, Black, Clayey, SILT with Fine to Coarse Sand and Trace Organics	3.0
22.1	22.1	5.0	1	2	3									19.6	UNDIVIDED COASTAL PLAIN Low Plasticity, Loose, Gray, Clayey, SAND with Silt and Trace Wood Fragments	7.5
20														19.6	UNDIVIDED COASTAL PLAIN Non Plastic, Loose to Medium Dense, Gray, Fine to Medium SAND with Trace Silt	7.5
18.6	18.6	8.5	2	4	5											
15																
13.6	13.6	13.5	5	6	9											
10																
8.6	8.6	18.5	2	4	4											
5																
3.6	3.6	23.5	5	8	7											
0																
-1.4	-1.4	28.5	3	2	5									0.6	UNDIVIDED COASTAL PLAIN Non Plastic to Low Plasticity, Loose to Medium Dense, Gray, Silty, Fine to Coarse SAND with Trace Clay	26.5
-5																
-6.4	-6.4	33.5	5	6	6											
-10																
-11.4	-11.4	38.5	4	4	7											
-15																
-16.4	-16.4	43.5	5	5	5											
-20																
-21.4	-21.4	48.5	2	3	3											
-25																
-26.4	-26.4	53.5	2	3	2											
-30																
-31.4	-31.4	58.5	4	4	2											
-35																
-36.4	-36.4	63.5	3	3	3											
-40																
-41.4	-41.4	68.5	2	3	3											
-45																
-46.4	-46.4	73.5	1	2	3											
-50																

WBS 34360.1.2		TIP R-1015		COUNTY CRAVEN		GEOLOGIST R. Bliefertich	
SITE DESCRIPTION Site No. 4 - Bridge No. 279 On -L- (US 70 Havelock Bypass) Over -RR EY2- (Camp Lejeune Railroad)							GROUND WTR (ft)
BORING NO. EB2-B RL		STATION 228+36		OFFSET 80 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 27.1 ft		TOTAL DEPTH 100.0 ft		NORTHING 412,508		EASTING 2,620,492	
DRILL RIG/HAMMER EFF./DATE GET0674 CME-45C 93% 03/22/2018			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER T. Donahue		START DATE 05/22/18		COMP. DATE 05/23/18		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-50															
-51.4	-51.4	78.5	30	100	0.4										
-55															
-56.4	-56.4	83.5	15	12	4										
-60															
-61.4	-61.4	88.5	4	3	4										
-65															
-66.4	-66.4	93.5	53	14	50										
-70															
-71.4	-71.4	98.5	10	9	8										

-50		Match Line					
-54.4		81.5		COASTAL PLAIN		Non Plastic, Loose to Very Dense, Gray, Calcareous, Silty, Fine to Coarse SAND with Trace to Little Cemented Sand Fragments, Trace to Little Marine Shell Fragments, Trace Fine to Medium Gravel, and Trace Clay ("Duplin Formation")	
-59.4		96.5		COASTAL PLAIN SEDIMENTARY ROCK		Soft, Gray, LIMESTONE with Trace Marine Shell Fragments ("River Bend Formation")	
-72.9		100.0				Boring Terminated at Elevation -72.9 ft in Soft, LIMESTONE with Trace Marine Shell Fragments ("River Bend Formation")	
				Other Samples:		ST-2 (50.0 - 52.0) ST-3 (60.0 - 62.0)	

NCDOT BORE DOUBLE EC18-161G_R-1015_SITE 4.GPJ_NC_DOT.GDT 7/19/18

BRIDGE 0278

SOIL TEST RESULTS EB1-A LL

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
ST-1	68 FT LT	226+59	50.0 - 52.0	A-4(0)	29	3	3.8	51.5	16.1	28.7	99	97	57	35	==
SS-14	68 FT LT	226+59	63.5 - 65.0	A-7-5(69)	101	71	2.8	5.8	29.3	62.1	91	89	86	61	==
SS-18	68 FT LT	226+59	83.5 - 85.0	A-2-4(0)	NV	NP	13.4	69.0	11.7	6.0	91	90	18	25	==

SOIL TEST RESULTS B1-A LL

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-38	67 FT LT	227+07	73.5 - 75.0	A-2-4	NV	NP	--	--	--	--	--	--	13	15	--

SOIL TEST RESULTS B2-A LL

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-47	67 FT LT	228+13	13.5 - 15.0	A-3	NV	NP	8.6	88.5	0.9	2.0	100	99	3	24	--
SS-55	67 FT LT	228+13	53.5 - 55.0	A-2-4(0)	NV	NP	41.0	33.8	9.2	15.9	86	59	25	25	--

SOIL TEST RESULTS EB2-A LL

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-72	72 FT LT	228+42	28.5 - 30.0	A-2-4(0)	NV	NP	7.7	76.4	4.9	10.9	100	100	17	29	--
SS-76	72 FT LT	228+42	48.5 - 50.0	A-2-4(0)	NV	NP	9.1	66.6	10.3	14.0	95	89	34	28	--

BRIDGE 0279

SOIL TEST RESULTS EB1-B RL

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-98	73 FT RT	226+46	58.5 - 60.0	A-6(1)	34	14	--	--	--	--	--	--	38	28	--
SS-100	73 FT RT	226+46	68.5 - 70.0	A-2-4(0)	26	9	27.5	44.3	10.1	18.1	86	77	32	25	--

SOIL TEST RESULTS B1-B RL

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-113	74 FT RT	226+88	28.5 - 30.0	A-3	NV	NP	4.4	86.6	2.0	7.0	100	100	10	25	--
SS-121	74 FT RT	226+88	68.5 - 70.0	A-2-4(0)	NV	NP	42.2	45.0	7.1	5.8	98	83	13	22	--

SOIL TEST RESULTS B2-B RL

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-134	77 FT RT	227+97	18.5 - 20.0	A-3	NV	NP	68.6	24.7	1.7	5.0	100	68	8	24	--
SS-141	77 FT RT	227+97	53.5 - 55.0	A-2-4(0)	29	8	25.9	42.1	11.9	20.1	69	57	27	29	--

SOIL TEST RESULTS EB2-B RL

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-153	80 FT RT	228+36	0.0 - 1.5	A-4(0)	NV	NP	11.3	55.9	15.3	17.6	100	98	36	23	3.9
SS-163	80 FT RT	228+36	48.5 - 50.0	A-2-7(0)	47	29	--	--	--	--	--	--	21	31	--
ST-2	80 FT RT	228+36	50.0 - 52.0	A-6(2)	39	16	3.6	67.5	8.5	20.3	99	98	39	34	--
SS-165	80 FT RT	228+36	58.5 - 60.0	A-2-4(0)	29	7	--	--	--	--	--	--	25	30	--
ST-3	80 FT RT	228+36	60.0 - 62.0	A-7-6(53)	75	48	1.6	7.5	25.8	65.1	99	98	95	57	--

SITE PHOTOGRAPHS

Bridge 0278 LEFT BRIDGE




VIEW AT EB1-A LL ALONG -L-
FACING UP-STATIONING TOWARDS B1-A LL
AND -RR EY2-
(CAMP LEJEUNE RAILROAD)



VIEW AT EB2-A LL ALONG -L-
FACING DOWN-STATIONING TOWARDS B2-A LL
AND -RR EY2-
(CAMP LEJEUNE RAILROAD)

SITE PHOTOGRAPHS

Bridge 0279 RIGHT BRIDGE



VIEW AT EB1-B RL ALONG -L-
FACING UP-STATIONING TOWARDS B1-B RL
AND -RR EY2-
(CAMP LEJEUNE RAILROAD)



VIEW AT EB2-B RL ALONG -L-
FACING DOWN-STATIONING TOWARDS B2-B RL
AND -RR EY2-
(CAMP LEJEUNE RAILROAD)

REFERENCE: R-1015

PROJECT: 34360

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY CRAVEN
PROJECT DESCRIPTION US 70 (Havelock Bypass) from North
of Pine Grove to North of Carteret County Line

SITE DESCRIPTION MSE Retaining Walls 3 & 4: Site No. 9
- Dual Bridges on US 70 over 70 Business between SR 1747
and SR 1176 - Station 516+87.37 -L- / 69+02.79 -RP2AC-

CONTENTS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4-5	PROFILES
6	SOIL TEST RESULTS

APPENDICES

APPENDIX	TITLE	SHEETS
A	CONSOLIDATION & TRIAXIAL TESTS RESULTS	7-35

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	R-1015	1	35

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF PREPARING THE SCOPE OF WORK TO BE INCLUDED IN THE REQUEST FOR PROPOSAL. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

SOIL AND ROCK BOUNDARIES WITHIN A BOREHOLE ARE BASED ON GEOTECHNICAL INTERPRETATION UNLESS ENCOUNTERED IN A SAMPLE. INTERPRETED BOUNDARIES MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN SAMPLED STRATA AND BOREHOLE INFORMATION MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

P.M. WEAVER

C.R. PASTRANA

GET Solutions

INVESTIGATED BY ESP Associates, INC.


DRAWN BY C.R. PASTRANA

CHECKED BY P.M. WEAVER

SUBMITTED BY ESP Associates, INC.

DATE August 2018

 **ESP**
 ESP ASSOCIATES, INC.
 7011 ALBERT PICK RD
 SUITE E
 GREENSBORO, NC 27409
 FIRM # C-0587
 WWW.ESPASSOCIATES.COM





DocuSigned by:
Paul M. Weaver 8/28/2018
 01847D3739804040 DATE

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS


Table with 4 main columns: SOIL DESCRIPTION, GRADATION, ROCK DESCRIPTION, and TERMS AND DEFINITIONS. Includes sub-sections like SOIL LEGEND AND AASHTO CLASSIFICATION, CONSISTENCY OR DENSENESS, TEXTURE OR GRAIN SIZE, SOIL MOISTURE - CORRELATION OF TERMS, PLASTICITY, COLOR, MISCELLANEOUS SYMBOLS, RECOMMENDATION SYMBOLS, ABBREVIATIONS, EQUIPMENT USED ON SUBJECT PROJECT, FRACTURE SPACING, BEDDING, and INDURATION.

PROJECT REFERENCE NO.	SHEET NO.
R-1015	3
SITE PLAN	
SITE 9 BRIDGE SKEW = 126°41' 28" MSE RETAINING WALLS 3 & 4	




- BRIDGE SUPERSTRUCTURES NOT SHOWN FOR CLARITY.

REFERENCE "R1015_GEO_BRDG_Site9_Inventor Report" FOR BRIDGE DETAILS



PROJECT REFERENCE NO.	SHEET NO.
R-1015	5
SITE 9: END BENT 2 PROFILE ALONG MSE RETAINING WALL 4	



- (B) Undivided Coastal Plain: Brown to Gray, Very Soft to Soft, Sandy CLAY and Silty CLAY, Wet to Saturated
- (D) Alluvial: Black and Brown, Very Soft, Sandy CLAY, Moderately Organic, Wet
- (E) Alluvial: Black, Loose, Silty SAND, Little Organics, Saturated

- GROUNDLINE AND WALL PROFILE TAKEN FROM "R-1015 MSE WALL_END BENT 2_Site 9.dgn"
 FILE PROVIDED BY NCDOT DATED 5/21/2018.
 - INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH
 PROJECTED ONTO THE WALL PROFILE.
 - ALL DIMENSIONS AND STATIONS ARE ALONG FRONT FACE OF WALL.

-WALL_4-

SOILS LABORATORY TESTS RESULTS

WBS NO.: 34360.1.1

TIP NO.: R-1015

COUNTY: Craven

SITE DESCRIPTION: Site #9 - Dual Bridges on US 70 (Havelock Bypass) over US 70 Business - MSE Wall Abutments

BORING NO.	SAMPLE NO.	Boring Location			DEPTH INTERVAL (FT)	AASHTO	N	L.L	P.I.	% BY WEIGHT				% PASSING SIEVES			% MOISTURE	% ORGANIC
		Alignment	Station	Offset						CSE. SAND	F. SAND	SILT	CLAY	10	40	200		
EB1-A LL	SS-1	-WALL_3-	13+10	7' LT	53.0-54.5	A-2-4 (0)	9	NP	NP	29	50	6	15	80	67	18	30.8	-
EB1-B LL	SS-2	-WALL_4-	12+38	6' LT	13.0-14.5	A-3 (1)	4	NP	NP	27	66	2	5	100	98	8	-	-
EB1-B RL	SS-3	-WALL_3-	11+47	7' LT	3.2-4.7	A-2-4 (0)	8	NP	NP	36	50	2	12	100	79	15	-	-
EB1-B RL	SS-4	-WALL_3-	11+47	7' LT	48.2-49.7	A-2-4 (0)	0	NP	NP	68	21	3	8	99	64	11	26.1	0.5
EB2-A LL	SS-9	-WALL_4-	11+01	5' LT	48.5-50.0	A-2-4 (0)	9	NP	NP	12	67	7	14	100	93	27	31.0	-
EB2-B RL	SS-10	-WALL_4-	12+66	7' LT	18.5-20.0	A-2-4 (0)	6	NP	NP	7	79	5	9	100	97	17	31.1	-
RWAL3-1	SS-11	-WALL_3-	13+84	CL	3.5-5.0	A-2-4 (0)	8	NP	NP	13	65	11	11	100	98	23	14.2	-
RWAL3-2	SS-12	-WALL_3-	13+34	CL	3.0-4.5	A-2-4 (0)	7	NP	NP	11	72	10	7	100	98	18	13.1	-
RWAL3-3	SS-13	-WALL_3-	11+93	CL	14.2-15.7	A-3 (1)	14	NP	NP	29	68	0	3	100	89	5	21.8	-
RWAL3-4	SS-14	-WALL_3-	10+97	CL	13.0-14.5	A-2-4 (0)	4	24	10	18	48	22	12	99	92	35	29.8	-
RWAL3-6	SS-15	-WALL_3-	10+00	CL	3.1-4.6	A-2-4 (0)	7	NP	NP	7	70	2	21	100	99	24	19.4	-
RWAL4-2	SS-16	-WALL_4-	13+16	CL	3.1-4.6	A-2-4 (0)	7	NP	NP	9	69	3	19	100	98	23	16.8	-
RWAL4-3	SS-17	-WALL_4-	12+31	1' LT	1.0-2.5	A-2-4 (0)	5	24	8	6	66	16	12	100	99	29	20.4	-
RWAL4-4	SS-18	-WALL_4-	11+45	CL	1.0-2.5	A-2-4 (0)	4	NP	NP	7	71	8	14	100	99	24	25.7	3.9
RWAL4-4	SS-19	-WALL_4-	11+45	CL	28.0-29.5	A-3 (1)	26	NP	NP	62	32	2	4	100	65	8	17.9	-
RWAL4-5	SS-20	-WALL_4-	10+50	CL	8.5-10.0	A-7-6 (17)	1	41	21	2	17	61	20	100	99	84	68.6	-
RWAL4-6	SS-21	-WALL_4-	10+00	CL	3.0-4.5	A-2-4 (0)	6	NP	NP	8	74	2	16	100	98	19	21.6	-
-	ST-1	-L-	516+16	16' LT	4.0-6.0	A-6 (7)	N/A	31	18	6	39	20	35	100	98	57	34.6	-
-	ST-2	-L-	517+11	59' RT	11.0-13.0	A-2-4 (0)	N/A	NP	NP	6	84	1	9	100	98	11	23.6	-
-	ST-3	-L-	517+15	23' RT	9.8-11.8	A-7-6 (36)	N/A	65	44	2	20	27	51	100	99	79	64.2	-

Jorge Dumoncia
 Certification No. 121-01-1108

For all test samples but ST-3

Signed: *Sam F. Jarr*

NCDOT Certification No. 129-04-0411
 For test sample ST-3

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
APPENDIX A
CONSOLIDATION & TRIAXIAL TESTS RESULTS


REFERENCE: R-1015

PROJECT: 34360

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client	ESP Associates	Boring No.	-L- STA. 516+16, 16'LT
Client Reference	R-1015 Site 9 - CS34.327.00	Depth (ft)	4.0-6.0
Project No.	R-2018-095-001	Sample No.	ST-1
Lab ID	R-2018-095-001-002	Visual Description	LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Tested By 129-04-0411 Date 4/10/18 Approved By MPS Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client	ESP Associates	Boring No.	-L- STA. 516+16, 16'LT
Client Reference	R-1015 Site 9 - CS34.327.00	Depth (ft)	4.0-6.0
Project No.	R-2018-095-001	Sample No.	ST-1
Lab ID	R-2018-095-001-002	Visual Description	LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED

Consolidometer No. R409
1 Division = 0.0001 (in.)

Sample Properties

	Initial	Final
<i>Water Content</i>		
Tare Number	SS-6	800
Wt. Tare & WS (g)	313.18	232.09
Wt. Tare & DS (g)	267.85	206.50
Wt. Water (g)	45.33	25.59
Wt. Tare (g)	100.77	103.09
Wt. DS (g)	167.08	103.41
Water Content (%)	27.13	24.75
<i>Sample Parameters</i>		
Sample Diameter (in)	2.5	2.5
Sample Height (in)	1.0000	0.8822
Sample Volume (cc)	80.44	70.96
Wt. Wet Sample + Ring (g)	247.89	245.20
Wt. of Ring (g)	104.49	104.49
Wt. of Wet Sample (g)	143.40	140.71
Wet Density (pcf)	111.24	123.73
Wet Density (g/cc)	1.78	1.98
Water Content (%)	27.13	24.75
Wt. of Dry Sample (g)	112.80	112.80
Dry Density (pcf)	87.50	99.19
Dry Density (g/cc)	1.40	1.59
Void Ratio	0.8755	0.6546
Saturation (%)	81.50	99.42
Specific Gravity	2.63	Measured


Test Data Summary

Applied Pressure (tsf)	Final Dial Reading (div)	Machine Deflection (div)	Corrected Reading (div)	Height of Sample (mm)	Volume (cc)	Dry Density (g/cc)	Void Ratio
Seating	0	0	0	25.400	80.440	1.40226	0.87555
0.125	51.5	7.5	44.1	25.288	80.085	1.40846	0.86728
0.25	106.2	18.6	87.6	25.178	79.735	1.41465	0.85912
0.5	247.8	33.9	214.0	24.856	78.719	1.43292	0.83541
1	469.4	55.5	413.9	24.349	77.111	1.46280	0.79793
2	789.6	86.4	703.2	23.614	74.783	1.50832	0.74366
4	1218.3	125.8	1092.4	22.625	71.652	1.57423	0.67066
8	1734.8	168.6	1566.2	21.422	67.841	1.66267	0.58179
2	1584.7	109.7	1475.0	21.654	68.575	1.64487	0.59891
0.5	1391.9	67.4	1324.5	22.036	69.785	1.61634	0.62713
0.25	1297.5	60.3	1237.2	22.258	70.488	1.60024	0.64351
0.125	1238.4	60.3	1178.1	22.408	70.963	1.58951	0.65459

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client	ESP Associates	Boring No.	-L- STA. 516+16, 16'LT
Client Reference	R-1015 Site 9 - CS34.327.00	Depth (ft)	4.0-6.0
Project No.	R-2018-095-001	Sample No.	ST-1
Lab ID	R-2018-095-001-002	Visual Description	LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Coefficient of Consolidation (cm²/sec)

◆ First Cycle Up

page 3 of 4 DCN: CT-24E Date: 5/3/12 Revision: 6 Tested By 129-04-0411 Date 4/10/18 Input Checked By GEM Date 5/15/18

Z:\2018 PROJECTS\ESP Associates\2018-095 ESP - R-1015 SITE 9\2018-095-001-002 GEOJAC-16TST1 Cv.xls\m\FINAL PLOT

2200 Westinghouse Blvd., Suite 103 • Raleigh, NC 27604 • Phone (919) 876-0405 • Fax (919) 876-0460 • www.geotechnics.net

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client	ESP Associates	Boring No.	-L- STA. 516+16, 16'LT
Client Reference	R-1015 Site 9 - CS34.327.00	Depth (ft)	4.0-6.0
Project No.	R-2018-095-001	Sample No.	ST-1
Lab ID	R-2018-095-001-002	Visual Description	LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED

Consolidometer No. R409

1 Division = 0.0001 (in.)

Sample Properties

Water Content			
Tare Number	SS-6	Initial	Final
Wt. Tare & WS (g)	313.18	800	
Wt. Tare & DS (g)	267.85	232.09	
Wt. Water (g)	45.33	25.59	
Wt. Tare (g)	100.77	103.09	
Wt. DS (g)	167.08	103.41	
Water Content (%)	27.13	24.75	

Sample Parameters

Sample Diameter (in)	2.5	2.5
Sample Height (in)	1.000	0.882
Sample Volume (cc)	80.44	70.96
Wt. of Wet Sample + Ring (g)	247.89	245.20
Wt. of Ring (g)	104.49	104.49
Wt. of Wet Sample (g)	143.40	140.71
Wet Density (pcf)	111.24	123.73
Wet Density (g/cc)	1.78	1.98
Water Content (%)	27.13	24.75
Wt. of Dry Sample (g)	112.80	112.80
Dry Density (pcf)	87.50	99.19
Dry Density (g/cc)	1.40	1.59
Void Ratio	0.8755	0.6546
Saturation (%)	81.50	99.42
Specific Gravity	2.63	Measured

Load Increment (tsf)	Dial Reading @ t ₅₀ (div)	Machine Deflection (div)	C _v Test Data Summary	
			Corrected Dial Reading @ t ₅₀ (div)	Sample Height @ t ₅₀ (cm)
0.0 - 0.125	25.0	7.5	17.5	2.536
0.125 - 0.25	75.4	18.6	56.8	2.526
0.25 - 0.5	173.7	33.9	139.8	2.504
0.5 - 1	358.5	55.5	303.0	2.463
1 - 2	627.9	86.4	541.4	2.402
2 - 4	995.3	125.8	869.4	2.319
4 - 8	1462.1	168.6	1293.5	2.211
8 - 2	NA	109.7	NA	NA
2 - 0.5	NA	67.4	NA	NA
0.5 - 0.25	NA	60.3	NA	NA
0.25 - 0.125	NA	60.3	NA	NA

Time t ₅₀ (min.)	C _v (cm ² /sec)
1.00	0.00528
2.30	0.00228
3.50	0.00147
3.50	0.00142
3.50	0.00135
3.80	0.00116
3.50	0.00115
NA	NA
NA	NA
NA	NA
NA	NA

page 4 of 4 DCN: CT-24E Date: 5/3/12 Revision: 6 Tested By 129-04-0411 Date 4/10/18 Input Checked By GEM Date 5/15/18

Z:\2018 PROJECTS\ESP Associates\2018-095 ESP - R-1015 SITE 9\2018-095-001-002 GEOJAC-16TST1 Cv.xls\m\FINAL PLOT


2200 Westinghouse Blvd., Suite 103 • Raleigh, NC 27604 • Phone (919) 876-0405 • Fax (919) 876-0460 • www.geotechnics.net

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client ESP Associates Boring No. -L- STA. 516+16, 16'LT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 4.0-6.0
 Project No. R-2018-095-001 Sample No. ST-1
 Lab ID R-2018-095-001-002 Visual Description LIGHT BROWN / GRAY CLAY


Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.0-0.125
Final Reading (div) 51.5
 Consolidometer No. **R409**
 1 Division (in) 0.0001

Start Date 4/10/18
 Start Time 17:10:38

Elapsed Time (min)	Dial Reading (div)
Initial	0.0
0.05	0.9
0.10	1.8
0.15	5.1
0.20	12.8
0.25	15.3
0.32	17.5
0.47	20.7
0.57	21.7
1.07	25.2
2.32	31.2
4.07	36.2
9.07	43.4
16.07	47.7
25.07	49.1
36.07	50.5
49.07	50.5
64.07	51.2
81.07	51.0
100.07	51.1
121.07	51.4
144.07	51.5




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client ESP Associates Boring No. -L- STA. 516+16, 16'LT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 4.0-6.0
 Project No. R-2018-095-001 Sample No. ST-1
 Lab ID R-2018-095-001-002 Visual Description LIGHT BROWN / GRAY CLAY


Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.125-0.25
Final Reading (div) 106.2
 Consolidometer No. **R409**
 1 Division (in) 0.0001

Start Date 4/11/18
 Start Time 0:11:01

Elapsed Time (min)	Dial Reading (div)
Initial	51.5
0.05	53.1
0.10	55.3
0.15	56.3
0.20	57.5
0.25	58.0
0.30	58.5
0.45	60.4
0.55	61.2
1.05	67.2
2.30	75.5
4.05	80.2
9.05	89.3
16.05	95.3
25.05	97.7
36.05	99.2
49.05	100.1
64.05	101.3
81.05	102.1
100.05	102.8
121.07	103.9
144.07	104.2
180.07	104.4
300.07	105.3
420.33	106.2



Tested By 129-04-0411 Date 4/10/18 Checked By GEM Date 5/15/18


Tested By 129-04-0411 Date 4/11/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Boring No. -L- STA. 516+16, 16'LT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 4.0-6.0
 Project No. R-2018-095-001 Sample No. ST-1
 Lab ID R-2018-095-001-002 Visual Description LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.25-0.5
Final Reading (div) 247.8
 Consolidometer No. **R409**
 1 Division (in) 0.0001
 Start Date 4/11/18
 Start Time 7:11:21

Elapsed Time (min)	Dial Reading (div)
Initial	106.2
0.03	119.2
0.08	129.7
0.15	132.6
0.20	135.1
0.25	137.1
0.30	138.1
0.45	141.0
0.55	143.5
1.05	150.9
2.30	164.1
4.05	175.3
9.05	194.1
16.05	208.3
25.05	216.5
36.05	221.2
49.05	224.3
64.05	226.1
81.05	227.7
100.05	229.0
121.05	229.4
144.05	230.6
180.05	232.4
300.05	241.0
420.38	247.8




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Boring No. -L- STA. 516+16, 16'LT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 4.0-6.0
 Project No. R-2018-095-001 Sample No. ST-1
 Lab ID R-2018-095-001-002 Visual Description LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.5-1.0
Final Reading (div) 469.4
 Consolidometer No. **R409**
 1 Division (in) 0.0001
 Start Date 4/11/18
 Start Time 14:11:46

Elapsed Time (min)	Dial Reading (div)
Initial	247.8
0.05	268.6
0.10	280.8
0.15	284.3
0.20	286.4
0.25	289.0
0.30	291.2
0.45	299.6
0.55	304.4
1.05	317.0
2.30	342.7
4.05	364.2
9.05	394.8
16.05	422.3
25.05	435.3
36.05	441.5
49.05	445.7
64.07	452.7
81.07	458.5
100.07	461.5
121.07	463.9
144.07	465.0
180.07	466.1
300.07	469.4



Tested By 129-04-0411 Date 4/11/18 Checked By GEM Date 5/15/18


Tested By 129-04-0411 Date 4/11/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client: ESP Associates Boring No.: -L- STA. 516+16, 16'LT
 Client Project: R-1015 Site 9 - CS34.327.00 Depth (ft): 4.0-6.0
 Project No.: R-2018-095-001 Sample No.: ST-1
 Lab ID: R-2018-095-001-002 Visual Description: LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 1.0-2.0
 Final Reading (div) 789.6
 Consolidometer No. R409
 1 Division (in) 0.0001
 Start Date 4/11/18
 Start Time 21:12:10

Elapsed Time (min)	Dial Reading (div)
Initial	469.4
0.03	486.0
0.10	503.2
0.15	510.3
0.20	519.1
0.25	525.0
0.30	527.9
0.45	535.0
0.55	539.6
1.05	564.3
2.30	602.3
4.05	638.8
9.07	691.3
16.07	732.0
25.07	752.0
36.07	759.4
49.07	767.0
64.07	772.5
81.07	777.2
100.07	778.1
121.07	779.3
144.07	780.3
180.07	782.7
300.07	786.9
420.35	789.6




Tested By 129-04-0411 Date 4/11/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client: ESP Associates Boring No.: -L- STA. 516+16, 16'LT
 Client Project: R-1015 Site 9 - CS34.327.00 Depth (ft): 4.0-6.0
 Project No.: R-2018-095-001 Sample No.: ST-1
 Lab ID: R-2018-095-001-002 Visual Description: LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 2.0-4.0
 Final Reading (div) 1218.3
 Consolidometer No. R409
 1 Division (in) 0.0001
 Start Date 4/12/18
 Start Time 4:12:32

Elapsed Time (min)	Dial Reading (div)
Initial	789.6
0.05	824.7
0.10	835.9
0.15	849.0
0.20	856.1
0.25	861.6
0.30	867.5
0.45	879.6
0.55	884.3
1.07	917.7
2.32	960.9
4.07	1007.6
9.07	1076.8
16.07	1127.2
25.07	1157.1
36.07	1174.0
49.07	1183.0
64.07	1189.5
81.07	1194.8
100.07	1199.5
121.07	1201.6
144.07	1203.5
180.07	1206.8
300.07	1214.1
370.07	1218.3




Tested By 129-04-0411 Date 4/12/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client: ESP Associates Boring No.: -L- STA. 516+16, 16'LT
 Client Project: R-1015 Site 9 - CS34.327.00 Depth (ft): 4.0-6.0
 Project No.: R-2018-095-001 Sample No.: ST-1
 Lab ID: R-2018-095-001-002 Visual Description: LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf): 4.0-8.0
Final Reading (div): 1734.8
 Consolidometer No.: **R409**
 1 Division (in): 0.0001
 Start Date: 4/12/18
 Start Time: 10:22:37

Elapsed Time (min)	Dial Reading (div)
Initial	1218.3
0.05	1259.8
0.10	1287.1
0.15	1291.8
0.20	1300.6
0.25	1308.3
0.30	1316.3
0.45	1330.3
0.55	1339.3
1.05	1372.4
2.30	1427.1
4.07	1479.2
9.07	1564.0
16.07	1624.1
25.07	1658.9
36.07	1672.8
49.07	1690.1
64.07	1696.7
81.07	1700.9
100.07	1704.6
121.07	1708.6
144.07	1713.2
180.07	1718.7
300.07	1729.9
420.22	1734.8




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client: ESP Associates Boring No.: -L- STA. 516+16, 16'LT
 Client Project: R-1015 Site 9 - CS34.327.00 Depth (ft): 4.0-6.0
 Project No.: R-2018-095-001 Sample No.: ST-1
 Lab ID: R-2018-095-001-002 Visual Description: LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf): 8.0-2.0
Final Reading (div): 1584.7
 Consolidometer No.: **R409**
 1 Division (in): 0.0001
 Start Date: 4/12/18
 Start Time: 17:22:50

Elapsed Time (min)	Dial Reading (div)
Initial	1734.8
0.05	1686.6
0.10	1673.8
0.15	1669.6
0.20	1668.1
0.27	1664.9
0.32	1661.5
0.47	1659.2
0.57	1656.8
1.07	1647.8
2.32	1631.6
4.07	1622.9
9.07	1611.7
16.07	1602.9
25.07	1598.7
36.07	1596.2
49.07	1593.8
64.07	1591.9
81.07	1590.7
100.07	1589.7
121.07	1589.0
144.08	1587.6
180.08	1587.7
300.08	1585.9
420.20	1584.7



Tested By 129-04-0411 Date 4/12/18 Checked By GEM Date 5/15/18


Tested By 129-04-0411 Date 4/12/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client: ESP Associates Boring No.: -L- STA. 516+16, 16'LT
 Client Project: R-1015 Site 9 - CS34.327.00 Depth (ft): 4.0-6.0
 Project No.: R-2018-095-001 Sample No.: ST-1
 Lab ID: R-2018-095-001-002 Visual Description: LIGHT BROWN / GRAY CLAY


Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf): 2.0-0.5
Final Reading (div): 1391.9
 Consolidometer No.: **R409**
 1 Division (in): 0.0001

Start Date: 4/13/18
 Start Time: 0:23:02

Elapsed Time (min)	Dial Reading (div)
Initial	1584.7
0.03	1560.5
0.08	1555.4
0.15	1553.1
0.20	1552.7
0.25	1551.8
0.30	1547.3
0.45	1545.1
0.55	1542.1
1.05	1532.5
2.30	1523.5
4.05	1503.8
9.05	1479.3
16.05	1460.0
25.05	1441.3
36.05	1428.7
49.05	1420.5
64.05	1414.5
81.05	1409.8
100.05	1407.3
121.05	1404.6
144.05	1402.9
180.05	1400.0
300.05	1395.7
420.33	1391.9




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client: ESP Associates Boring No.: -L- STA. 516+16, 16'LT
 Client Project: R-1015 Site 9 - CS34.327.00 Depth (ft): 4.0-6.0
 Project No.: R-2018-095-001 Sample No.: ST-1
 Lab ID: R-2018-095-001-002 Visual Description: LIGHT BROWN / GRAY CLAY


Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf): 0.5-0.25
Final Reading (div): 1297.5
 Consolidometer No.: **R409**
 1 Division (in): 0.0001

Start Date: 4/13/18
 Start Time: 7:23:23

Elapsed Time (min)	Dial Reading (div)
Initial	1391.9
0.05	1388.1
0.10	1385.8
0.15	1384.8
0.20	1384.3
0.25	1383.5
0.30	1383.1
0.45	1383.0
0.55	1381.9
1.05	1379.9
2.32	1376.8
4.07	1374.7
9.07	1367.3
16.07	1362.2
25.07	1355.6
36.07	1350.1
49.07	1347.2
64.07	1343.0
81.07	1339.0
100.07	1335.3
121.07	1332.4
144.07	1328.4
180.07	1327.3
300.07	1323.2
520.07	1317.6
700.08	1313.2
960.08	1305.0
1440.02	1297.5



Tested By 129-04-0411 Date 4/13/18 Checked By GEM Date 5/15/18



Tested By 129-04-0411 Date 4/13/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client	ESP Associates	Boring No.	-L- STA. 516+16, 16'LT
Client Project	R-1015 Site 9 - CS34.327.00	Depth (ft)	4.0-6.0
Project No.	R-2018-095-001	Sample No.	ST-1
Lab ID	R-2018-095-001-002	Visual Description	LIGHT BROWN / GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf)	0.25-0.125
Final Reading (div)	1238.4
Consolidometer No.	R409
1 Division (in)	0.0001
Start Date	4/14/18
Start Time	7:23:25


Elapsed Time (min)	Dial Reading (div)
Initial	1297.5
0.05	1295.3
0.10	1294.7
0.15	1294.7
0.20	1294.5
0.25	1294.6
0.30	1294.0
0.45	1293.5
0.55	1293.1
1.05	1292.5
2.30	1291.2
4.05	1290.4
9.05	1287.5
16.05	1285.8
25.05	1283.6
36.05	1280.6
49.05	1277.9
64.05	1276.1
81.05	1274.4
100.05	1272.4
121.05	1269.8
144.05	1264.1
180.05	1259.8
300.05	1255.7
520.05	1253.8
700.05	1253.2
960.05	1248.1
1440.05	1243.9
1680.07	1243.6
1920.05	1243.3
2160.07	1240.1
2400.07	1238.4



ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client	ESP Associates	Boring No.	-L- STA. 517+11, 59'RT
Client Reference	R-1015 Site 9 - CS34.327.00	Depth (ft)	11.0-13.0
Project No.	R-2018-095-001	Sample No.	ST-2
Lab ID	R-2018-095-001-011	Visual Description	GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Tested By 129-04-0411 Date 4/14/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client: ESP Associates Boring No.: -L- STA. 517+11, 59RT
 Client Reference: R-1015 Site 9 - CS34.327.00 Depth (ft): 11.0-13.0
 Project No.: R-2018-095-001 Sample No.: ST-2
 Lab ID: R-2018-095-001-011 Visual Description: GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED

Consolidometer No.: R470
1 Division = 0.0001 (in.)

Sample Properties **Initial** **Final**

Water Content
 Tare Number: TB-08 815
 Wt. Tare & WS (g): 485.43 287.95
 Wt. Tare & DS (g): 418.64 259.52
 Wt. Water (g): 66.79 28.43
 Wt. Tare (g): 135.33 135.83
 Wt. DS (g): 283.31 123.69
 Water Content (%): 23.57 22.98

Sample Parameters
 Sample Diameter (in): 2.5 2.5
 Sample Height (in): 1.0000 0.9866
 Sample Volume (cc): 80.44 79.36
 Wt. Wet Sample + Ring (g): 371.31 370.56
 Wt. of Ring (g): 214.30 214.30
 Wt. of Wet Sample (g): 157.01 156.26
 Wet Density (pcf): 121.80 122.87
 Wet Density (g/cc): 1.95 1.97
 Water Content (%): 23.57 22.98
 Wt. of Dry Sample (g): 127.06 127.06
 Dry Density (pcf): 98.56 99.90
 Dry Density (g/cc): 1.58 1.60
 Void Ratio: 0.6714 0.6490
 Saturation (%): 92.70 93.50
 Specific Gravity: 2.64 Measured

Test Data Summary

Applied Pressure (tsf)	Final Dial Reading (div)	Machine Deflection (div)	Corrected Reading (div)	Height of Sample (mm)	Volume (cc)	Dry Density (g/cc)	Void Ratio
Seating	0	0	0	25.400	80.440	1.57952	0.67139
0.125	24.4	4.2	20.2	25.349	80.278	1.58272	0.66802
0.25	49.9	13.1	36.9	25.306	80.143	1.58537	0.66523
0.5	81.7	27.4	54.3	25.262	80.003	1.58815	0.66231
1	125.6	51.0	74.5	25.211	79.840	1.59138	0.65893
2	184.5	87.1	97.4	25.153	79.656	1.59506	0.65511
4	254.4	124.7	129.7	25.071	79.396	1.60028	0.64971
8	337.6	163.1	174.5	24.957	79.036	1.60758	0.64222
2	276.1	103.0	173.1	24.960	79.047	1.60734	0.64246
0.5	227.0	55.9	171.1	24.965	79.063	1.60703	0.64279
0.25	204.7	48.4	156.3	25.003	79.183	1.60460	0.64527
0.125	182.6	48.4	134.2	25.059	79.361	1.60100	0.64897

page 2 of 2 DCN: CT-24E Date: 5/3/12 Revision: 6 Tested By: 129-04-0411 Date: 4/17/18 Input Checked By: GEM Date: 5/15/18

Z:\2018 PROJECTS\ESP Associates\2018-095 ESP - R-1015 SITE 9\2018-095-001-011 GEOJAC-16TSF1 Cv.xlsm\FINAL_PLOT


2200 Westinghouse Blvd., Suite 103 • Raleigh, NC 27604 • Phone (919) 876-0405 • Fax (919) 876-0460 • www.geotechnics.net

ONE DIMENSIONAL CONSOLIDATION

AASHTO T-216

Client: ESP Associates Boring No.: -L- STA. 517+11, 59RT
 Client Reference: R-1015 Site 9 - CS34.327.00 Depth (ft): 11.0-13.0
 Project No.: R-2018-095-001 Sample No.: ST-2
 Lab ID: R-2018-095-001-011 Visual Description: GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Coefficient of Consolidation (cm²/sec)

— First Cycle Up

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client: ESP Associates
 Client Reference: R-1015 Site 9 - CS34.327.00
 Project No.: R-2018-095-001
 Lab ID: R-2018-095-001-011

Boring No.: -L- STA. 517+11, 59'RT
 Depth (ft): 11.0-13.0
 Sample No.: ST-2
 Visual Description: GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED

Consolidometer No. R470
 1 Division = 0.0001 (in.)

Sample Properties	Initial	Final
Water Content		
Tare Number	TB-08	815
Wt. Tare & WS (g)	485.43	287.95
Wt. Tare & DS (g)	418.64	259.52
Wt. Water (g)	66.79	28.43
Wt. Tare (g)	135.33	135.83
Wt. DS (g)	283.31	123.69
Water Content (%)	23.57	22.98
Sample Parameters		
Sample Diameter (in)	2.5	2.5
Sample Height (in)	1.000	0.987
Sample Volume (cc)	80.44	79.36
Wt. Wet Sample + Ring (g)	371.31	370.56
Wt. of Ring (g)	214.30	214.30
Wt. of Wet Sample (g)	157.01	156.26
Wet Density (pcf)	121.80	122.87
Wet Density (g/cc)	1.95	1.97
Water Content (%)	23.57	22.98
Wt. of Dry Sample (g)	127.06	127.06
Dry Density (pcf)	98.56	99.90
Dry Density (g/cc)	1.58	1.60
Void Ratio	0.6714	0.6490
Saturation (%)	92.70	93.50
Specific Gravity	2.64	Measured

Load Increment (tsf)	Dial Reading @ t ₅₀ (div)	Machine Deflection (div)	Corrected Dial Reading @ t ₅₀ (div)	Sample Height @ t ₅₀ (cm)	Time t ₅₀ (min.)	C _v (cm ² /sec)
0.0 - 0.125	12.2	4.2	8.0	2.538	0.17	0.03110
0.125 - 0.25	38.7	13.1	25.6	2.534	0.12	0.04391
0.25 - 0.5	74.2	27.4	46.8	2.528	0.80	0.00656
0.5 - 1	117.3	51.0	66.2	2.523	0.48	0.01089
1 - 2	164.8	87.1	77.6	2.520	0.06	0.08690
2 - 4	235.6	124.7	110.9	2.512	0.07	0.07968
4 - 8	321.7	163.1	158.6	2.500	0.10	0.05399
8 - 2	NA	103.0	NA	NA	NA	NA
2 - 0.5	NA	55.9	NA	NA	NA	NA
0.5 - 0.25	NA	48.4	NA	NA	NA	NA
0.25 - 0.125	NA	48.4	NA	NA	NA	NA

Tested By: 129-04-0411 Date: 4/17/18 Input Checked By: GEM Date: 5/15/18

DCN: CT-24E Date: 5/3/12 Revision: 6 Z:\2018 PROJECTS\ESP Associates\2018-095 ESP - R-1015 SITE 9\2018-095-001-011 GEOJAC-16TSF1 Cv.xlsm\FINAL PLOT

2200 Westinghouse Blvd., Suite 103 • Raleigh, NC 27604 • Phone (919) 876-0405 • Fax (919) 876-0460 • www.geotechnics.net



page 4 of 4

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client: ESP Associates
 Client Project: R-1015 Site 9 - CS34.327.00
 Project No.: R-2018-095-001
 Lab ID: R-2018-095-001-011

Boring No.: -L- STA. 517+11, 59'RT
 Depth (ft): 11.0-13.0
 Sample No.: ST-2
 Visual Description: GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.0-0.125
 Final Reading (div) 24.4
 Consolidometer No. R470
 1 Division (in) 0.0001

Start Date 4/17/18
 Start Time 10:32:22

Elapsed Time (min)	Dial Reading (div)
Initial	0.0
0.05	0.3
0.10	1.1
0.15	11.0
0.20	12.5
0.25	13.6
0.30	14.1
0.35	15.6
0.40	15.8
0.45	17.1
0.50	19.7
0.55	19.8
0.60	22.4
0.65	17.6
0.70	23.0
0.75	18.6
0.80	19.0
0.85	20.0
0.90	21.4
0.95	22.3
1.00	22.6
1.05	23.8
1.10	24.4


Tested By: 129-04-0411 Date: 4/17/18 Checked By: GEM Date: 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.125-0.25
 Final Reading (div) 49.9
 Consolidometer No. R470
 1 Division (in) 0.0001
 Start Date 4/17/18
 Start Time 13:32:46

Elapsed Time (min)	Dial Reading (div)
Initial	24.4
0.05	36.8
0.10	38.1
0.15	38.8
0.20	39.3
0.25	39.5
0.30	39.6
0.45	40.1
0.55	40.1
1.07	40.9
2.32	41.5
4.07	42.3
9.07	43.3
16.07	43.6
25.07	45.1
36.07	45.4
49.07	45.7
64.07	46.4
81.07	47.2
100.07	47.8
121.07	48.8
144.07	49.3
180.07	49.9
180.42	49.9




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.25-0.5
 Final Reading (div) 81.7
 Consolidometer No. R470
 1 Division (in) 0.0001
 Start Date 4/17/18
 Start Time 16:33:11

Elapsed Time (min)	Dial Reading (div)
Initial	49.9
0.03	69.7
0.08	71.3
0.13	71.9
0.18	72.5
0.25	72.9
0.30	72.9
0.45	73.4
0.55	73.8
1.05	74.4
2.30	74.9
4.05	75.8
9.05	76.9
16.05	77.6
25.05	78.7
36.05	78.8
49.05	80.2
64.05	80.9
81.05	81.1
100.05	81.4
121.05	81.2
144.05	81.5
180.05	81.5
180.32	81.7



Tested By 129-04-0411 Date 4/17/18 Checked By GEM Date 5/15/18


Tested By 129-04-0411 Date 4/17/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.5-1.0
Final Reading (div) 125.6
 Consolidometer No. **R470**
 1 Division (in) 0.0001
 Start Date 4/17/18
 Start Time 19:33:31

Elapsed Time (min)	Dial Reading (div)
Initial	81.7
0.03	111.6
0.08	112.5
0.13	113.1
0.20	113.9
0.25	114.4
0.30	114.8
0.45	117.0
0.55	117.5
1.05	118.6
2.30	120.3
4.05	121.4
9.05	122.7
16.05	123.5
25.05	124.4
36.05	124.5
49.07	125.2
64.07	125.3
81.07	125.4
100.07	125.4
121.07	125.6




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 1.0-2.0
Final Reading (div) 184.5
 Consolidometer No. **R470**
 1 Division (in) 0.0001
 Start Date 4/17/18
 Start Time 22:33:55

Elapsed Time (min)	Dial Reading (div)
Initial	125.6
0.03	159.1
0.08	167.8
0.15	169.7
0.20	170.9
0.25	171.5
0.30	172.2
0.45	173.5
0.55	174.2
1.05	176.6
2.30	178.5
4.05	179.3
9.05	180.8
16.05	181.7
25.05	182.7
36.05	182.5
49.05	183.2
64.05	183.7
81.05	183.6
100.07	184.0
121.07	183.9
144.07	184.4
180.07	184.5



Tested By 129-04-0411 Date 4/17/18 Checked By GEM Date 5/15/18


Tested By 129-04-0411 Date 4/17/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND


Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 2.0-4.0
Final Reading (div) 254.4
 Consolidometer No. **R470**
 1 Division (in) 0.0001

Start Date 4/18/18
 Start Time 1:34:20

Elapsed Time (min)	Dial Reading (div)
Initial	184.5
0.03	230.3
0.08	237.5
0.13	240.5
0.18	241.2
0.25	241.5
0.30	242.4
0.45	243.0
0.55	242.9
1.05	244.9
2.30	246.2
4.05	247.0
9.05	248.2
16.05	249.5
25.05	250.5
36.05	251.9
49.05	251.9
64.05	252.4
81.05	253.3
100.05	253.3
121.05	253.4
144.05	253.8
180.05	254.4




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND


Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 4.0-8.0
Final Reading (div) 337.6
 Consolidometer No. **R470**
 1 Division (in) 0.0001

Start Date 4/18/18
 Start Time 4:34:44

Elapsed Time (min)	Dial Reading (div)
Initial	254.4
0.05	317.5
0.10	322.1
0.15	323.3
0.20	325.1
0.25	325.6
0.30	326.0
0.45	326.5
0.55	326.8
1.05	327.5
2.30	328.4
4.05	329.3
9.07	330.6
16.07	332.2
25.07	333.4
36.07	334.3
49.07	334.5
64.07	334.9
81.07	334.9
100.07	335.0
121.07	335.7
144.07	335.8
180.07	336.0
220.47	337.6



Tested By 129-04-0411 Date 4/18/18 Checked By GEM Date 5/15/18


Tested By 129-04-0411 Date 4/18/18 Checked By GEM Date 5/15/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf)	8.0-2.0
Final Reading (div)	276.1
Consolidometer No.	R470
1 Division (in)	0.0001
Start Date	4/18/18
Start Time	8:15:13

Elapsed Time (min)	Dial Reading (div)
Initial	337.6
0.05	288.0
0.10	282.8
0.15	281.5
0.20	280.9
0.25	280.7
0.30	280.6
0.45	280.2
0.55	280.0
1.05	279.3
2.30	278.3
4.05	277.9
9.05	277.5
16.05	276.7
25.05	276.3
36.05	276.5
49.05	276.1
64.05	276.1




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf)	2.0-0.5
Final Reading (div)	227.0
Consolidometer No.	R470
1 Division (in)	0.0001
Start Date	4/18/18
Start Time	11:15:34

Elapsed Time (min)	Dial Reading (div)
Initial	276.1
0.05	243.4
0.10	235.3
0.15	233.5
0.20	232.3
0.25	231.8
0.30	231.3
0.45	230.4
0.55	230.2
1.05	229.9
2.30	229.1
4.05	228.7
9.05	228.4
16.05	227.6
25.05	227.1
36.05	227.2
49.05	227.1
64.07	227.0



Tested By 129-04-0411 Date 4/18/18 Checked By GEM Date 5/15/18


Tested By 129-04-0411 Date 4/18/18 Checked By GEM Date 5/15/18



ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216


Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.5-0.25
 Final Reading (div) 204.7
 Consolidometer No. R470
 1 Division (in) 0.0001
 Start Date 4/18/18
 Start Time 14:15:59


Elapsed Time (min)	Dial Reading (div)
Initial	227.0
0.03	216.5
0.08	215.2
0.13	214.7
0.18	214.3
0.23	214.2
0.30	214.5
0.45	213.8
0.55	213.7
1.05	213.4
2.30	212.7
4.05	212.7
9.05	209.5
16.05	209.2
25.05	207.6
36.05	207.5
49.05	206.4
64.05	205.7
81.05	205.6
100.05	205.0
121.05	204.7
144.07	204.7
180.07	204.7



ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216


Client ESP Associates Boring No. -L- STA. 517+11, 59'RT
 Client Project R-1015 Site 9 - CS34.327.00 Depth (ft) 11.0-13.0
 Project No. R-2018-095-001 Sample No. ST-2
 Lab ID R-2018-095-001-011 Visual Description GRAY SAND

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.25-0.125
 Final Reading (div) 182.6
 Consolidometer No. R470
 1 Division (in) 0.0001
 Start Date 4/18/18
 Start Time 17:16:22

Elapsed Time (min)	Dial Reading (div)
Initial	204.7
0.05	196.2
0.10	195.1
0.15	194.6
0.20	194.6
0.25	194.3
0.30	194.5
0.45	194.3
0.55	194.4
1.05	194.3
2.30	193.9
4.05	193.9
9.05	193.8
16.05	192.7
25.05	192.5
36.05	192.8
49.05	192.4
64.07	191.6
81.07	191.7
100.07	190.2
121.07	190.4
144.07	189.6
180.07	188.3
300.07	186.4
520.07	183.9
700.07	182.1
941.73	182.6



Tested By 129-04-0411 Date 4/18/18 Checked By GEM Date 5/15/18

Tested By 129-04-0411 Date 4/18/18 Checked By GEM Date 5/15/18



SPECIFIC GRAVITY
AASHTO T-100-15

Client	ESP Associates	Location	-L-STA.217+15,23'RT
Client Reference	R-2015 Site 9 MSE Wall CS34.368	Depth (ft)	9.8-11.8
Project No.	R-2018-181-001	Sample No.	ST-3
Lab ID	R-2018-181-001-001	Visual Description	GRAY (Minus No.4 sieve material, airdried)


Replicate Number	1	2
Pycnometer ID	R 280	R 347
Weight of Pycnometer + Soil + Water (gm)	718.53	711.58
Temperature, T (°Celsius)	28.1	27.8
Weight of Pycnometer + Water (gm)	685.04	668.72
Tare Number	280	347
Weight of Tare + Dry Soil (gm)	241.14	239.34
Weight of Tare (gm)	187.33	170.75
Weight of Dry Soil (gm)	53.81	68.59
Specific Gravity of Soil @ T	2.649	2.666
Specific Gravity of Water @ T	0.9962	0.9963
Conversion Factor for Temperature T	0.9980	0.9981
Specific Gravity @ 20° Celsius	2.654	2.671

Average Specific Gravity @ 20° Celsius	2.66
--	------

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client	ESP Associates	Location	-L-STA.217+15,23'RT
Client Reference	R-1015 Site 9 MSE Wall CS34.368	Depth (ft)	9.8-11.8
Project No.	R-2018-181-001	Sample No.	ST-3
Lab ID	R-2018-181-001-001	Visual Description	GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Tested By 129-04-0411 Date 7/3/18 Checked By GEM Date 7/3/18

DCN: CT-S5 Date: 03/24/05 Revision: 10 R:\2018 PROJECTS\ESP Associates\2018-181 ESP - R-1015 SITE 9 MSE WALL\2018-181-001-001 rename DOTSp. Gravity.xlsm\Sheet1

Tested By 129-04-0411 Date 6/26/18 Approved By MPS Date 7/6/18

DCN: CT-24E Date: 5/3/12 Revision: 6

page 1 of 2

Z:\2018 PROJECTS\ESP Associates\2018-181 ESP - R-1015 SITE 9 MSE WALL\2018-181-001-001 DOT GEOJAC-16T5F1 Cv.xlsm\FINAL PLOT
2200 Westinghouse Blvd., Suite 103 • Raleigh, NC 27604 • Phone (919) 876-0405 • Fax (919) 876-0460 • www.geotechnics.net

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216

Client ESP Associates Location -L-STA.217+15,23RT
 Client Reference R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED

Consolidometer No. R487
1 Division = 0.0001 (in.)

Sample Properties

Water Content
 Tare Number 912 826
 Wt. Tare & WS (g) 335.79 237.23
 Wt. Tare & DS (g) 244.03 205.02
 Wt. Water (g) 91.76 32.21
 Wt. Tare (g) 101.01 133.76
 Wt. DS (g) 143.02 71.26
 Water Content (%) 64.16 45.20

Sample Parameters
 Sample Diameter (in) 2.5 2.5
 Sample Height (in) 1.0000 1.0000
 Sample Volume (cc) 80.44 80.44
 Wt. Wet Sample + Ring (g) 337.93 323.70
 Wt. of Ring (g) 214.69 214.69
 Wt. of Wet Sample (g) 123.24 109.01
 Wet Density (pcf) 95.60 84.56
 Wet Density (g/cc) 1.53 1.36
 Water Content (%) 64.16 45.20
 Wt. of Dry Sample (g) 75.07 75.07
 Dry Density (pcf) 58.24 58.24
 Dry Density (g/cc) 0.93 0.93
 Void Ratio 1.8501 1.8501
 Saturation (%) 92.24 64.99
 Specific Gravity 2.66 Measured

Test Data Summary

Applied Pressure (tsf)	Final Dial Reading (div)	Machine Deflection (div)	Corrected Reading (div)	Height of Sample (mm)	Volume (cc)	Dry Density (g/cc)	Void Ratio
Seating	0	0	0	25.400	80.440	0.93329	1.85013
0.125	123.7	3.6	120.1	25.095	79.474	0.94463	1.81591
0.25	207.3	9.0	198.3	24.896	78.844	0.95218	1.79360
0.5	474.4	21.0	453.4	24.248	76.793	0.97762	1.72091
1	1143.0	40.0	1103.0	22.598	71.567	1.04900	1.53575
2	2071.0	59.6	2011.4	20.291	64.260	1.16828	1.27685
4	2889.6	85.0	2804.6	18.276	57.880	1.29707	1.05078
8	3565.8	123.4	3442.5	16.656	52.749	1.42323	0.86898
2	3350.2	114.6	3235.6	17.182	54.413	1.37970	0.92795
0.5	3027.2	84.0	2943.2	17.924	56.765	1.32254	1.01129
0.125	2626.5	76.4	2550.1	18.923	59.927	1.25276	1.12332

DCN: CT-24E Date: 5/3/12 Revision: 6
 Tested By 129-04-0411 Date 6/26/18 Input Checked By GEM Date 7/6/18

Z:\2018 PROJECTS\ESP Associates\2018-181 ESP - R-1015 SITE 9 MSE WALL\2018-181-001-001 DOT GEOJAC-16TSF1 Cv.xlsm\FINAL_PLOT


2200 Westinghouse Blvd., Suite 103 • Raleigh, NC 27604 • Phone (919) 876-0405 • Fax (919) 876-0460 • www.geotechnics.net

ONE DIMENSIONAL CONSOLIDATION

AASHTO T-216

Client ESP Associates Location -L-STA.217+15,23RT
 Client Reference R-1015 Site 9 MSE Wall CS34.368 Depth (ft) Sample 9.8-11.8
 Project No. R-2018-181-001 No. Visual ST-3
 Lab ID R-2018-181-001-001 Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Coefficient of Consolidation (cm²/sec)

— First Cycle Up

ONE DIMENSIONAL CONSOLIDATION

AASHTO T-216

Client ESP Associates
 Client Reference R-1015 Site 9 MSE Wall CS34.368
 Project No. R-2018-181-001
 Lab ID R-2018-181-001-001

Location -L-STA.217+15,23'RT
 Depth (ft) Sample 9.8-11.8
 No. Visual ST-3
 Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED

Consolidometer No. R487

1 Division = 0.0001 (in.)

Sample Properties

Water Content		
Tare Number	912	826
Wt. Tare & WS (g)	335.79	237.23
Wt. Tare & DS (g)	244.03	205.02
Wt. Water (g)	91.76	32.21
Wt. Tare (g)	101.01	133.76
Wt. DS (g)	143.02	71.26
Water Content (%)	64.16	45.20
Sample Parameters		
Sample Diameter (in)	2.5	2.5
Sample Height (in)	1.000	1.000
Sample Volume (cc)	80.44	80.44
Wt. Wet Sample + Ring (g)	337.93	323.70
Wt. of Ring (g)	214.69	214.69
Wt. of Wet Sample (g)	123.24	109.01
Wet Density (pcf)	95.60	84.56
Wet Density (g/cc)	1.53	1.36
Water Content (%)	64.16	45.20
Wt. of Dry Sample (g)	75.07	75.07
Dry Density (pcf)	58.24	58.24
Dry Density (g/cc)	0.93	0.93
Void Ratio	1.8501	1.8501
Saturation (%)	92.24	64.99
Specific Gravity	2.66	Measured

Load Increment (tsf)	Dial Reading @ t ₅₀ (div)	Machine Deflection (div)	Corrected Dial Reading @ t ₅₀ (div)	Sample Height @ t ₅₀ (cm)	Time t ₅₀ (min.)	C _v (cm ² /sec)
0.0 - 0.125	60.3	3.6	56.7	2.526	4.00	0.00131
0.125 - 0.25	184.2	9.0	175.2	2.495	15.00	0.00034
0.25 - 0.5	360.8	21.0	339.8	2.454	72.00	0.00007
0.5 - 1	817.6	40.0	777.6	2.342	25.10	0.00018
1 - 2	1565.5	59.6	1505.9	2.157	25.10	0.00015
2 - 4	2486.4	85.0	2401.4	1.930	22.00	0.00014
4 - 8	3228.8	123.4	3105.4	1.751	15.00	0.00017
8 - 2	NA	114.6	NA	NA	NA	NA
2 - 0.5	NA	84.0	NA	NA	NA	NA
0.5 - 0.125	NA	76.4	NA	NA	NA	NA

Tested By 129-04-0411 Date 6/26/18 Input Checked By GEM Date 7/6/18

DCN: CT-24E Date: 5/3/12 Revision: 6

Z:\2018 PROJECTS\ESP Associates\2018-181 ESP - R-1015 SITE 9 MSE WALL\2018-181-001-001 DOT GEOJAC-16TSF1 Cv.xls\m\FINAL PLOT

2200 Westinghouse Blvd., Suite 103 • Raleigh, NC 27604 • Phone (919) 876-0405 • Fax (919) 876-0460 • www.geotechnics.net



page 4 of 4



ONE DIMENSIONAL CONSOLIDATION
 AASHTO T-216

Client	ESP Associates	Location	-L-STA.217+15,23'RT
Client Project	R-1015 Site 9 MSE Wall CS34.368	Depth (ft)	9.8-11.8
Project No.	R-2018-181-001	Sample No.	ST-3
Lab ID	R-2018-181-001-001	Visual Description	GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.0-0.125
 Final Reading (div) 123.7
 Consolidometer No. R487
 1 Division (in) 0.0001
 Start Date 6/26/18
 Start Time 17:27:35

Elapsed Time (min)	Dial Reading (div)
Initial	0.0
0.05	0.4
0.10	19.3
0.15	25.0
0.20	28.9
0.25	29.0
0.30	35.0
0.45	35.3
0.55	35.3
1.07	48.1
2.32	56.3
4.07	61.2
9.07	74.4
16.07	90.5
25.07	101.6
36.07	102.2
49.07	115.2
64.07	115.5
81.07	115.6
100.07	115.9
121.07	122.3
144.07	122.8
180.07	122.4
300.07	123.2
420.05	123.7


Tested By 129-04-0411 Date 6/26/18 Checked By GEM Date 7/6/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Location -L-STA.217+15,23'RT
 Client Project R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.125-0.25
 Final Reading (div) 207.3
 Consolidometer No. R487
 1 Division (in) 0.0001
 Start Date 6/27/18
 Start Time 0:27:38

Elapsed Time (min)	Dial Reading (div)
Initial	123.7
0.05	172.7
0.10	172.5
0.15	172.7
0.20	172.7
0.25	172.8
0.30	172.5
0.45	173.0
0.55	173.0
1.05	173.4
2.30	173.0
4.05	173.2
9.05	178.7
16.07	183.8
25.07	188.8
36.07	189.1
49.07	194.8
64.07	195.6
81.07	195.6
100.07	201.9
121.07	202.0
144.07	201.9
180.07	202.9
300.07	207.3
420.25	207.3




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Location -L-STA.217+15,23'RT
 Client Project R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.25-0.5
 Final Reading (div) 474.4
 Consolidometer No. R487
 1 Division (in) 0.0001
 Start Date 6/27/18
 Start Time 7:27:53

Elapsed Time (min)	Dial Reading (div)
Initial	207.3
0.05	257.6
0.10	257.5
0.15	258.6
0.20	258.5
0.25	258.5
0.30	258.6
0.45	258.5
0.57	258.5
1.07	258.7
2.32	271.7
4.07	279.3
9.07	303.1
16.07	310.0
25.07	324.7
36.07	336.3
49.07	347.0
64.07	356.8
81.07	361.9
100.07	382.0
121.07	389.9
144.07	400.0
180.08	411.0
300.08	442.6
420.50	474.4



Tested By 129-04-0411 Date 6/27/18 Checked By GEM Date 7/6/18


Tested By 129-04-0411 Date 6/27/18 Checked By GEM Date 7/6/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Location -L-STA.217+15,23'RT
 Client Project R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 0.5-1.0
Final Reading (div) 1143.0
 Consolidometer No. **R487**
 1 Division (in) 0.0001
 Start Date 6/27/18
 Start Time 14:28:23

Elapsed Time (min)	Dial Reading (div)
Initial	474.4
0.05	554.7
0.10	554.8
0.15	555.0
0.20	554.8
0.25	554.9
0.32	557.6
0.47	566.6
0.57	569.3
1.07	578.0
2.32	609.9
4.07	638.0
9.07	702.9
16.07	760.9
25.07	815.7
36.07	864.8
49.07	913.5
64.07	948.5
81.07	976.1
100.07	999.1
121.07	1027.9
144.07	1046.0
180.07	1077.3
300.08	1126.1
420.50	1143.0




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Location -L-STA.217+15,23'RT
 Client Project R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 1.0-2.0
Final Reading (div) 2071.0
 Consolidometer No. **R487**
 1 Division (in) 0.0001
 Start Date 6/27/18
 Start Time 21:28:53

Elapsed Time (min)	Dial Reading (div)
Initial	1143.0
0.05	1164.5
0.10	1177.9
0.15	1182.6
0.20	1190.2
0.25	1195.3
0.32	1198.2
0.47	1205.6
0.57	1212.2
1.07	1238.0
2.32	1271.4
4.07	1310.2
9.07	1393.9
16.07	1469.5
25.07	1563.9
36.07	1634.3
49.07	1710.4
64.07	1776.7
81.07	1840.5
100.07	1885.8
121.07	1926.1
144.07	1951.3
180.08	1989.4
300.08	2043.6
420.47	2071.0



Tested By 129-04-0411 Date 6/27/18 Checked By GEM Date 7/6/18


Tested By 129-04-0411 Date 6/27/18 Checked By GEM Date 7/6/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Location -L-STA.217+15,23'RT
 Client Project R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 2.0-4.0
Final Reading (div) 2889.6
 Consolidometer No. **R487**
 1 Division (in) 0.0001
 Start Date 6/28/18
 Start Time 4:29:21

Elapsed Time (min)	Dial Reading (div)
Initial	2071.0
0.05	2146.9
0.10	2147.0
0.15	2147.1
0.20	2152.0
0.25	2157.7
0.30	2159.6
0.45	2165.7
0.55	2169.8
1.07	2193.9
2.32	2231.5
4.07	2273.1
9.07	2353.0
16.07	2433.4
25.07	2518.7
36.07	2590.8
49.07	2650.2
64.07	2704.3
81.08	2746.5
100.08	2777.2
121.08	2801.8
144.08	2817.9
180.08	2839.1
300.08	2876.3
420.48	2889.6




Tested By 129-04-0411 Date 6/28/18 Checked By GEM Date 7/6/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216




Client ESP Associates Location -L-STA.217+15,23'RT
 Client Project R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 4.0-8.0
Final Reading (div) 3565.8
 Consolidometer No. **R487**
 1 Division (in) 0.0001
 Start Date 6/28/18
 Start Time 11:29:50

Elapsed Time (min)	Dial Reading (div)
Initial	2889.6
0.03	2942.6
0.10	2955.3
0.15	2958.2
0.20	2963.4
0.25	2968.4
0.30	2969.8
0.45	2979.7
0.55	2986.8
1.05	3009.7
2.30	3046.0
4.05	3081.7
9.05	3165.5
16.05	3235.9
25.05	3303.6
36.05	3364.4
49.05	3411.0
64.05	3452.9
81.05	3478.3
100.05	3496.9
121.05	3511.7
144.05	3524.5
180.05	3537.5
300.05	3558.4
420.05	3565.8




Tested By 129-04-0411 Date 6/28/18 Checked By GEM Date 7/6/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client ESP Associates Location -L-STA.217+15,23'RT
 Client Project R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY


Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 8.0-2.0
Final Reading (div) 3350.2
 Consolidometer No. **R487**
 1 Division (in) 0.0001

Start Date 6/28/18
 Start Time 18:29:54

Elapsed Time (min)	Dial Reading (div)
Initial	3565.8
0.03	3518.0
0.10	3507.1
0.15	3502.5
0.20	3497.5
0.25	3492.0
0.30	3488.0
0.45	3482.0
0.55	3478.2
1.05	3467.5
2.30	3451.0
4.05	3435.9
9.05	3419.6
16.05	3404.8
25.05	3396.2
36.05	3389.2
49.05	3382.4
64.05	3377.2
81.05	3373.9
100.05	3368.8
121.05	3364.2
144.05	3362.2
180.07	3360.2
300.07	3356.1
420.08	3350.2




ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client ESP Associates Location -L-STA.217+15,23'RT
 Client Project R-1015 Site 9 MSE Wall CS34.368 Depth (ft) 9.8-11.8
 Project No. R-2018-181-001 Sample No. ST-3
 Lab ID R-2018-181-001-001 Visual Description GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf) 2.0-0.5
Final Reading (div) 3027.2
 Consolidometer No. **R487**
 1 Division (in) 0.0001

Start Date 6/29/18
 Start Time 1:30:00

Elapsed Time (min)	Dial Reading (div)
Initial	3350.2
0.05	3309.8
0.10	3307.9
0.15	3306.7
0.20	3305.0
0.25	3303.5
0.30	3300.9
0.45	3297.2
0.55	3294.7
1.05	3288.4
2.30	3266.7
4.07	3253.8
9.07	3228.3
16.07	3205.5
25.07	3190.5
36.07	3170.8
49.07	3147.0
64.07	3132.1
81.07	3118.8
100.07	3102.8
121.07	3086.2
144.07	3075.2
180.07	3063.4
300.07	3038.8
420.10	3027.2



Tested By 129-04-0411 Date 6/28/18 Checked By GEM Date 7/6/18



Tested By 129-04-0411 Date 6/29/18 Checked By GEM Date 7/6/18

ONE DIMENSIONAL CONSOLIDATION
AASHTO T-216



Client: ESP Associates Location: -L-STA.217+15,23'RT
 Client Project: R-1015 Site 9 MSE Wall CS34.368 Depth (ft): 9.8-11.8
 Project No.: R-2018-181-001 Sample No.: ST-3
 Lab ID: R-2018-181-001-001 Visual Description: GRAY CLAY

Sample Conditions: UNDISTURBED, INUNDATED AND DOUBLE DRAINED



Test Load (tsf): 0.5-0.125
Final Reading (div): 2626.5
 Consolidometer No.: R487
 1 Division (in): 0.0001
 Start Date: 6/29/18
 Start Time: 8:30:06


Elapsed Time (min)	Dial Reading (div)
Initial	3027.2
0.05	2993.0
0.10	2991.3
0.15	2991.4
0.20	2991.4
0.25	2991.4
0.30	2991.5
0.45	2992.2
0.55	2991.7
1.07	2992.3
2.32	2989.9
4.07	2980.5
9.07	2965.9
16.07	2953.5
25.07	2932.7
36.07	2915.3
49.07	2898.6
64.07	2884.7
81.07	2865.3
100.07	2851.7
121.07	2832.1
144.07	2817.8
180.07	2799.7
300.07	2752.8
520.08	2707.8
700.08	2683.2
960.08	2663.3
1440.08	2647.4
1680.08	2643.5
1920.08	2640.8
2160.08	2633.4
2400.08	2626.5

CONSOLIDATED UNDRAINED TRIAXIAL TEST WITH PORE PRESSURE READINGS
AASHTO T-297



Client: ESP Associates Location: -L-STA 217+15, 23' RT
 Client Reference: R-1015 Site 9 MSE Wall CS34.368 Depth (ft): 9.8-11.8
 Project No.: R-2018-181-001 Sample No.: ST-3
 Lab ID: R-2018-181-001-001

Consolidated Undrained Triaxial Test with Pore Pressure



a = 0.56 C-bar = 0.61
alpha = 22.2 Phi-bar = 24.10

Tested By: 129-04-0411 Date: 6/29/18 Checked By: GEM Date: 7/6/18

Tested By: 129-04-0411 Date: 7/2/18 Approved By: MPS Date: 7/16/18

MOHR TOTAL STRENGTH ENVELOPE
AASHTO T-297



Client: ESP Associates
 Client Reference: R-1015 Site 9 MSE Wall CS34.368
 Project No.: R-2018-181-001
 Lab ID: R-2018-181-001-001
 Visual Description: TAN CLAYEY SAND (UNDISTURBED)

Location: -L-STA 217+15, 23' RT
 Depth (ft): 9.8-11.8
 Sample No.: ST-3


CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS
AASHTO T-297



Client: ESP Associates
 Client Reference: R-1015 Site 9 MSE Wall CS34.368
 Project No.: R-2018-181-001
 Lab ID: R-2018-181-001-001

Location: -L-STA 217+15, 23' RT
 Depth (ft): 9.8-11.8
 Sample No.: ST-3

Visual Description: TAN CLAYEY SAND (UNDISTURBED)



Stage No.	1
Test No.	1

INITIAL SAMPLE DIMENSIONS (in)

Length 1:	6.097	Diameter 1:	2.838
Length 2:	6.097	Diameter 2:	2.869
Length 3:	6.071	Diameter 3:	2.852
Length 4:	6.087	Diameter 4:	2.874
Avg. Length:	6.088	Avg. Diam.:	2.858

PRESSURES (psi)

Cell Pressure (psi)	42.8
Back Pressure (psi)	40.0
Eff. Conf. Pressure (psi)	2.8
Pore Pressure Response (%)	100

VOLUME CHANGE

Initial Burette Reading (ml)	24.0
Final Burette Reading (ml)	20.1
Final Change (ml)	3.9

MAXIMUM OBLIQUITY POINTS

P	=	4.40
Q	=	3.18

Initial Dial Reading (mil)	55
Dial Reading After Saturation (mil)	99
Dial Reading After Consolidation (mil)	115

LOAD (LB)	DEFORMATION (IN)	PORE PRESSURE (PSI)
10.7	0.000	40.0
13.8	0.001	39.8
18.3	0.003	39.8
26.2	0.009	40.2
32.9	0.015	40.4
36.8	0.021	40.6
41.2	0.030	40.9
44.4	0.039	41.1
47.5	0.052	41.3
50.4	0.073	41.5
51.5	0.105	41.6
50.8	0.141	41.6
48.7	0.177	41.6
42.2	0.220	41.4
41.1	0.251	41.4
40.9	0.293	41.4
41.1	0.351	41.5
43.8	0.754	41.5
43.5	0.768	41.5
43.8	0.782	41.5
44.0	0.796	41.5
42.8	0.818	41.5
43.5	0.872	41.5
43.0	0.924	41.5

Failure Based on Maximum Effective Principal Stress Ratio

NOTE: GRAPH NOT TO SCALE

Tested By: 129-04-0411 Date: 7/2/18 Approved By: MPS Date: 7/16/18

page 2 of 11 DCN: CT-S28 DATE: 4/12/13 REVISION: 3

Tested By: 129-04-0411 Date: 7/2/18 Input Checked By: GEM Date: 7/16/18

page 3 of 11 DCN: CT-S28 DATE: 4/12/13 REVISION: 3

Sigmatrax.xls

**CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS**
AASHTO T-297



**CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS**
AASHTO T-297



Client: ESP Associates Location: -L-STA 217+15, 23' RT
 Client Reference: R-1015 Site 9 MSE Wall CS34.368 Depth (ft): 9.8-11.8
 Project No.: R-2018-181-001 Sample No.: ST-3
 Lab ID: R-2018-181-001-001

Client: ESP Associates Location: -L-STA 217+15, 23' RT
 Client Reference: R-1015 Site 9 MSE Wall CS34.368 Depth (ft): 9.8-11.8
 Project No.: R-2018-181-001 Sample No.: ST-3
 Lab ID: R-2018-181-001-001

Visual Description: TAN CLAYEY SAND (UNDISTURBED)

Visual Description: TAN CLAYEY SAND (UNDISTURBED)

Effective Confining Pressure (psi)	2.8	Stage No.	1
		Test No.	1

Stage No.	1
Test No.	2

INITIAL SAMPLE DIMENSIONS (in)			
Length 1:	6.265	Diameter 1:	2.869
Length 2:	6.235	Diameter 2:	2.865
Length 3:	6.234	Diameter 3:	2.860
Length 4:	6.200	Diameter 4:	2.848
Avg. Length:	6.234	Avg. Diam.:	2.861

INITIAL DIMENSIONS		VOLUME CHANGE	
Initial Sample Length (in)	6.09	Volume After Consolidation (in ³)	37.98
Initial Sample Diameter (in)	2.86	Length After Consolidation (in)	6.03
Initial Sample Area (in ²)	6.42	Area After Consolidation (in ²)	6.300
Initial Sample Volume (in ³)	39.06		

PRESSURES (psi)	
Cell Pressure (psi)	45.6
Back Pressure (psi)	40.0
Eff. Conf. Pressure (psi)	5.6
Pore Pressure	
Response (%)	100

VOLUME CHANGE	
Initial Burette Reading (ml)	48.0
Final Burette Reading (ml)	25.6
Final Change (ml)	22.4

Strain (%)	Deviation Stress	ΔU	$\bar{\sigma}_1$	$\bar{\sigma}_3$	Effective Principle Stress Ratio	\bar{A}	\bar{P}	Q
------------	------------------	------------	------------------	------------------	----------------------------------	-----------	-----------	-----

MAXIMUM OBLIQUITY POINTS

\bar{P}	=	5.35
Q	=	2.75

Initial Dial Reading (mil)	8
Dial Reading After Saturation (mil)	31
Dial Reading After Consolidation (mil)	77

0.02	0.48	-0.21	3.53	3.0	1.159	-0.43	3.28	0.24
0.05	1.21	-0.16	4.20	3.0	1.403	-0.13	3.59	0.60
0.15	2.46	0.17	5.13	2.7	1.922	0.07	3.90	1.23
0.25	3.51	0.43	5.92	2.4	2.459	0.12	4.16	1.76
0.35	4.13	0.64	6.32	2.2	2.887	0.16	4.26	2.07
0.51	4.81	0.89	6.75	1.9	3.481	0.19	4.35	2.41
0.65	5.31	1.10	7.05	1.7	4.057	0.21	4.39	2.66
0.86	5.80	1.28	7.35	1.6	4.737	0.22	4.45	2.90
1.22	6.22	1.51	7.54	1.3	5.688	0.24	4.44	3.11
1.74	6.36	1.61	7.59	1.2	6.199	0.25	4.40	3.18
2.33	6.21	1.61	7.43	1.2	6.094	0.26	4.32	3.11
2.94	5.85	1.55	7.13	1.3	5.578	0.27	4.20	2.92
3.66	4.82	1.38	6.28	1.5	4.309	0.29	3.87	2.41
4.17	4.63	1.40	6.06	1.4	4.237	0.30	3.75	2.32
4.86	4.56	1.42	5.97	1.4	4.226	0.31	3.69	2.28
5.83	4.55	1.45	5.93	1.4	4.299	0.32	3.65	2.27
12.51	4.60	1.50	5.93	1.3	4.450	0.33	3.63	2.30
12.75	4.55	1.50	5.87	1.3	4.420	0.33	3.60	2.27
12.97	4.57	1.50	5.91	1.3	4.425	0.33	3.62	2.29
13.20	4.58	1.50	5.91	1.3	4.449	0.33	3.62	2.29
13.57	4.40	1.52	5.71	1.3	4.364	0.35	3.51	2.20
14.47	4.45	1.52	5.76	1.3	4.400	0.34	3.54	2.23
15.33	4.34	1.49	5.68	1.3	4.235	0.34	3.51	2.17

LOAD (LB)	DEFORMATION (IN)	PORE PRESSURE (PSI)
19.2	0.000	40.0
22.8	0.001	39.4
28.0	0.003	39.5
36.7	0.008	39.9
40.4	0.015	40.2
43.3	0.022	40.5
46.6	0.032	40.9
49.2	0.042	41.3
51.5	0.056	41.6
54.2	0.081	42.1
55.9	0.117	42.5
56.9	0.161	42.7
55.0	0.202	42.9
54.8	0.252	43.0
53.5	0.288	43.0
51.7	0.339	43.0
50.1	0.424	43.1
51.6	0.519	43.2
49.8	0.590	43.2
50.9	0.684	43.2
48.5	0.757	43.4
46.8	0.826	43.4
47.5	0.912	43.4
45.7	0.932	43.4

**CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS**
AASHTO T-297



Client: ESP Associates Location: -L-STA 217+15, 23' RT
 Client Reference: R-1015 Site 9 MSE Wall CS34.368 Depth (ft): 9.8-11.8
 Project No.: R-2018-181-001 Sample No.: ST-3
 Lab ID: R-2018-181-001-001

Visual Description: TAN CLAYEY SAND (UNDISTURBED)

Effective Confining Pressure (psi)	5.6	Stage No.	1
		Test No.	2

INITIAL DIMENSIONS

Initial Sample Length (in)	6.23
Initial Sample Diameter (in)	2.86
Initial Sample Area (in ²)	6.43
Initial Sample Volume (in ³)	40.06

VOLUME CHANGE

Volume After Consolidation (in ³)	38.25
Length After Consolidation (in)	6.16
Area After Consolidation (in ²)	6.205

Strain (%)	Deviation Stress	ΔU	$\bar{\sigma}_1$	$\bar{\sigma}_3$	Effective Principle Stress Ratio	\bar{A}	\bar{P}	Q
0.02	0.57	-0.60	6.77	6.2	1.092	-1.05	6.48	0.29
0.05	1.40	-0.50	7.50	6.1	1.230	-0.35	6.80	0.70
0.12	2.80	-0.10	8.50	5.7	1.492	-0.04	7.10	1.40
0.24	3.41	0.23	8.78	5.4	1.635	0.07	7.07	1.70
0.35	3.87	0.54	8.92	5.1	1.765	0.14	6.99	1.93
0.52	4.38	0.94	9.04	4.7	1.941	0.21	6.85	2.19
0.68	4.80	1.27	9.12	4.3	2.108	0.27	6.73	2.40
0.91	5.16	1.63	9.13	4.0	2.298	0.32	6.55	2.58
1.32	5.56	2.09	9.07	3.5	2.586	0.38	6.29	2.78
1.90	5.80	2.50	8.90	3.1	2.871	0.43	6.00	2.90
2.61	5.91	2.70	8.80	2.9	3.039	0.46	5.85	2.95
3.28	5.58	2.89	8.28	2.7	3.060	0.52	5.50	2.79
4.08	5.49	2.99	8.10	2.6	3.105	0.54	5.35	2.75
4.68	5.26	3.00	7.86	2.6	3.028	0.57	5.23	2.63
5.49	4.94	3.01	7.53	2.6	2.911	0.61	5.06	2.47
6.87	4.64	3.07	7.17	2.5	2.836	0.66	4.85	2.32
8.41	4.78	3.20	7.18	2.4	2.991	0.67	4.79	2.39
9.58	4.45	3.24	6.81	2.4	2.887	0.73	4.58	2.23
11.10	4.53	3.24	6.89	2.4	2.926	0.72	4.62	2.27
12.28	4.14	3.38	6.36	2.2	2.868	0.82	4.29	2.07
13.40	3.84	3.38	6.06	2.2	2.732	0.88	4.14	1.92
14.80	3.87	3.39	6.09	2.2	2.753	0.87	4.15	1.94
15.12	3.61	3.40	5.81	2.2	2.647	0.94	4.00	1.81

**CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS**
AASHTO T-297



Client: ESP Associates Location: -L-STA 217+15, 23' RT
 Client Reference: R-1015 Site 9 MSE Wall CS34.368 Depth (ft): 9.8-11.8
 Project No.: R-2018-181-001 Sample No.: ST-3
 Lab ID: R-2018-181-001-001

Visual Description: TAN CLAYEY SAND (UNDISTURBED)

Stage No.	1
Test No.	3

INITIAL SAMPLE DIMENSIONS (in)

Length 1:	6.114	Diameter 1:	2.853
Length 2:	6.192	Diameter 2:	2.857
Length 3:	6.167	Diameter 3:	2.883
Length 4:	6.134	Diameter 4:	2.844
Avg. Length:	6.152	Avg. Diam.:	2.859

PRESSURES (psi)

Cell Pressure (psi)	62.2
Back Pressure (psi)	40.0
Eff. Conf. Pressure (psi)	22.2
Pore Pressure Response (%)	99

VOLUME CHANGE

Initial Burette Reading (ml)	72.0
Final Burette Reading (ml)	14.5
Final Change (ml)	57.5

MAXIMUM OBLIQUITY POINTS

\bar{P}	=	14.61
Q	=	6.53

Initial Dial Reading (mil)	31
Dial Reading After Saturation (mil)	88
Dial Reading After Consolidation (mil)	429

LOAD (LB)	DEFORMATION (IN)	PORE PRESSURE (PSI)
16.3	0.000	40.0
19.6	0.001	39.8
28.8	0.002	39.9
51.7	0.008	42.3
63.3	0.014	44.0
70.2	0.019	45.3
76.2	0.028	46.7
80.1	0.036	47.7
85.7	0.049	48.6
86.9	0.070	49.9
92.3	0.100	51.1
99.2	0.138	52.1
104.3	0.175	52.8
105.1	0.218	53.4
102.9	0.249	53.7
99.7	0.293	54.1
94.4	0.352	54.6
101.2	0.756	55.7
95.7	0.769	55.7
95.8	0.783	55.7
95.5	0.797	55.8
92.0	0.823	55.8
93.7	0.878	55.8

**CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS**
AASHTO T-297



Client: ESP Associates Location: -L-STA 217+15, 23' RT
 Client Reference: R-1015 Site 9 MSE Wall CS34.368 Depth (ft): 9.8-11.8
 Project No.: R-2018-181-001 Sample No.: ST-3
 Lab ID: R-2018-181-001-001

Visual Description: TAN CLAYEY SAND (UNDISTURBED)

Effective Confining Pressure (psi)	22.2	Stage No.	1
		Test No	3

INITIAL DIMENSIONS

Initial Sample Length (in)	6.15
Initial Sample Diameter (in)	2.86
Initial Sample Area (in ²)	6.42
Initial Sample Volume (in ³)	39.50

VOLUME CHANGE


Volume After Consolidation (in ³)	34.89
Length After Consolidation (in)	5.75
Area After Consolidation (in ²)	6.064

Strain (%)	Deviation Stress	ΔU	$\bar{\sigma}_1$	$\bar{\sigma}_3$	Effective Principle Stress Ratio	\bar{A}	\bar{P}	Q
0.02	0.54	-0.20	22.94	22.4	1.024	-0.37	22.67	0.27
0.04	2.06	-0.13	24.39	22.3	1.092	-0.07	23.36	1.03
0.14	5.83	2.26	25.76	19.9	1.292	0.39	22.85	2.91
0.24	7.73	3.99	25.94	18.2	1.425	0.52	22.08	3.87
0.33	8.85	5.28	25.78	16.9	1.523	0.60	21.35	4.43
0.49	9.82	6.68	25.35	15.5	1.633	0.69	20.43	4.91
0.63	10.46	7.67	24.99	14.5	1.720	0.74	19.76	5.23
0.84	11.34	8.63	24.91	13.6	1.836	0.77	19.24	5.67
1.21	11.50	9.89	23.81	12.3	1.934	0.87	18.06	5.75
1.74	12.30	11.15	23.36	11.1	2.113	0.92	17.20	6.15
2.40	13.34	12.13	23.41	10.1	2.325	0.92	16.74	6.67
3.05	14.06	12.81	23.46	9.4	2.497	0.92	16.42	7.03
3.80	14.08	13.38	22.90	8.8	2.597	0.96	15.86	7.04
4.32	13.65	13.68	22.17	8.5	2.603	1.01	15.34	6.83
5.09	13.05	14.12	21.13	8.1	2.614	1.09	14.61	6.53
6.11	12.09	14.57	19.72	7.6	2.584	1.22	13.67	6.04
13.13	12.16	15.73	18.63	6.5	2.880	1.31	12.55	6.08
13.37	11.34	15.73	17.81	6.5	2.753	1.40	12.14	5.67
13.60	11.32	15.72	17.80	6.5	2.748	1.40	12.14	5.66
13.85	11.24	15.76	17.69	6.4	2.745	1.42	12.06	5.62
14.30	10.69	15.76	17.13	6.4	2.659	1.49	11.79	5.34
15.26	10.81	15.79	17.22	6.4	2.687	1.48	11.82	5.41

**CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS**
AASHTO T-297



Client: ESP Associates Location: -L-STA 217+15, 23' RT
 Client Reference: R-1015 Site 9 MSE Wall CS34.368 Depth (ft): 9.8-11.8
 Project No.: R-2018-181-001 Sample No.: ST-3
 Lab ID: R-2018-181-001-001
 Visual Description: TAN CLAYEY SAND (UNDISTURBED)



Tested By: 129-04-0411 Date: 7/2/18 Approved By: MPS Date: 7/16/18



**CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS
AASHTO T-297**



**CONSOLIDATED UNDRAINED TRIAXIAL TEST
WITH PORE PRESSURE READINGS
AASHTO T-297**

Client: ESP Associates
 Client Reference: R-1015 Site 9 MSE Wall CS34.368
 Project No.: R-2018-181-001
 Lab ID: R-2018-181-001-001

Location: -L-STA 217+15, 23'
 Depth (ft): 9.8-11.8
 Sample No.: ST-3

Client: ESP Associates
 Client Reference: R-1015 Site 9 MSE Wall CS34.368
 Project No.: R-2018-181-001
 Lab ID: R-2018-181-001-001 Specific Gravity (Measured) 2.66

Visual Description: TAN CLAYEY SAND (UNDISTURBED)

SAMPLE CONDITION SUMMARY

	-L-STA 217+15, 23' RT	-L-STA 217+15, 23' RT	-L-STA 217+15, 23' RT
Location:	-L-STA 217+15, 23' RT	-L-STA 217+15, 23' RT	-L-STA 217+15, 23' RT
Depth (ft):	9.8-11.8	9.8-11.8	9.8-11.8
Sample No.:	ST-3	ST-3	ST-3
Test No.	T1	T2	T3
Deformation Rate (in/min)	0.0006	0.0006	0.0006
Back Pressure (psi)	40.0	40.0	40.0
Consolidation Time (days)	2	2	2
Moisture Content (%) (INITIAL)	64.2	64.2	64.2
Total Unit Weight (pcf)	99.7	99.3	100.8
Dry Unit Weight (pcf)	60.7	60.5	61.4
Moisture Content (%) (FINAL)	67.1	63.1	52.4
Initial State Void Ratio, e	1.735	1.745	1.705
Void Ratio at Shear, e	1.659	1.621	1.390

TEST 1 INITIAL



TEST 1 FINAL



TEST 2 INITIAL



TEST 2 FINAL



TEST 3 INITIAL



TEST 3 FINAL



Tested By: 129-04-0411 Date: 7/2/18 Input Checked By: GEM Date: 7/16/18

Tested By 129-04-0411 Date 7/2/18

Approved By MPS Date 7/16/18