


TYPICAL EXPOSED PILE END BENT 1 & 2
SEE SLOPE PROTECTION REPAIR DETAILS
FOR LOCATION AND QUANTITIES



FIGURE A



TYPICAL SECTION

	AS-BUILT REPAIR QUANTITY TABLE				
	END BENT 2 REPAIRS	QUANTITIES			
		ESTIMATE		ACTUAL	
	SHOTCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF
	CAP	0	0		
	CURTAINWALL	3.0	1 . 5		
	WINGS	0	0		
	CONCRETE REPAIRS	AREA SF	VOLUME CF	AREA SF	VOLUME CF
	CAP	0	0		
	CURTAINWALL	0	0		
	WINGS	1.2	0.6		
	EPOXY COATING	AREA SF		AREA SF	
	CAP	442			

NOTES

VALUES IN CHART REPRESENT ESTIMATED REPAIR TOTALS AFTER REMOVAL OF UNSOUND CONCRETE, MINIMUM OF 1"BEHIND REBAR AND MINIMUM OF 2" CLEARANCE TO SAWCUT. FOR REPAIR DETAILS, SEE "TYPICAL CAP AND COLUMN REPAIR DETAILS" SHEET.

REPAIR LOCATIONS AND ESTIMATE OF QUANTITIES ARE BASED ON THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER SHALL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATION AND DESCRIPTION OF THE REPAIRS AND ENTER THE ACTUAL QUANTITIES INTO THE AS-BUILT REPAIR QUANTITY TABLE.

CLEAN AND REMOVE DEBRIS FROM THE TOP OF THE CAP AND APPLY EPOXY PROTECTIVE COATING. EPOXY COATING SHALL BE APPLIED TO THE TOP SURFACE OF THE CAP AND TO THE TOP SURFACE OF THE PILE CAPS. THE CONTRACTOR SHALL NOT COAT THE AREA OF THE CAP BENEATH THE MASONRY PLATES. FOR EPOXY COATING, SEE SPECIAL PROVISIONS.


CONCRETE REPAIRS MAY BE SUBSTITIUTED IN LIEU OF SHOTCRETE REPAIRS WITH THE APPROVAL OF THE ENGINEER.

FOR SHOTCRETE REPAIRS, SEE SPECIAL PROVISIONS.


FOR CONCRETE REPAIRS, SEE SPECIAL PROVISIONS.

FOR EPOXY RESIN INJECTION (ERI), SEE SPECIAL PROVISIONS.

CONTRACTOR TO DETERMINE SIZE OF MISSING UTILITY COVER PLATE, SEE FIGURE A.



SHOTCRETE REPAIR AREA




CONCRETE REPAIR AREA (FORM AND POUR)



EPOXY RESIN INJECTION (ERI)

PROJECT NO. I-5769 MECKLENBURG COUNTY BRIDGE NO. 590227



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION SUBSTRUCTURE

END BENT 2

SHEET NO REVISIONS S3-12 NO. BY: DATE: DATE: DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

_ DATE : 08/2018 _ DATE : 12/2018 N.A. PIERCE DRAWN BY : _ D.A. CANTRELL CHECKED BY :