PROJECT REFERENCE NO.

SHEET NO. 48793.31 /Α

ROADWAY DESIGN **ENGINEER** SEAL' 039183

INDEX OF SHEETS, GENERAL NOTES, AND STANDARD DRAWINGS

TITLE SHEET INDEX OF SHEETS, GENERAL NOTES, AND STANDARD DRAWINGS CONVENTIONAL SYMBOLS PAVEMENT SCHEDULE AND TYPICAL SECTIONS

2A-1 THRU 2A-4ROADWAY DETAIL SHEET SPECIAL DETAILS IN LIEU OF STANDARDS

2C-1 THRU 2C-6 2G-1 THRU 2G-18 GEOTECHNICAL DETAILS ROADWAY SUMMARY SHEET 3D-1 THRU 3D-2 DRAINAGE SUMMARY SHEETS 3 G GEOTECHNICAL SUMMARY 3P PARCEL INDEX SHEET

INDEX OF SHEETS

4 - 6PLAN SHEETS 7 - 9PROFILE SHEETS RIGHT OF WAY SHEETS RW01 THRU RW06 TRAFFIC MANAGEMENT PLANS TMP-1 THRU TMP-9 PMP-1 THRU PMP-4 PAVEMENT MARKING PLANS EC-1 THRU EC-12 EROSION CONTROL PLANS SIGN-1 THRU SIGN-4 SIGNING PLANS S-1 THRU S-107 STRUCTURE PLANS

CROSS SECTION INDEX X-1AX-1BCROSS SECTION SUMMARY

CROSS SECTIONS X-1 THRU X-45

2018 SPECIFICATIONS GENERAL NOTES: EFFECTIVE: 01-16-2018

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II MODIFIED.

SUPERELEVATION:

1 A

1 B

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NOS. 225.04 AND 225.05 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS, SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

TEMPORARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC NOT SHOWN ON THE PLANS WILL BE PAID FOR AT THE CONTRACT PRICE FOR "TEMPORARY SHORING".

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE CENTURY LINK, DUKE ENERGY PROGRESS (DISTRIBUTION AND AERIAL LIGHTING). ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS, EXCEPT AS SHOWN ON THE PLANS.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



4505 Falls of Neuse Road, Suite 1 Raleigh, North Carolina 27609 Phone: 803-822-0333

EFF. 01-16-2018 REV.

2018 ROADWAY ENGLISH STANDARD DRAWINGS

876.02 Guide for Rip Rap at Pipe Outlets

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2018 are applicable to this project and by reference hereby are considered a part of these plans:

```
TITLE
DIVISION 2 - EARTHWORK
200d02 Method of Clearing - Modified Method II (Detail in Lieu of Standard)
225.01 Guide for Grading Subgrade - Interstate and Freeway
225.02 Guide for Grading Subgrade - Secondary and Local
        Method of Obtaining Superelevation - Two Lane Pavement
225.05 Method of Obtaining Superelevation - Divided Highways
         Rock Plating
DIVISION 3 - PIPE CULVERTS
300.01 Method of Pipe Installation
DIVISION 4 - MAJOR STRUCTURES
422.01 Bridge Approach Fills - Type I Standard Approach Fill
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS
560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I
DIVISION 6 - ASPHALT BASES AND PAVEMENTS
654.01 Pavement Repairs
DIVISION 8 - INCIDENTALS
815.02 Subsurface Drain
          Concrete Pads
816.01
         Brick Catch Basin - 12" thru 54" Pipe
Concrete Catch Basin - 12" thru 54" Pipe
840.01
        Frame, Grates and Hood - for Use on Standard Catch Basin
          Concrete Grated Drop Inlet Type 'B' - 12" thru 36" Pipe
840.22 Frames and Wide Slot Sag Grates
         Frames and Narrow Slot Sag Grates
          Anchorage for Frames - Brick or Concrete or Precast
          Brick Grated Drop Inlet Type 'B' - 12" thru 36" Pipe
840.29 Frames and Narrow Slot Flat Grates
          Concrete Junction Box - 12" thru 66" Pipe
840.31
          Brick Junction Box - 12" thru 66" Pipe
840.32
          Traffic Bearing Grated Drop Inlet - for Cast Iron Double Frame and Grates
840.35
840.54
          Manhole Frame and Cover
          Concrete and Brick Pipe Plug
840.71
          Concrete Curb, Gutter and Curb & Gutter
846.01
          Drop Inlet Installation in Shoulder Berm Gutter
846.04
852.01
          Concrete Islands
          Method for Placement of Drop Inlets in Concrete Islands
852.06
852D06
          Method for Placement of Drop Inlets in Concrete Islands (Detail in Lieu of Standard)
852.10
          Median Construction - with Curb and Gutter
862.01
          Guardrail Placement
          Guardrail Installation
862.02
          Guardrail Installation (Detail in Lieu of Standard - Sheet 6 of 8)
862D02
862.03
          Structure Anchor Units
          Structure Anchor Units (Detail in Lieu of Standard - Sheet 1 of 7)
862D03
876.01 Rip Rap in Channels
```