PROJECT REFERENCE NO.	SHEET NO.
48793.3.1	EC-03
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	L	110+50	112+00	LT	275
5,6	L	125+45	128+00	LT	465
6	L	130+00	132+00	LT	365
				SUBTOTAL	1,105
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					16,565
				TOTAL	17,670
				SAY	17,765

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
6	L	128+00	130+00	LT	365
				SUBTOTAL	365
ADDITIONAL PSRM TO BE INSTALLED					0
				TOTAL	365
				SAY	400