

F.A. PROJECT NO .: NHPP-0040(032)

## NOTES

GENERAL DRAWING INFORMATION IS TAKEN FROM THE ORIGINAL PLANS AND THE ROUTINE INSPECTION REPORT DATED 8/7/2018.

BRIDGE ORIENTATION CONFORMS TO THE EXISTING BRIDGE PLANS/ROUTINE INSPECTION.

EXISTING GROUND

\_FILL FACE @ END BENT 2

I HEREBY CERTIFY THAT THIS STRUCTURE WAS REHABILITATED ACCORDING TO THESE PLANS OR AS NOTED HEREIN.

RESIDENT ENGINEER

DATE

## SCOPE OF WORK

PARTIALLY REMOVE TOP OF BRIDGE DECK CONCRETE BY SCARIFICATION AND SHOTBLASTING METHODS. APPLY DECK SEALANT TO PREPARED TOP OF BRIDGE DECK. REMOVE EXISTING JOINT MATERIAL AND INSTALL FOAM JOINTS.

REMOVE UNSOUND CONCRETE AND PROPERLY PREPARE EXISTING END BENT AND BENT AREAS AND PERFORM SHOTCRETE AND/OR CONCRETE REPAIRS.

CLEAN AND EPOXY COAT EXISTING PRESTRESSED CONCRETE GIRDER ENDS.

REMOVE DEBRIS FROM TOP OF EXISTING END BENT AND BENT CAPS AND APPLY EPOXY COATING. EPOXY RESIN INJECTION OF CONCRETE CRACKS.

TO WINSTON SALEM

PRASAD

Krishna P. Sedar

-EA6F794150BF4B7.

TH CARO

SEESSION,

SEAL 22005

ACINEE

F8B6AD6DB2FC48F

FILL FACE @ END BENT 2

	PROJECT NO	I-5795
	FORSYTH	
	BRIDGE NO	330162
8/4/2020 NTH CAROLINA NORTH CAROLINA CEESSION	STATE OF NOT DEPARTMENT OF RALL	

GENERAL DRAWING FOR BRIDGE ON I-40 WBL OVER MUDDY CREEK

	REVISIONS				SHEET NO.	
DOCUMENT NOT CONSIDERED	NO. BY:	DATE:	N0.	BY:	DATE:	S16-01
FINAL UNLESS ALL	1		3			TOTAL SHEETS
SIGNATURES COMPLETED	2		4			5