PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.01.10321.1, etc.	40	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPH. REQUIRED	LENGTH	WIDTH	BORROW	REM. OF EXI. CONC. PAVEMENT	GEO-TEXTILE FOR SOIL STABILIZATION	SHOULDER GRADING	SHALLOW UNDER-CUT	CLASS IV SUB-GRADE STABILIZATION	INC. STONE BASE	ASB	1½" MILLING	0" TO 1.5" MILLING	INC. MILLING	BASE COURSE, B25.0C	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXI. PAVEMENT	4" CONC SIDEWALK	RETROFIT EXI. CURB RAMP	CONC CURB RAMP	REM. & REPL. CURB RAMPS	REM. & REPL. DRIVEWAY APRON	2' 6" CONC CURB & GUTTER	REM. CURB RAMPS	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOXES	PORTABLE LIGHTING	TEMP. SILT FENCE	WATTLE	SEED & MULCHING	RESP. FOR EC	INDUCTIVE LOOP SAWCUT	PED. CHANNELIZING DEVICES	PED. TRANSPORT. SERV.	AUD. WARNING DEVICE
									MI	FT	CY	SY	SY	SMI	CY	TON	TONS	TON	SY	SY	SY	TONS	TONS	TONS	TON	TONS	SY	EA	EA	EA	SY	LF		EA	EA	LS	LF	LF	AC	EA	LF	LF	EA	EA
2021CPT.05.01.10321.1	Durham	1	US 501 (N. DUKE ST)	S. END OF I-85 BRG. TO SR 1443 (HORTON RD)	1	5	NO	NO	1.99	62-84									78,140		4,492			7,301	438	160	18	21	5	39		651	48	28	5	0.45					10,227	60	15	4
		2	BUS 501 (N. ROXBORO ST)	I-85 TO US 501	1	3	NO	NO	3.07	29-64		207	207.1		69	131			99,778		6,624	125		9,404	570	620	43	27	3	29	42	75	4	18	7	0.45					11,232			
		TOTAL FOR PROJ NO. 2021CPT.05.01.10321.1							**5.06**			**207**	**207.1**		**69**	**131**			**177,918**		**11,116**	**125**		**16,705**	**1,008**	**780**	**61**	**48**	**8**	**68**	**42**	**726**	**52**	**46**	**12**	**0.90**					**21,459**	**60**	**15**	**4**
2021CPT.05.01.20321.1	Durham	3	SR 1305 (MT SINAI RD)	ORANGE CO TO SR 1306 (ERWIN ROAD)	3	2	NO	NO	0.34	20-36	17			0.68			17	31			453		549		37	150		1									25	70	0.25					
		4	SR 1306 (ERWIN RD)	ORANGE CO TO SR 1308 (W CORNWALLIS ROAD)	3	2	NO	NO	1.48	24-36	62			2.49			62	115		1,133	1,135		2,133		143	150	3	3				16	1	1	1		91	230	0.91					
		5	SR 1332 (SANDY CREEK DR)	SR 1303 (PICKETT RD) TO DEAD END	2	2	NO	NO	0.63	20-26	47			1.26			32	29	7,507		330		683		46	20											69	180	0.69					
		6	SR 1413 (HILLANDALE RD)	SR 1404 (ROSE OF SHARON RD) TO PVMT JOINT	3	2	NO	NO	0.22	20-22	11			0.44			11	20			383		264		18	35	18	1		1		54	2				16	40	0.16					
		7	SR 1443 (HORTON RD)	US 501 TO US 501 BUS	1	4	NO	NO	0.1	48									2,816		554			298	18	100	12	2	1							0.10								
		8	SR 1639 (INFINITY RD)	1800" EAST OF US 501 TO SR 1631 (SNOW HILL RD)	3	2	NO	NO	2.45	22-33	112			4.49			112	208		290	1,123		3,259		218	300	18			2		36		2	5		163	410	1.63	1				
		9	SR 1884 (PERVIS RD)	SR 1800 (CHEEK RD) TO SR 1675 (JUNCTION ROAD)	2	2	NO	NO	0.46	18	46			0.92			23		4,858		434		461		31	205											67	170	0.67					
		10	SR 2295 (ARCHDALE DR/ S. ROXBORO ST)	SR 1146 (MLK) TO SR 1158 (CORNWALLIS RD)	2	2	NO	NO	1.04	20-40	42			1.70			42	79	14,909		1,044		1,389		93	140		3	2	2							62	160	0.62		1,035			
		11	SR 2324 (WESCOTT PL)	SR 2323 (HEATHER GLEN RD) TO CUL-DE-SAC	4	2	NO	NO	0.1	20							5						82		5	5																			
		12	SR 2328 (FALKIRK DR)	END OF MAINTENANCE TO END OF MAINTENANCE	4	2	NO	NO	0.55	20							28						374		25	60																	50	15	3
		13	SR 2329 (ST CLAIR PL)	SR 2328 (FALKIRK DR) TO CUL-DE-SAC	4	2	NO	NO	0.05	20							3						49		3	5																			
		14	SR 2351 (TROON LN)	SR 2352 (INVERNESS DRIVE) TO SR 1449 (UMSTEAD ROAD)	4	2	NO	NO	0.26	20							13				1,465		186		12	100																			
		15	SR 2382 (TAVISTOCK DR)	SR 2352 (INVERNESS DRIVE) TO SR 2393 (SONNETT PLACE)	4	2	NO	NO	0.65	20							33						442		30	75																			
		16	SR 2392 (CANTER PL)	SR 2350 (SADDLE DR) TO CUL-DE-SAC	4	2	NO	NO	0.1	20							5						84		6	5																			
		17	SR 1520 (LILLIE DR)	SR 1453 (BIVINS RD) TO END OF MAINTENANCE	4	2	NO	NO	0.28	18							14				726		176		12	202																			
		18	SR 2323 (HEATHER GLEN RD)	SR 1451 (RUSSELL RD) TO SR 2328 (FALKIRK DR)	4	2	NO	NO	0.24	20							12				1,379		172		12	40																			
		19	SR 2350 (SADDLE DR)	SR 1450 (CRAIG RD) TO SR 2352 (INVERNESS DR)	4	2	NO	NO	0.28	20							14				1,174		198		13	30																			
		20	SR 2352 (INVERNESS DR)	SR 1449 (UMSTEAD RD) TO CUL-DE-SAC	4	2	NO	NO	1.02	20							51				1,586		720		48	560															1				
		TOTAL FOR PROJ NO. 2021CPT.05.01.20321.1							**10.25**		**337**			**11.98**			**477**	**482**	**30,090**	**1,423**	**11,786**		**11,221**	**298**	**770**	**2,182**	**51**	**10**	**3**	**5**		**106**	**3**	**3**	**6**	**0.10**	**493**	**1,260**	**4.93**	**2**	**1,035**	**50**	**15**	**3**
2021CPT.05.01.20322.1	Durham	21	SR 2359 (QUINCEMOOR RD)	SR 2328 (FALKIRK DR) TO SR 2393 (SONNETT PL)	4	2	NO	NO	0.34	20							17						231		16	65																			
		22	SR 2365 (SPLIT RAIL PL)	SR 1450 (CRAIG RD) TO SR 2382 (TAVISTOCK DR)	4	2	NO	NO	0.29	20							15				1,890		209		14	20																			
		23	SR 2372 (CARDRIFF PL)	SR 2359 (QUINCEMOOR RD) TO CUL-DE-SAC	4	2	NO	NO	0.1	20							5						86		6	130																			
		24	SR 2373 (KILTSHIRE RD)	SR 2359 (QUINCEMOOR RD) TO END OF MAINTENANCE	4	2	NO	NO	0.41	20							21						279		19	155																			
		25	SR 2378 (SHANTERCLIFF PL)	SR 2359 (QUINCEMOOR RD) TO CUL-DE-SAC	4	2	NO	NO	0.07	20							4						62		4	30																			
		26	SR 2383 (MUIRFIELD CT)	SR 2382 (TAVISTOCK DR) TO CUL-DE-SAC	4	2	NO	NO	0.15	20							8						121		8	145																			
		27	SR 2391 (GLENEAGLES PL)	SR 1451 (RUSSELL RD) TO SR 2352 (INVERNESS DR)	4	2	NO	NO	0.12	20							6				1,448		91		6	175																	50	15	3
		28	SR 2393 (SONNETT PL)	SR 2359 (QUINCEMOOR RD) TO CUL-DE-SAC	4	2	NO	NO	0.05	20							3						42		3	35																			
		29	SR 2415 (PERTH PL)	SR 2328 (FALKIRK DR) TO CUL-DE-SAC	4	2	NO	NO	0.06	20							3						57		4	36																			
		30	SR 2431 (FAIRNTOSH PL)	SR 2328 (FALKIRK DR) TO CUL-DE-SAC	4	2	NO	NO	0.11	20							6						92		6	110																			
		31	SR 2447 (PRESCOTT DR)	SR 2373 (KILTSHIRE RD) TO END OF MAINTENANCE	4	2	NO	NO	0.25	20							13				1,410		179		12	190																			
		32	SR 2448 (TRAWICK PL)	SR 2373 (KILTSHIRE RD) TO END OF MAINTENANCE	4	2	NO	NO	0.12	20							6						102		7	58																			
		33	SR 2464 (ROTHBURY DR)	SR 1451 (RUSSELL RD) TO END OF MAINTENANCE	4	2	NO	NO	0.1	20							5				1,267		76		5	15																			
		34	SR 2468 (HEATHER RIDGE CT)	SR 2382 (TAVISTOCK DR) TO CUL-DE-SAC	4	2	NO	NO	0.2	20							10						155		10	110																			
		TOTAL FOR PROJ NO. 2021CPT.05.01.20322.1							**2.37**								**122**				**6,015**		**1,782**		**120**	**1,274**																	**50**	**15**	**3**
		GRAND TOTAL							**17.68**		**337**	**207**	**207.1**	**11.98**	**69**	**131**	**599**	**482**	**208,008**	**1,423**	**28,917**	**125**	**13,003**	**17,003**	**1,898**	**4,236**	**112**	**58**	**11**	**73**	**42**	**832**	**55**	**49**	**18**	**1**	**493**	**1,260**	**4.93**	**2**	**22,494**	**160**	**45**	**10**