

SIGN NUMBER: 1 TYPE: STATIONARY QUANTITY: 12 SIGN WIDTH: 4'-0" HEIGHT: 1'-6" TOTAL AREA: 6 Sq.Ft. BORDER TYPE: INSET RECESS: 0.47" WIDTH: 0.63" RADII: 1.50" NO. Z BARS: LENGTH:	BACKG COLOR: Fluorescent Orange COPY COLOR: Black <table border="1"> <tr> <th>SYMBOL</th> <th>X</th> <th>Y</th> <th>WID</th> <th>HT</th> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </table> MAT'L: 0.080" (2.0 mm) ALUMINUM	SYMBOL	X	Y	WID	HT																																																								DESIGN BY: A. MCSWAIN PROJECT ID: BR-0117 CHECKED BY: J. DUKE LOCATION: NORTHAMPTON COUNTY DATE: 11/15/2019 DIV: 1
SYMBOL	X	Y	WID	HT																																																										

USE NOTES: 1,2

- Legend and border shall be direct applied non-reflective sheeting.
- Background shall be NC Grade B fluorescent orange retroreflective sheeting.

BORDER
 R=1.5"
 TH=0.63"
 IN=0.47"

Spacing Factor is 1 unless specified otherwise

LETTER POSITIONS

Letter spacings are to start of next letter

Letter Spacings													Series/Size		
H	A	R	G	R	A	V	E	S	R	D				Text Length	
6.9	9.7	12.8	15.7	18.7	21.3	24.1	27.2	29.7	31.9	35.9	38.8				C 2000 34.2

FILENAME: Guidesign_Design NORTH CAROLINA D.O.T. SIGN DETAIL

2/14/2020
 BR-0117_TC_TMP_Sign_Design.dgn
 User: jdebbono

APPROVED: _____ DATE: _____ 2/24/2020 DocuSigned by: 80253AD0C6829400			<h2>SIGN DESIGN</h2>
---	--	--	----------------------

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED