COMPUTED BY: AJM DATE: 06/13/19
CHECKED BY: JPM DATE: 06/13/19

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
BR-0117	X-1A

PREPARED IN THE OFFICE OF: KSINGER CAMPO & ASSOCIATES
NC FIRM LICENSE No: C-1506
301 Fayetteville St., Suite 1500
Raleigh, NC 27601
(919)882-7839

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

CROSS-SECTION SUMMARY

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	0	0
10+55.00	0	0
11+00.00	0	3
11+50.00	0	11
12+00.00	0	38
12+50.00	0	77
13+00.00	0	131
13+50.00	0	188
13+77.66	0	116
14+75.03	0	0
15+00.00	0	95
15+50.00	0	160
16+00.00	5	89
16+50.00	12	33
17+00.00	9	13
17+50.00	4	4
17+55.00	0	0

Note: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Fine Grading, Clearing and Grubbing, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading."

Note: Embankment column does not include backfill for undercut.

12/06/07

19-FEB-2020 15:12
BR-0117_cg_sum_x-section.dgn
dbpope