



TYPICAL SECTION NO. 1

MAP NO. 4
SR 1219 (LUTHER BANKS RD.)
MP 0.00 - MP 2.99

MAP NO. 7
SR 1307 (FRANCKTOWN RD.)
MP 0.00 - MP 2.05

MAP NO. 9
SR 1211 (FIRE TOWER RD.)
MP 0.00 - MP 4.16

MAP NO. 8
SR 1304 (PETERSBURG RD.)
MP 0.00 - MP 1.76

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1" DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 110 LBS. PER SQ.YD.
C2	PROP. APPROX. 1½" DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ.YD.
C3	PROP. APPROX. 3" DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ.YD. IN EACH OF TWO LAYERS.
C4	PROP. APPROX. 1" DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S4.75A, AT AN AVERAGE RATE OF 110 LBS. PER SQ.YD.
T	EARTH MATERIAL (SHOULDER RECONSTRUCTION)
U	EXISTING PAVEMENT
V1	MILLING ASPHALT PAVEMENT, 1½" DEPTH

REVISIONS

01-OCT-2020 17:09
 S:\Division Resurfacing\Resurfacing Data\2021\Resurfacing\NONSLOW\RALEIGH SUBMITTAL\2021\Onslow_Typical1.dgn