PROJECT NO.		SHEET NO.
2021CPT.10.07.10901, 2021CPT.10.07.20901		20
2021CPT.10.07.20902		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW EXC.	0241000000-E GENERIC GRADING ITEM SOIL CEMENT BASE FULL DEPTH RECLAMATION	1187000000-E PORTLAND CEMENT FOR SOIL CEMENT BASE	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECON-STRUCTION	1297000000-E 2.0" MILLING	1297000000-E 1½" MILLING	1308000000-E 0" TO 2.0" MILLING	1308000000-E 0" TO 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1503000000-E INTERMEDIATE COURSE, I19.0C	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1524000000-E LEVELING COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE
										MI	FT	CY	SY	TON	TONS	SMI	SY	SY	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	SY
2021CPT.10.07.10901	Union	1	US 74 EASTBOUND	FROM SR 1223 DICKERSON BLVD TO SR 1501 SECREST SHORTCUT ROAD MP 9.56 TO 9.86	1,2	2	MD	NO	NO	0.3	38	65				0.30	9,050							1,115		67	200	
TOTAL FOR MAP NO. 1										0.3		65				0.30	9,050							1,115		67	200	
2021CPT.10.07.10901	Union	2	NC 84	FROM CONCRETE ISLAND APPROX. 270' WEST OF SR 3318 SILVERLEAF LANE TO PVMT JT APPROX. 600' EAST OF SR 1377 WESLEY CHAPEL ROAD MILEPOST 4.7 TO 6.04	5	2	2WU	NO	NO	1.34	35	550			50	2.70			620		740			3,078	1,300	269	840	23,735
TOTAL FOR MAP NO. 2										1.34		550			50	2.70			620		740			3,078	1,300	269	840	23,735
TOTAL FOR PROJ NO. 2021CPT.10.07.10901										1.64		615			50	3.00	9,050		620		740			4,193	1,300	336	1,040	23,735
2021CPT.10.07.20901	Union	3	SR 1305 KENSINGTON DRIVE	FROM SC STATE LINE TO SR 1301 WAXHAW-MARVIN ROAD MILEPOST 0 TO 0.92	3	2	2WU	NO	NO	0.92	30	280			45	1.80				710	770			1,800	655	151	600	
TOTAL FOR MAP NO. 3										0.92		280			45	1.80				710	770			1,800	655	151	600	
2021CPT.10.07.20901	Union	4	SR 1008 WAXHAW-INDIAN TRAIL ROAD	FROM SR 1327 PLEASANT GROVE CHURCH ROAD TO SR 1328 SHANNON ROAD MILEPOST 1.89 TO 4.17	5	2	2WU	NO	NO	2.35	21.5	480			190	4.70	560				530			3,720	1,825	342		29,637
TOTAL FOR MAP NO. 4										2.35		480			190	4.70	560				530			3,720	1,825	342		29,637
2021CPT.10.07.20901	Union	5	SR 1520 INDIAN TRAIL-FAIRVIEW ROAD	FROM SR 1526 CUNNINGHAM ROAD TO SR 1518 FAITH CHURCH ROAD MILEPOST 5.42 TO 6.22	6	2	2WU	NO	NO	0.82	29	335			15	1.60					410	1,840		1,175		159		
TOTAL FOR MAP NO. 5										0.82		335			15	1.60					410	1,840		1,175		159		
2021CPT.10.07.20901	Union	6	SR 1520 INDIAN TRAIL-FAIRVIEW ROAD	FROM SR 1518 FAITH CHURCH ROAD TO SR 1501 SECREST SHORTCUT ROAD MILEPOST 6.22 TO 6.7	6	2	2WU	NO	NO	0.48	24	200			150	1.00					650	1,185		745		102		
TOTAL FOR MAP NO. 6										0.48		200			150	1.00					650	1,185		745		102		
2021CPT.10.07.20901	Union	7	SR 1524 STEVENS MILL ROAD	FROM SR 1501 IDLEWILD ROAD TO SR 1004 LAWYERS ROAD MILEPOST 0 TO 2.10	3	2	2WU	NO	NO	2.15	24	260			95	3.40		220		3,287	800			3,790	1,500	325	1,220	
TOTAL FOR MAP NO. 7										2.15		260			95	3.40		220		3,287	800			3,790	1,500	325	1,220	
2021CPT.10.07.20901	Union	8	SR 1005 LANDSFORD ROAD	FROM SR 2102 MEDLIN ROAD TO PAVEMENT JOPINT AT SR 2113 LANEY ROGERS ROAD MILEPOST 4.5 T0 5.7	6	2	2WU	NO	NO	1.2	21.5	500			110	2.40					393	2,370		1,440		200		
TOTAL FOR MAP NO. 8										1.2		500			110	2.40					393	2,370		1,440		200		
2021CPT.10.07.20901	Union	9	SR 1719 OLIVE BRANCH ROAD	FROM US 74 TO SR 1735 EAST UNION STREET MILEPOST 8.7 TO 8.95	4	2	2WU	NO	NO	0.25	24							3,800			40			440		26		
TOTAL FOR MAP NO. 9										0.25								3,800			40			440		26		
2021CPT.10.07.20901	Union	10	SR 3095 POSTAGE WAY	FROM SR 3096 POST OFFICE DRIVE TO SR 3096 POST OFFICE DRIVE	4	2	2WU	NO	NO	0.27	24							4,306						390		23	260	
TOTAL FOR MAP NO. 10										0.27								4,306						390		23	260	
2021CPT.10.07.20901	Union	11	SR 3096 POST OFFICE DRIVE	FROM SR 1008 INDIAN TRAIL ROAD TO SR 2649 CORPORATE BLVD MILEPOST 0 TO 0.34	4	2	2WU	NO	NO	0.34	24							6,146						568		34	300	
TOTAL FOR MAP NO. 11										0.34								6,146						568		34	300	
2021CPT.10.07.20901	Union	12	SR 1104 WAXHAW CREEK ROAD	FROM SR 1100 TIRZAH CHURCH ROAD TO SOUTH CAROLINA STATE LINE MILEPOST 0 TO 0.84	7	2	2WU	NO	NO	0.84	20	100	10,692.00	326.00	50	1.40							590			40		
TOTAL FOR MAP NO. 12										0.84		100	10,692.00	326.00	50	1.40							590			40		
2021CPT.10.07.20901	Union	13	SR 1100 TIRZAH CHURCH ROAD	FROM SOUTH CAROLINA STATE LINE TO SR 1104 WAXHAW CREEK ROAD MILEPOST 0 TO 1.88	8	2	2WU	NO	NO	1.88	20	200	24,379.00	853.00	115	3.80					20		1,385			93		
TOTAL FOR MAP NO. 13										1.88		200	24,379.00	853.00	115	3.80					20		1,385			93		
2021CPT.10.07.20901	Union	14	SR 1941 OLD PAGELAND-MONROE ROAD	FROM SR 1951 MOUNTAIN SPRINGS CHURCH ROAD TO SR 1937 OLD PAGELAND-MARSHVILLE ROAD MILEPOST 6.0 TO 0	8	2	2WU	NO	NO	6	19	615			540	12.00					100		4,310			289		
TOTAL FOR MAP NO. 14										6		615			540	12.00					100		4,310			289		
TOTAL FOR PROJ NO. 2021CPT.10.07.20901										17.5		2,970	35,071.00	1,179.00	1,310	32.10	560	14,472		3,997	3,713	5,395	6,285	14,068	3,980	1,784	2,380	29,637
2021CPT.10.07.20902	Union	14	SR 1941 OLD PAGELAND-MONROE ROAD	FROM SR 1951 MOUNTAIN SPRINGS CHURCH ROAD TO SR 1937 OLD PAGELAND-MARSHVILLE ROAD MILEPOST 6.0 TO 0	8	2	2WU	NO	NO	6	19		73,923.00	2,291.00														
TOTAL FOR MAP NO. 14										6			73,923.00	2,291.00														
TOTAL FOR PROJ NO. 2021CPT.10.07.20902										6			73,923.00	2,291.00														
GRAND TOTAL										25.14		3,585	108,994.00	3,470.00	1,360	35.10	9610	14,472	620	3,997	4,453	5,395	6,285	18,261	5,280	2,120	3,420	53,372