PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.09.20921.1		24

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW	0264000000-E SHOULDER GRADING	1220000000-E INCIDENTAL STONE BASE	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1½" MILLING	3" MILLING	1308000000-E 0" TO 1.25" MILLING	0" TO 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2549000000-E 2'-6" CURB & GUTTER	2591000000-E 4" CONCRETE SIDEWALK	2600000000-N RETROFIT EXISTING CURB RAMP	2605000000-N CONCRETE CURB RAMP	2613000000-N REMOVE AND REPLACE CURB RAMPS	2739000000-E REMOVE AND REPLACE 5" MONOLITHIC CONCRETE ISLANDS(KEYED IN)	2752000000-E REMOVE AND REPLALCE VALLEY GUTTER	2759000000-N REMOVE CURB RAMPS	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEED & MULCHING	5117000000-I RESPONSE FOR EROSION CONTROL	7444000000-E INDUCTIVE LOOP SAWCUT
									MI	FT	CY	SMI	TONS	TON	SY	SY	SY	SY	SY	TONS	TONS	TON	TONS	LF	SY	EA	EA	EA	SY	LF	EA	EA	EA	LF	LF	AC	EA	LF
		1	SR 1508 - MYRA RD	SR 1314 - BASHFORD RD TO DEAD END	1	2	NO	NO	0.19	22			7				421		88	180		12	129															
		2	SR 1509 - GLOSSON RD	SR 1508 - MYRA RD TO SR 1510 - GARRETT RD	1	2	NO	NO	0.11	22							517			106		7	11							150								
		3	SR 1510 - GARRETT RD	SR 1441 - STROTHER RD TO END PVMT	1	2	NO	NO	0.11	20			2				622		22	95		6	149															
		4	SR 1657 - NOWELL RD	SR 1656 - TRINITY RD TO SR 5808 - HILLSBOROUGH ST	2	2	NO	NO	1.11	24-40		1.28	28	103				1,302	2,360	1,605		108	87	33	9	13		10			2		3				1	634
		5	SR 1829 - STRICKLAND RD	SR 1822 -LEESVILLE RD TO NC 50	3	2	NO	NO	2.85	24-61	3	0.40	10	31	59,392				2,515	5,402		362	300	183	110	8		7			14				4	20	0.04	1	526
		6	SR 3009 - CREEDMOOR RD	US 70 - GLENWOOD AVE TO N END OF BRIDGE #527	5	2	NO	NO	0.19	80-83						8,917			91		1,626	98	25			1	5	1										2,462
		7	SR 3009 - EDWARD MILL RD	N END OF BRIDGE # 527 to SR 1656 - TRINITY RD	4&6	2	NO	NO	3.54	64-110		0.72	18	67	147,301				15,104		14,364	862	988	396	155	70	2	34	5		25	1	5				1	1,768
		8	SR 3232 - BOXELDER DR	SR 1826 - RAY RD TO SR 3379 - WOODVALLEY DR	2	2	NO	NO	0.65	20	65	1.30	32						167	689		46	76											94	240	0.94		
		9	SR 3233 - BUSHVELD LN	SR 3232 - BOXELDER DR TO SR 3232 - BOXELDER DR	2	2	NO	NO	0.71	20	71	1.42	35							736		49	20											103	260	1.03		
		10	SR 3234 - BAVIN PL	SR 3233 - BUSHVELD LN TO CUL-DE-SAC	2	2	NO	NO	0.1	20	10	0.20	5							134		9	10											14	40	0.14		
		11	SR 3318 - ROADSTEAD WAY	SR 3380 - CUL - DE- SAC TO CUL-DE-SAC	1	2	NO	NO	0.5	20										459		31	10															
		12	SR 3319 - TOUCHWOOD PL	SR 3318 - READSTEAD WAY TO CUL-DE-SAC	1	2	NO	NO	0.06	20										69		5																
		13	SR 3320 - CHAMISAL PL	SR 3232 - BOXELDER DR TO CUL-DE-SAC	1	2	NO	NO	0.09	20										109		7																
		14	SR 3321 - BARTONS RD	SR 3233 - BUSHVELD LN TO CUL-DE-SAC	1	2	NO	NO	0.08	20										92		6	5															
		15	SR 3322 - SMALLWOOD CT	SR 3233 - BUSHVELD LN TO CUL-DE-SAC	1	2	NO	NO	0.05	20										70		5																
		16	SR 3379 - WOODVALLEY DR	SR 1834 - NORWOOD RD TO SR 1833 - MACON RD	1	2	NO	NO	2.13	20									332	1,837		123	3														1	
		17	SR 3380 - WINDING WOOD TRL	SR 3379 - WOODVALLEY DR TO SR 3379 - WOODVALLEY	1	2	NO	NO	0.61	20										634		42																
		18	SR 3381 - TREE BARK CT	SR 3380 - WINDING WOOD TRL TO CUL-DE-SAC	1	2	NO	NO	0.11	20										125		8	10										1					
		19	SR 3382 - CABER RD	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.24	20										239		16	7															
		20	SR 3438 - CHINKAPIN PL	SR 3380 - WINDING WOOD TRL TO CUL-DE-SAC	1	2	NO	NO	0.06	20										77		5																
		21	SR 3439 - LEAFWOOD PL	SR 3380 - WINDING WOOD TRL TO CUL-DE-SAC	1	2	NO	NO	0.14	20										148		10																
		22	SR 3459 - MISTY OAK DR	SR 3379 - WOODVALLEY DR TO SR 3460 - SOMA CT	1	2	NO	NO	0.28	20										247		17	5															
		23	SR 3460 - SOMA CT	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.2	18										180		12																
		24	SR 3461 - SPIRAL WOOD CT	SR 3459 - MISTY OAK DR TO CUL-DE-SAC	1	2	NO	NO	0.06	18										77		5	2															
		25	SR 3462 - CAMBIUM CT	SR 3459 - MISTY OAK DR TO CUL-DE-SAC	1	2	NO	NO	0.06	18										74		5																
		26	SR 3467 - BENT TWIG DR	SR 3379 - WOODVALLEY DR TO SR 3468 - OAK WAY	1	2	NO	NO	0.2	18										165		11											2					
		27	SR 3468 - OAK WAY	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.18	18										165		11	6										1					
		28	SR 3469 - TWINWOOD CT	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.08	18										95		6																
		29	SR 3470 - FALLSWOOD PL	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.11	18										96		6																
		30	SR 3488 - BADEN PL	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.08	18										90		6																
		31	SR 3489 - OLD PINE CT	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.06	18										73		5																
		32	SR 3490 - NEW ARDEN WAY	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.19	18										173		12																
		33	SR 4298 - HEMINGWOOD	SR 1826 - RAY RD TO CUL-DE-SAC	1	2	NO	NO	0.16	20									124	158		11	2															
		34	SR 4299 - HEMINGWOOD CT	SR 4298 - WOODSONG CT TO CUL-DE-SAC	1	2	NO	NO	0.06	18										74		5																
		35	SR 4600 - DEER HILL CT	SR 3318 - ROADSTEAD WAY TO CUL-DE-SAC	1	2	NO	NO	0.06	18										75		5																
		36	SR 4603 - BLOSSOM HILL CT	SR 3379 - WOODVALLEY DR TO CUL-DE-SAC	1	2	NO	NO	0.47	20										424		28	10															
		37	SR 4604 - EVERGREEN CHASE WAY	SR 3379 - WOODVALLEY DR TO SR 4603 - BLOSSOM HILL	1	2	NO	NO	0.17	20										150		10																
		38	SR 4691 - CHAMBERSBURY RD	SR 1826 - RAY RD TO SR 4692 - GRALYN RD	1	2	NO	NO	0.1	18									147	85		6	5															
		39	SR 4692 - GRALYN RD	CUL-DE-SAC TO CUL-DE-SAC	1	2	NO	NO	0.26	18										248		17	4															
		40	SR 4693 - WESSEX CT	SR 4692 - GRALYN RD TO CUL-DE-SAC	1	2	NO	NO	0.03	18										50		3																
		41	SR 4694 - CHARLTON CT	SR 4692 - GRALYN RD TO CUL-DE-SAC	1	2	NO	NO	0.03	18										46		3																
		42	SR 4940 - LACEBARK LN	SR 3233 - BUSHVELD LN TO CUL-DE-SAC	1	2	NO	NO	0.14	18										139		9	6										1					
		43	SR 4941 - SANDBERRY LN	SR 1826 - RAY RD TO CUL-DE-SAC	1	2	NO	NO	0.11	18									190	121		8																
TOTAL FOR PROJ NO. 2021CPT.05.09.20921.1									16.7		149	5.32	137	201	206,693	8,917	1,560	1,302	21,140	15,811	15,990	2,018	1,870	612	274	92	7	52	5	150	41	1	13	215	560	2.15	4	5,390
GRAND TOTAL									16.7		149	5.32	137	201	206,693	8,917	1,560	1,302	21,140	15,811	15,990	2,018	1,870	612	274	92	7	52	5	150	41	1	13	215	560	2.15	4	5,390

Wake

2021CPT.05.09.20921.1