PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.08.02.10191	5	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1.5" MILLING	INC. MILLING	S9.5C	ASPHALT BINDER FOR PLANT MIX	MILLED RUMBLE STRIPS
										MI	FT	SY	SY	TONS	TONS	LF
2021CPT.08.02.	Chatham	1	US 64 EAST (INCLUDE RAMPS)	FROM PVMT JOINT AT EXIT 378 TO BRIDGE AT HAW RIVER	1	2	MD	NO	NO	9.01	31	195,011		18,020	1,081	95,206
		2	US 64 WEST (INCLUDE RAMPS)	FROM PVMT JOINT AT HAW RIVER TO PAVMNT JOINT AT EXIT 378	1	2	MD	NO	NO	9.01	31	202,824	500	18,650	1,119	95,238
GRAND TOTAL FOR PROJ NO. 2021CPT.08.02.10191										**18.02**		**397,835**	**500**	**36,670**	**2,200**	**190,444**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	441300000 WZ ADV/ GEN. WARN. SIGNING	445700000 TEMP. TRAFFIC CONTROL	451000000 LAW ENFORCEMENT	4685000000-E 4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	4688000000-E 6" X 90 M WHITE THERMO	6" X 90 M YELLOW THERMO	470000000 12" X 90 M WHITE THERMO	4725000000-E THERMO STR & RT ARROW 90 M	THERMO STR & LT ARROW 90 M	THERMO RT ARROW 90 M	THERMO LT ARROW 90 M	THERMO MERGE ARROW 90M
								MI	FT	SF	LS	HR	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA
2021CPT.08	Chatham	1	US 64 EAST (INCLUDE RAMPS)	FROM PVMT JOINT AT EXIT 378 TO BRIDGE AT HAW RIVER	1	2	MD	9.01	31	510	*	90	12,421	8,133	60,249	51,317	4,840	1	2	3	3	18
		2	US 64 WEST (INCLUDE RAMPS)	FROM PVMT JOINT AT HAW RIVER TO PAVMNT JOINT AT EXIT 378	1	2	MD	9.01	31	510		90	12,681	8,515	63,843	54,726	3,120			2	2	16
GRAND TOTAL FOR PROJ NO. 2021CPT.08.02.10191								**18.02**		**1,020**	**1**	**180**	**25,102**	**16,648**	**124,092**	**106,043**	**7,960**	**1**	**2**	**5**	**5**	**34**
													41,750		**230,135**			**47**				

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4810000000-E 4" WHITE PAINT	4" YELLOW PAINT	4815000000-E 6" WHITE PAINT	6" YELLOW PAINT	48200000 8" WHITE PAINT	4845000000-N PAINT MERGE ARROW	PAINT STR & RT ARROW	PAINT STR & LT ARROW	PAINT LT ARROW	PAINT RT ARROW	4850000 4" LINE REMOVAL	489100000 24" X 90 M WHITE THERMO	4905000000-N SNOW PLOWABLE C & R MARKERS	SNOW PLOWABLE Y & Y MARKERS
								MI	FT	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	LF	LF	EA	EA
2021CPT.08.02.10	Chatham	1	US 64 EAST (INCLUDE RAMPS)	FROM PVMT JOINT AT EXIT 378 TO BRIDGE AT HAW RIVER	1	2	MD	9.01	31	72,670	59,450	1,210	310	4,840	18	1	2	3	3	760	35	830	10
		2	US 64 WEST (INCLUDE RAMPS)	FROM PVMT JOINT AT HAW RIVER TO PAVMNT JOINT AT EXIT 378	1	2	MD	9.01	31	76,524	63,241	2,910	730	3,120	16			2	2	1,820	35	670	10
GRAND TOTAL FOR PROJ NO. 2021CPT.08.02.10191								**18.02**		**149,194**	**122,691**	**4,120**	**1,040**	**7,960**	**34**	**1**	**2**	**5**	**5**	**2,580**	**70**	**1,500**	**20**
										271,885		**5,160**			**47**							**1,520**	