

| | | |
|--------------------------|-----------|-----------|
| PROJECT NO. | SHEET NO. | TOTAL NO. |
| 2021CPT.08.03.10471, etc | 4 | |

SUMMARY OF QUANTITIES

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | SH. RECON. | ASB | 1.5" MILLING | INC. MILLING | S9.5C | ASPHALT BINDER FOR PLANT MIX | PATCHING EXISTING PAVEMENT | VACUUM TRUCK | MILLED RUMBLE STRIPS |
|---|--------|--------|-----------|---|--------|-------|-----------|--------------------------------|---------------------------|--------------|-------|--------------|--------------|----------------|--------------|---------------|------------------------------|----------------------------|--------------|----------------------|
| | | | | | | | | | | MI | FT | SMI | TON | SY | SY | TONS | TONS | TONS | WK | LF |
| 2021CPT.08.03.10471 | Hoke | 1 | US 15-501 | FROM MOORE CO LINE TO SCOTLAND CO. LINE | 1 | 2 | 2WU | NO | NO | 3.475 | 28.5 | 6.95 | 940 | 58,885 | 500 | 5,440 | 326 | 195 | 2 | 52,615 |
| TOTAL FOR PROJ NO. 2021CPT.08.03.10471 | | | | | | | | | | 3.475 | | 6.95 | 940 | 58,885 | 500 | 5,440 | 326 | 195 | 2 | 52,615 |
| 2021CPT.08.04.10631 | Moore | 2 | US 15-501 | FROM C.J. S. OF NC HWY 211 TO HOKE CO. | 1 | 2 | 2WU | NO | NO | 3.476 | 29 | 5.62 | 787 | 51,357 | 1,170 | 6,205 | 372 | 210 | 2 | 39,722 |
| TOTAL FOR PROJ NO. 2021CPT.08.04.10631 | | | | | | | | | | 3.476 | | 5.62 | 787 | 51,357 | 1,170 | 6,205 | 372 | 210 | 2 | 39,722 |
| GRAND TOTAL | | | | | | | | | | 6.951 | | 12.57 | 1,727 | 110,242 | 1,670 | 11,645 | 698 | 405 | 4 | 92,337 |

THERMOPLASTIC AND PAINT QUANTITIES

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | LENGTH | WIDTH | 4413000000-E | 445700000 | 4685000000-E | 468700000 | 470000000 | 4720000000-E | | | 4725000000-E | | | | | | |
|---|--------|--------|-----------|---|--------|-------|-----------|--------|-------|-----------------------------|---------------------|------------------------|-------------------------|-------------------------|--------------------------|----------------------|-----------------------|------------------------|----------------------|----------------------|-----------------------|---------------------------|-----------|----------|
| | | | | | | | | | | WZ ADV./ GEN. WARN. SIGNING | TEMP. TRAF. CONTROL | 4" X 90 M WHITE THERMO | 4" X 90 M YELLOW THERMO | 4" X 240 M WHITE THERMO | 12" X 90 M YELLOW THERMO | THERMO MSG STOP 90 M | THERMO MSG AHEAD 90 M | THERMO MSG SCHOOL 90 M | THERMO LT ARROW 90 M | THERMO RT ARROW 90 M | THERMO STR ARROW 90 M | THERMO LT & RT ARROW 90 M | | |
| | | | | | | | | | | SF | LS | LF | LF | LF | LF | EA | EA | EA | EA | EA | EA | EA | | |
| 2021CPT.08.03.10471 | Hoke | 1 | US 15-501 | FROM MOORE CO LINE TO SCOTLAND CO. LINE | 1 | 2 | 2WU | 3.475 | 28.5 | 389 | * | 36,780 | 20,755 | 850 | | 8 | 10 | | | | | | | |
| TOTAL FOR PROJ NO. 2021CPT.08.03.10471 | | | | | | | | | | 3.475 | | 389 | * | 36,780 | 20,755 | 850 | | 8 | 10 | | | | | |
| | | | | | | | | | | | | 57,535 | | | | 18 | | | | | | | | |
| 2021CPT.08.04.10631 | Moore | 2 | US 15-501 | FROM C.J. S. OF NC HWY 211 TO HOKE CO. | 1 | 2 | 2WU | 3.476 | 29 | 389 | * | 37,920 | 30,480 | | 330 | | | 12 | 17 | 4 | 10 | 1 | | |
| TOTAL FOR PROJ NO. 2021CPT.08.04.10631 | | | | | | | | | | 3.476 | | 389 | * | 37,920 | 30,480 | | 330 | | 12 | 17 | 4 | 10 | 1 | |
| | | | | | | | | | | | | 68,400 | | | | 12 | | | 32 | | | | | |
| GRAND TOTAL | | | | | | | | | | 6.951 | | 778 | 1 | 74,700 | 51,235 | 850 | 330 | 8 | 10 | 12 | 17 | 4 | 10 | 1 |
| | | | | | | | | | | | | 125,935 | | | | 30 | | | 32 | | | | | |

| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | LENGTH | WIDTH | 4810000000-E | | 482500000 | 483500000 | 4840000000-N | | 4845000000-N | | | | 4891000000 | 4905000000-N | | | |
|---|--------|--------|-----------|---|--------|-------|-----------|--------|-------|----------------|-----------------|------------------|-----------------|-----------------|----------------|----------------|----------------|-----------------|---------------------|-------------------------|-------------------------------------|-------------------------------------|------------|-----------|
| | | | | | | | | | | 4" WHITE PAINT | 4" YELLOW PAINT | 12" YELLOW PAINT | 24" WHITE PAINT | PAINT MSG AHEAD | PAINT MSG STOP | PAINT LT ARROW | PAINT RT ARROW | PAINT STR ARROW | PAINT LT & RT ARROW | 24" X 90 M WHITE THERMO | SNOW PLOWABLE MARKERS Y & Y MARKERS | SNOW PLOWABLE MARKERS C & R MARKERS | | |
| | | | | | | | | | | LF | LF | LF | LF | EA | EA | EA | EA | EA | EA | LF | EA | EA | | |
| 2021CPT.08.03.10471 | Hoke | 1 | US 15-501 | FROM MOORE CO LINE TO SCOTLAND CO. LINE | 1 | 2 | 2WU | 3.475 | 28.5 | 36,780 | 20,755 | | | 10 | 8 | | | | | | 75 | 218 | | |
| TOTAL FOR PROJ NO. 2021CPT.08.03.10471 | | | | | | | | | | 3.475 | | 36,780 | 20,755 | | 10 | 8 | | | | | 75 | 218 | | |
| | | | | | | | | | | | | 57,535 | | | 18 | | | | | | 75 | 218 | | |
| 2021CPT.08.04.10631 | Moore | 2 | US 15-501 | FROM C.J. S. OF NC HWY 211 TO HOKE CO. | 1 | 2 | 2WU | 3.476 | 29 | 37,920 | 30,480 | 330 | 144 | | | 17 | 4 | 10 | 1 | 144 | 309 | 50 | | |
| TOTAL FOR PROJ NO. 2021CPT.08.04.10631 | | | | | | | | | | 3.476 | | 37,920 | 30,480 | 330 | 144 | | | 17 | 4 | 10 | 1 | 144 | 309 | 50 |
| | | | | | | | | | | | | 68,400 | | | | 32 | | | | | 359 | | | |
| GRAND TOTAL | | | | | | | | | | 6.951 | | 74,700 | 51,235 | 330 | 219 | 10 | 8 | 17 | 4 | 10 | 1 | 219 | 527 | 50 |
| | | | | | | | | | | | | 125,935 | | | | 18 | | | 32 | | | 577 | | |