ENGV50059 11/9/2020 I:\Projects\4019918\4019918_0001\50_Deliverables Submittals\BR-0115\Roadway\XSC\Earthwork\BR-0115 XSC Earthwork Summary.xls
DocuSign Envelope ID: F08881BA-3F6A-461D-AE26-BA31FE511F64

PROJ. REFERENCE NO.	SHEET NO.
BR-0115	X-0

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+50.00	0	0
12+00.00	1	2
12+50.00	2	7
13+00.00	4	25
13+50.00	75	53
14+00.00	84	96
14+50.00	11	159
15+00.00	0	270

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+50.00	0	0
17+00.00	8	141
17+50.00	5	49
18+00.00	0	7
18+50.00	0	2

Station DR1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+13.43	0	0
10+25.00	0	41
10+50.00	0	81
10+75.00	0	59
11+00.00	1	33
11+20.00	1	8

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".