| PROJECT NO. | SHEET NO. | TOTAL NO. |
|---|---|---|
| 2019CPT.08.15.10631, etc | 9 | |

# THERMOPLASTIC AND PAINT QUANTITIES

| PROJECT NO / COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | LENGTH | WIDTH | 4413000 WZ ADV/ GEN. WARN. SIGNING | 4447( PED. CH. DEVICES | 4457( TEMP. TRAFFIC CONTROL | 4510( LAW ENFORCEMENT | 4685000000-E 4" X 90 M WHITE THERMO | 4" X 90 M YELLOW THERMO | 468700 4" X 240 M WHITE THERMO | 4695000000-E 8" X 90 M WHITE THERMO | 8" X 90 M YELLOW THERMO | 4720000000-E THERMO MSG ONLY 90 M | THERMO MSG EAST 90 M | THERMO MSG NC2 90 M | THERMO MSG SCHOOL 90 M | THERMO MSG XING 90MIL | THERMO RXR 90 M | 4725000000-E THERMO LT ARROW 90 M | THERMO RT ARROW 90 M | THERMO STR ARROW 90 M | THERMO STR & RT ARROW 90 M | THERMO STR & LT ARROW 90 M | THERMO MERGE ARROW 90M | 4810000000-E 4" WHITE PAINT | 4" YELLOW PAINT | 4820000000-E 8" WHITE PAINT | 8" YELLOW PAINT | 483000 16" WHITE PAINT | 4835000 24" WHITE PAINT | 4840000000-N PAINT MSG ONLY | PAINT MSG SCHOOL | PAINT MSG XING | PAINT MSG RXR | 4845000000-N PAINT LT ARROW | PAINT RT ARROW | PAINT STR ARROW | PAINT STR & RT ARROW | PAINT STR & LT ARROW | PAINT MERGE ARROW | 489100 24" X 90 M WHITE THERMO | 489100 16" X 90 M WHITE THERMO | 4905000000-N SNOW PLOWABLE C & R MARKERS | SNOW PLOWABLE Y & Y MARKERS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | MI | FT | SF | LF | LS | HR | LF | LF | LF | LF | LF | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | LF | LF | LF | LF | LF | LF | EA | EA | EA | EA | EA | EA | EA | EA | EA | EA | LF | LF | EA | EA |
| 2019CPT.08.15.10631 Moore | 1 | US 15-501 | FROM 0.17 MILES NORTH OF INTERSECTION WITH SR 1305 (MORGANTON RD) TO TRAFFIC CIRCLE (INCLUDE CIRCLE) | 1, 2, 3 | 2 | 2WU | 2.05 | 30 - 60 | 160 | | * | 160 | 32,800 | 26,300 | | 5,385 | 295 | 24 | 4 | 3 | | | | 34 | 23 | 9 | 11 | 3 | | 24,685 | 26,300 | 5,385 | 295 | | 160 | 24 | | | | 34 | 23 | 9 | 11 | 3 | | 225 | | 515 | 220 |
| | 2 | US 1 (PINEBLUFF) | FROM PVMNT JOINT +900' NORTH OF FIRE DEPT. TO JOINT 0.08 OF SR 2118 (CURRANT ST) | 1, 6, 10 | 2 | MU | 1.17 | 50 | 135 | | | | 9,730 | 13,190 | | | 578 | | | | | | | 39 | | 18 | 18 | | | 9,730 | 13,190 | | 578 | | | | | | | 39 | | 18 | 18 | | | | | 65 | 148 |
| **TOTAL FOR PROJ NO. 2019CPT.08.15.10631** | | | | | | | **3.22** | | **295** | | | **160** | **42,530** | **39,490** | | **5,385** | **873** | **24** | **4** | **3** | | | | **73** | **23** | **27** | **29** | **3** | | **34,415** | **39,490** | **5,385** | **873** | | **160** | **24** | | | | **73** | **23** | **27** | **29** | **3** | | **225** | | **580** | **368** |
| | | | | | | | | | | | | | **82,020** | | | **6,258** | | **31** | | | | | | **155** | | | | | | **73,905** | | **6,258** | | | | **24** | | | | **155** | | | | | | | | **948** |
| 2019CPT.08.15.20631 Moore | 3 | SR 1309 (MORGANTON RD) | FROM 0.07 MILES EAST OF INTERSECTION WITH US 15-501 TO PVMNT JT AT US 1 | 4,5 | 2 | MU | 1.32 | 60 | 126 | 40 | * | 80 | 5,365 | 12,365 | | 965 | | | | | | | | 29 | 6 | 21 | 4 | | | 5,400 | 12,400 | 965 | | | 945 | | | | | 29 | 6 | 21 | 4 | | | 945 | | 405 | 50 |
| **TOTAL FOR PROJ NO. 2019CPT.08.15.20631** | | | | | | | **1.32** | | **126** | **40** | | **80** | **5,365** | **12,365** | | **965** | | | | | | | | **29** | **6** | **21** | **4** | | | **5,400** | **12,400** | **965** | | | **945** | | | | | **29** | **6** | **21** | **4** | | | **945** | | **405** | **50** |
| | | | | | | | | | | | | | **17,730** | | | **965** | | | | | | | | **60** | | | | | | **17,800** | | **965** | | | | | | | | **60** | | | | | | | | **455** |
| 2021CPT.08.04.20631 Moore | 4 | SR 1318 (ARNOLD AVE) | FROM BEG STATE MAINT. TO DEAD END | 7 | 2 | 2WU | 0.2 | 18 | 45 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 5 | SR 1170 (SNOOZING PINE LN) | FROM SR 1112 (ROSELAND RD) TO DEAD END | 7 | 2 | 2WU | 0.28 | 18 | 32 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 6 | SR 1629 (PUTNAM GLENDON RD) | FROM SR 1638 (PUTNAM CH RD) TO SR 1635 (HERBIE RD) | 8 | 2 | 2WU | 0.94 | 20 | 106 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 7 | SR 1407 (MACK RD) | FROM SR 1405 (DOVER CH RD) TO SR 1409 (CHRISCO RD) | 9 | 2 | 2WU | 1.79 | 20 | 200 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 8 | SR 2077 (CAROLINA RD) | FROM HOKE CO LINE TO NC 211 | 7 | 2 | 2WU | 1.18 | 24 | 132 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 9 | SR 1843 (AIRPORT RD) | FROM PAVEMENT JOINT WEST OF ROUNDABOUT AT NC 22 TO NC 2 (MIDLAND RD) | 8 | 2 | 2WU | 2.89 | 24 | 323 | | | | 31,220 | 32,645 | | | 455 | | | | 12 | 8 | | 15 | 6 | | | | | 31,220 | 32,645 | | 455 | | 100 | | 12 | 8 | | 15 | 6 | | | | | | | 28 | 277 |
| | 10 | SR 1205 (MORGANTON RD) | FROM NC 5 TO TURNBERRY WAY | 8 | 2 | 2WU | 1.96 | 24 | 244 | | | 40 | 22,905 | 20,485 | 560 | 60 | 320 | | | | | 8 | 4 | 3 | 1 | | 6 | 4 | 6 | 22,905 | 20,485 | 60 | 320 | 100 | 294 | | | 8 | 4 | 3 | 1 | | 6 | 4 | 6 | 294 | 100 | 26 | 163 |
| **TOTAL FOR PROJ NO. 2021CPT.08.04.20631** | | | | | | | **9.24** | | **1,082** | | | **40** | **54,125** | **53,130** | **560** | **60** | **775** | | | | **12** | **16** | **4** | **18** | **7** | | **6** | **4** | **6** | **54,125** | **53,130** | **60** | **775** | **100** | **394** | | **12** | **16** | **4** | **18** | **7** | | **6** | **4** | **6** | **294** | **100** | **54** | **440** |
| | | | | | | | | | | | | | **107,255** | | | **835** | | **32** | | | | | | **41** | | | | | | **107,255** | | **835** | | | | **32** | | | | **41** | | | | | | | | **494** |
| **GRAND TOTAL** | | | | | | | **13.78** | | **1,503** | **40** | **1** | **280** | **102,020** | **104,985** | **560** | **6,410** | **1,648** | **24** | **4** | **3** | **12** | **16** | **4** | **120** | **36** | **48** | **39** | **7** | **6** | **93,940** | **105,020** | **6,410** | **1,648** | **100** | **1,499** | **24** | **12** | **16** | **4** | **120** | **36** | **48** | **39** | **7** | **6** | **1,464** | **100** | **1,039** | **858** |
| | | | | | | | | | | | | | **207,005** | | | **8,058** | | **63** | | | | | | **256** | | | | | | **198,960** | | **8,058** | | | | **56** | | | | **256** | | | | | | | | **1,897** |