PROJECT NO.	SHEET NO.
2021CPT.03.11.20821 ETC.	12

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	2830000000-N ADJUSTMENT OF MANHOLES	2845000000-N ADJUSTMENT OF METER OR VALVE BOX	6000000000-E TEMPORARY SILT FENCE	6009000000-E STONE FOR EC CLASS B	6012000000-E SEDIMENT CONTROL STONE	6015000000-E TEMPORARY MULCHING	6018000000-E SEED FOR TEMPORARY SEEDING	6021000000-E FERTILIZER FOR TEMPORARY SEEDING	6036000000-E MATTING FOR EROSION CONTROL	6042000000-E 1/4" HARDWARE CLOTH	6071010000-E WATTLE	6084000000-E SEED & MULCHING	6090000000-E SEED FOR REPAIR SEEDING	6093000000-E FERTILIZER FOR REPAIR SEEDING	6117000000-N RESPONSE FOR EROSION CONTROL
										MI	FT	EA	EA	LF	TON	TON	ACR	LBS	TON	SY	LF	LF	AC	LB	TON	EA
2021CPT.03.11.20821	Sampson	3	SR 1845 (CEDAR POINT RD. / ROSIN HILL RD.)	FROM SR 1711 (WILLIAM R. KING RD.) TO SR 1703 (CHURCH RD./MCLAMB RD.) [MP 0.00 - MP 4.72]	1 -3	2	2WU	NO	NO	4.72	19 - 23			472	118	118	4.72	236	1.18	40	236	80	4.58	236	1.18	2
TOTAL FOR MAP NO. 3										**4.72**				**472**	**118**	**118**	**4.72**	**236**	**1.18**	**40**	**236**	**80**	**4.58**	**236**	**1.18**	**2**
2021CPT.03.11.20821	Sampson	11	SR 1459 (FEED MILL RD.)	FROM SR 1456 (PENNY TEW MILL RD.) TO US 421 [MP 0.00 - MP 2.56]	1	2	2WU	NO	NO	2.56	18												2.50			2
TOTAL FOR MAP NO. 11										**2.56**													**2.50**			**2**
2021CPT.03.11.20821	Sampson	13	SR 1425 (SIVERTSEN RD.)	FROM SR 1414 (MINNIE HALL RD.) TO SR 1006 (WAXWELL RD.) [MP 0.00 - MP 4.56]	1	2	2WU	NO	NO	4.56	19			456	114	114	4.56	228	1.14	30	228	70	4.42	228	1.14	2
TOTAL FOR MAP NO. 13										**4.56**				**456**	**114**	**114**	**4.56**	**228**	**1.14**	**30**	**228**	**70**	**4.42**	**228**	**1.14**	**2**
2021CPT.03.11.20821	Sampson	14	SR 1424 (SOUTH RIVER RD.)	FROM SR 1414 (MINNIE HALL RD.) TO SR 1427 (HALLTOWN RD.) [MP 0.00 - MP 3.92]	1	2	2WU	NO	NO	3.92	20			392	98	98	3.92	196	0.98	30		60	3.92		196.98	2
TOTAL FOR MAP NO. 14										**3.92**				**392**	**98**	**98**	**3.92**	**196**	**0.98**	**30**		**60**	**3.92**		**196.98**	**2**
2021CPT.03.11.20821	Sampson	15	SR 1426 (FAIRCLOTH BRIDGE RD.)	FROM SR 1424 (S. RIVER RD.) TO CUMBERLAND COUNTY LINE [MP 0.00 - MP 0.68]	1	2	2WU	NO	NO	0.68	18			27									0.50			2
TOTAL FOR MAP NO. 15										**0.68**				**27**									**0.50**			**2**
TOTAL FOR PROJ NO. 2021CPT.03.11.20821										**16.44**				**1,347**	**330**	**330**	**13.20**	**660**	**3.30**	**100**	**464**	**210**	**15.92**	**464**	**199.30**	**10**
2021CPT.03.11.20822	Sampson	20	SR 1471 (BYNUM RD.)	FROM SR 1002 (DUNN RD.) TO SR 1454 (OLD WRENCH SCHOOL RD.) [MP 0.00 - MP 0.72]	4	2	2WU	NO	NO	0.72	19															
TOTAL FOR MAP NO. 20										**0.72**																
2021CPT.03.11.20822	Sampson	22	274 (OWENS AVE. / W. CLINTON ST. / E. CLINTON	FROM NC 242 (WEST ROSEBORO ST.) TO NC 24 (ROSEBORO HWY.) [MP 0.00 - MP 0.72]	4	2	2WU	NO	NO	0.72	22	9	7													
TOTAL FOR MAP NO. 22										**0.72**		**9**	**7**													
2021CPT.03.11.20822	Sampson	23	SR 1248 (BULLARD ST.)	FROM SR 1274 (WEST CLINTON ST.) TO SR 1271 (FISHER DR.) [MP 0.00 - MP 0.58]	4	2	2WU	NO	NO	0.58	21	6	9													
TOTAL FOR MAP NO. 23										**0.58**		**6**	**9**													
2021CPT.03.11.20822	Sampson	24	SR 1249 (DOUGLAS AVE.)	FROM BEGIN OF MAINTEANCE TO SR 1248 (BULLARD ST.) [MP 0.00 - MP 0.15]	4	2	2WU	NO	NO	0.15	21	2	1													
TOTAL FOR MAP NO. 24										**0.15**		**2**	**1**													
2021CPT.03.11.20822	Sampson	25	SR 1285 (DOUGLAS AVE.)	FROM 0.06 MILES NE OF SR 1248 (BULLARD ST.) TO SR 1251 (N. RAILROAD ST.) [MP 0.00 MP 0.10]	4	2	2WU	NO	NO	0.1	21															
TOTAL FOR MAP NO. 25										**0.1**																
2021CPT.03.11.20822	Sampson	26	SR 1271 (FISHER DR.)	FROM SR 1248 (BULLARD ST.) TO SR 1251 (HALL RD.) [MP 0.00 - MP 0.17]	4	2	2WU	NO	NO	0.17	21															
TOTAL FOR MAP NO. 26										**0.17**																
2021CPT.03.11.20822	Sampson	27	SR 1269 (CALVIN ST.)	FROM SR 1251(HALL RD.) TO SR 1249 (DOUGLAS AVE.) [MP 0.00 - MP 0.26]	4	2	2WU	NO	NO	0.26	20															
TOTAL FOR MAP NO. 27										**0.26**																
2021CPT.03.11.20822	Sampson	28	SR 1250 (BROAD ST.)	FROM NC 24 (AURTY HWY.) TO SR 1251 (N. RAILROAD ST.) [MP 0.00 - MP 0.11]	4	2	2WU	NO	NO	0.11	23	1	1													
TOTAL FOR MAP NO. 28										**0.11**		**1**	**1**													
2021CPT.03.11.20822	Sampson	29	SR 1252 (JOHNSON ST.)	FROM NC 24 (AUTRY HWY.) TO SR 1248 (BULLARD ST.) [MP 0.00 - MP 0.22]	4	2	2WU	NO	NO	0.22	19															
TOTAL FOR MAP NO. 29										**0.22**																
2021CPT.03.11.20822	Sampson	30	SR 1242 (S. WEST ST. / N. WEST ST.)	FROM END MAINTENANCE TO NC 242 (W. ROSEBORO ST.) [MP 0.00 - MP 0.69]	4	2	2WU	NO	NO	0.69	19	3														
TOTAL FOR MAP NO. 30										**0.69**		**3**														
2021CPT.03.11.20822	Sampson	31	SR 1300 (NORTH ST. / E. NORTH ST.)	FROM BEGIN OF MANTENANCE (0.07 MILES SOUTH OF NC 242) TO NC 24 (ROSEBORO HWY.) [MP 0.00 - MP 0.81]	4	2	2WU	NO	NO	0.81	19	1														
TOTAL FOR MAP NO. 31										**0.81**		**1**														