

PROJECT NO.	SHEET NO.
2021CPT.03.07.10821, ETC.	21

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1526000000-E	1575000000-E	1775500000-E	1838000000-E	1880000000-E			2591000000-E	2613000000-N	2752000000-E	
												SURFACE COURSE, S4.75A	ASPHALT BINDER FOR PLANT MIX	ASPHALT SURFACE TREATMENT, MATCOAT, #67 GRANITE	EMULSION FOR ASPHALT SURFACE TREATMENT	PATCHING EXISTING PAVEMENT (FULL DEPTH)	PATCHING EXISTING PAVEMENT (MILL)	LEVELING COURSE, S4.75A	4" CONCRETE SIDEWALK	REMOVE & REPLACE CURB RAMP	REMOVE & REPLACE 2'-6" CURB & GUTTER	
											MI	FT	TON	TON	SY	GAL	TON	TON	TON	SY	EA	LF
2021CPT.03.07.20822	Sampson	16	SR 1476 (TAYLORS CHAPEL RD.)	FROM US 13 (FAYETTEVILLE HWY.) TO SR 1607 (CHRISTMAS TREE RD.) [MP 1.65 - MP 4.48]	7	2	2WU	NO	NO	2.83	18	1,781	125					15				
TOTAL FOR MAP NO. 16											2.83		1,781	125					15			
2021CPT.03.07.20822	Sampson	17	SR 1617 (OLD US 421)	FROM US 421 (PLAIN VIEW HWY.) TO US 421 (PLAIN VIEW HWY.) [MP 0.00 - MP 0.69]	7	2		NO	NO	0.69	20	459	32					10				
TOTAL FOR MAP NO. 17											0.69		459	32					10			
2021CPT.03.07.20822	Sampson	18	SR 1616 (CORE RD.)	FROM US 421 (PLAIN VIEW HWY.) TO SR 1476 (UNION GROVE CHURCH RD.) [MP 0.00 - MP 1.29]	7	2	2WU	NO	NO	1.29	20	859	60					5				
TOTAL FOR MAP NO. 18											1.29		859	60					5			
2021CPT.03.07.20822	Sampson	19	SR 1622 (JADA ALLEN RD.)	FROM SR 1005 (GREEN PATH RD.) TO HARNETT COUNTY LINE [MP 0.00 - MP 1.19]	7	2	2WU	NO	NO	1.19	18	713	50						60			
TOTAL FOR MAP NO. 19											1.19		713	50					60			
2021CPT.03.07.20822	Sampson	21	SR 1958 (GLENN RD.)	FROM SR 1227 (TRAM RD.) TO DEAD END [MP 0.00 - MP 0.21]	7	2	2WU	NO	NO	0.21	20	140	10									
TOTAL FOR MAP NO. 21											0.21		140	10								
2021CPT.03.07.20822	Sampson	33	SR 1612 (ALDERMAN MILL RD.)	FROM SR 1607 (CHRISTMAS TREE RD.) TO SR 1002 (N. SPRING BRANCH RD.) [MP 0.00 - MP 2.86]	7	2	2WU	NO	NO	2.86	18	1,714	120						45			
TOTAL FOR MAP NO. 33											2.86		1,714	120					45			
TOTAL FOR PROJ NO. 2021CPT.03.07.20822											9.07		5,666	397					15	120		
36248.97	Sampson	35	(VANCE ST.)	FROM SR 1855 (SAMPSON ST.) TO SR 1839 (MCKOY ST.)	5	2		NO	NO	0.1	24		11									
TOTAL FOR MAP NO. 35											0.1			11								
36248.97	Sampson	36	(EAST MAIN ST.)	FROM SR 1839 (MCKOY ST. /NORTH WALL ST.) TO SR 1231 (LISBON ST.)	5	2		NO	NO	0.1	24		15									
TOTAL FOR MAP NO. 36											0.1			15								
TOTAL FOR PROJ NO. 36248.97											0.2			26								
GRAND TOTAL											29.25		8,122	2,297	129,084	51,640	85	588	300	33	9	384