PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.05.20.20921.1	46	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING	4457000000-N TEMPORARY TRAFFIC CONTROL	44470000000-E PEDESTRIAN CHANNELIZING DEVICES	4510000000-N LAW ENFORCEMENT	4600000000-N PEDESTRIAN TRANSPORT SERVICE	4600000000-N AUDIBLE WARNING DEVICE	4685000000-E 4" X 90 M WHITE THERMO	4685000000-E 4" X 90 M YELLOW THERMO	4695000000-E 8" X 90 M WHITE THERMO	4695000000-E 8" X 90 M YELLOW THERMO	4700000000-E 12" X 90 M YELLOW THERMO	4720000000-E THERMO MSG ONLY 90 M	4720000000-E THERMO MSG SCHOOL 90 M	4720000000-E THERMO Msg RxR 90 M	4725000000-E THERMO STR ARROW 90 M	4725000000-E THERMO LT ARROW 90 M	4725000000-E THERMO STR & RT ARROW 90 M	4725000000-E THERMO MERGE ARROW 90 M	4725000000-E THERMO RT ARROW 90 M	4725000000-E THERMO STR & LT ARROW 90 M	4725000000-E THERMO SYMBOL (SHARROW)
							MI	FT	SF	LS	LF	HR	EA	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
2021CPT.05.20.20921.1	Wake	24	SR 3909 - EARLE RD	SR 1382 - OLDE SOUTH RD TO SR 1501 - DONNYBROOK RD	2	2	0.7	20	74																				
		25	SR 3910 - GLEN OAK CT	SR 3909 - EARLE RD TO CUL-DE-SAC	2	2	0.1	18	10																				
		26	SR 3911 - BENT FORK CIR	SR 3909 - EARLE RD TO CUL-DE-SAC	2	2	0.1	18	6																				
		27	SR 3912 - WINDY RIDGE CT	SR 3909 - EARLE RD TO CUL-DE-SAC	2	2	0.1	18	9																				
		28	SR 3983 - MILLRACE TRL	SR 1382 - OLDE SOUTH RD TO CUL-DE-SAC	2	2	0.5	18	58																				
		29	SR 3984 - RHETT DR	SR 3983 - MILLRACE TRL TO SR 3983 - MILLRACE TRL	2	2	0.2	18	17																				
		30	SR 4020 - FORDLAND DR	SR 1383 - CAMPBELL RD TO CUL-DE-SAC	3	2	0.8	20	92																				
		31	SR 4033 - KOOMEN LN	SR 1383 - CAMPBELL RD TO DEAD END	3	2	0.2	20	19																				
		32	SR 4034 - ALLOWAY CT	SR 4033 - KOOMEN LN TO CUL-DE-SAC	3	2	0.1	18	11																				
		33	SR 4035 - TOBERMORY LN	SR 4033 - KOOMEN LN TO SR 4036 - SKIPTON CT	3	2	0.2	18	26																				
		34	SR 4036 - SKIPTON CT	SR 4035 - TOBERMORY LN TO CUL-DE-SAC	3	2	0	18	4																				
		35	SR 4061 - ENCHANTED OAKS DR	SR 4063 - BLUE SAGE DR TO SR 1371 - LAKE WHEELER RD	3	2	0.5	20	60																				
		36	SR 4062 - PAPER BIRCH CT	SR 4063 - BLUE SAGE DR TO CUL-DE-SAC	3	2	0.1	20	16	*																			
		37	SR 4063 - BLUE SAGE DR	SR 3988 - BIRCHLEAF DR TO CUL-DE-SAC	3	2	0.6	20	63																				
		38	SR 4064 - BLACK WALNUT CT	SR 4063 - BLUE SAGE DR TO CUL-DE-SAC	3	2	0.1	20	13																				
		39	SR 4067 - EDERLEE DR/REGENCY PKWY	SR 1379 - PENNY RD TO SR 1009 - TRYON RD	6	2	1.8	50-66	196		12	280	4	1	8,305	5,300	1,223	201		28	6		55	20	14		9		52
		40	SR 4070 - RELIANCE AVE	SR 1010 - TEN TEN RD TO END MAINT	7	2	0.3	30-45	28		12	40			100	400								1	1				
		41	SR 4094 - BLANEY BLUFFS LN	SR 1379 - PENNY RD TO SR 1377 - BLNY FRANKS R	3	2	0.6	20	68																				
		42	SR 4095 - DARCY LN	SR 4094 - BLNY BLUFFS TO SR 4094 - BLNY BLUFFS	2	2	0.3	18	28																				
		43	SR 4097 - MOSS POINTE LN	SR 4061 - ENCHANTED OAKS DR TO CUL-DE-SAC	3	2	0.1	18	9																				
		44	SR 4098 - HONEY LOCUST CT	SR 4061 - ENCHANTED OAKS TO CUL-DE-SAC	3	2	0.1	18	12																				
		45	SR 4783 - OAK STAND CIR	SR 3909 - EARLE RD TO CUL-DE-SAC	2	2	0.1	20	11																				
		46	SR 5040 - ROLLING OAKS LN	SR 1383 - CAMPBELL RD TO CUL-DE-SAC	3	2	0.1	20	12																				
TOTAL FOR PROJ NO. 2021CPT.05.20.20921.1							**21**		**2,297**	**1.00**	**96**	**840**	**25**	**6**	**76,645**	**91,815**	**7,457**	**201**	**1,235**	**48**	**48**	**4**	**130**	**155**	**50**	**3**	**31**	**3**	**52**
															168,460		**7,658**				**100**					**424**			
GRAND TOTAL							**21**		**2,297**	**1.00**	**96**	**840**	**25**	**6**	**76,645**	**91,815**	**7,457**	**201**	**1,235**	**48**	**48**	**4**	**130**	**155**	**50**	**3**	**31**	**3**	**52**
															168,460		**7,658**				**100**					**424**			