DocuSign Envelope ID: 49326A9B-14BF-43FE-B3B5-6FB348D429F2

PROJ. REFERENCE NO.	SHEET NO.
BR-0125	X-0

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+35.00	0	0
10+50.00	2	1
11+00.00	16	8
11+50.00	41	10
12+00.00	111	5
12+50.00	196	1
13+00.00	275	8
13+50.00	164	490
14+00.00	14	1235
14+49.56	19	1491

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+22.44	0	0
16+50.00	0	1019
17+00.00	83	1333
17+50.00	235	409
18+00.00	486	0
18+50.00	717	0
19+00.00	710	3
19+50.00	494	7
20+00.00	197	21
20+50.00	35	53
21+00.00	11	46
21+50.00	12	19
22+00.00	19	14
22+30.00	8	3

Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+15.00	0	0
10+50.00	0	20
11+00.00	0	65
11+50.00	13	39
11+67.51	9	2