

PROJECT NO.	SHEET NO.
2021CPT.14.06.10501	7

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0996000000-N	1297000000-E		1503000000-E	1523000000-E	1575000000-E	1577000000-E	1704000000-E	1839140000-E	1840000000-E		
												PIPE CLEAN OUT	1½" MILLING	4" MILLING	INTERMEDIATE COURSE, I19.0C	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ULTRA-THIN BONDED WEARING COURSE	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)		
											EA	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	TON	LF		
2021CPT.14.06.10501.1	Jackson	1	US 74/441 WEST	FROM SR-1390 TO SWAIN LINE	1	2	MU	NO	NO	6.4	36	4.00	74,500	48,500	7,000	12,305	1,074	192		3,690	67,584		
TOTAL FOR MAP NO. 1											4.00	74,500	48,500	7,000	12,305	1,074	192		3,690	67,584			
2021CPT.14.06.10501.1	Jackson	2	US 74/441 EAST	FROM SWAIN TO SR-1390	1	2	MU	NO	NO	6.4	36		74,500	48,500	7,000	12,286	1,073	192		3,690	67,584		
TOTAL FOR MAP NO. 2												74,500	48,500	7,000	12,286	1,073	192		3,690	67,584			
2021CPT.14.06.10501.1	Jackson	3	RAMP MP 74	EXIT 74 FROM US 441 TO US 74 EAST	2	2		NO	NO	0.354	25		1,662	3,532	503	436	50						
TOTAL FOR MAP NO. 3												0.354		1,662	3,532	503	436	50					
2021CPT.14.06.10501.1	Jackson	4	RAMP MP 74	EXIT 74 FROM US 74 EAST TO US441 NORTH	3	2		NO	NO	0.104	25		1,525			128	8						
TOTAL FOR MAP NO. 4												0.104		1,525			128	8					
2021CPT.14.06.10501.1	Jackson	5	RAMP MP 72	EXIT 72 FROM SR-1531 TO US 74 EAST	2	2		NO	NO	0.54	27		2,533	5,383	767	718	80						
TOTAL FOR MAP NO. 5												0.54		2,533	5,383	767	718	80					
2021CPT.14.06.10501.1	Jackson	6	RAMP MP 72	EXIT 72 FROM US 74 EAST TO SR-1531	2	2		NO	NO	0.337	25		1,582	3,362	479	415	48		60				
TOTAL FOR MAP NO. 6												0.337		1,582	3,362	479	415	48		60			
2021CPT.14.06.10501.1	Jackson	7	RAMP MP 72	EXIT 72 FROM SR-1531 TO US 74 WEST	2	2		NO	NO	0.142	30		1,083	1,417	202	210	22						
TOTAL FOR MAP NO. 7												0.142		1,083	1,417	202	210	22					
2021CPT.14.06.10501.1	Jackson	8	RAMP MP 72	EXIT 72 FROM US 74 WEST TO SR-1531	2	2		NO	NO	0.256	28		1,200	2,550	363	353	39						
TOTAL FOR MAP NO. 8												0.256		1,200	2,550	363	353	39					
TOTAL FOR PROJ NO. 2021CPT.14.06.10501.1												14.533		4.00	158,585	113,244	16,314	26,851	2,394	384	60	7,380	135,168
GRAND TOTAL												14.533		4.00	158,585	113,244	16,314	26,851	2,394	384	60	7,380	135,168