PROJ. REFERENCE NO.	SHEET NO.
BR-0009	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station PHASE 1 (DETOUR) L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+77.98	0	0
12+00.00	17	0
12+50.00	19	38
12+70.82	0	39

Station PHASE 1 (DETOUR) L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+45.86	0	0
14+00.00	0	282
14+50.00	0	107
15+00.00	0	52

Station PHASE 2 (NC 9) L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	0	48
11+00.00	3	72
11+50.00	5	48
12+00.00	6	53
12+50.00	4	67
12+60.93	0	16

Station PHASE 2 (NC 9) L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+28.50	0	0
13+50.00	0	57
14+00.00	1	85
14+50.00	4	33
15+00.00	6	30
15+50.00	11	38
16+00.00	10	25
16+23.00	2	2

Station PHASE 3 (DETOUR REMOVAL) L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+50.00	0	0
12+70.82	0	38

Station PHASE (DETOUR REMOVAL) L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+45.86	0	0
14+00.00	0	278
14+50.00	0	93