



| PAVEMENT SCHEDULE | |
|-------------------|--|
| C | PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ YD. |
| C1 | PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 165 LBS PER SQ YD. |
| D | PROP. APPROX. 2" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, TO BE APPLIED AT AN AVERAGE RATE OF 228 LBS PER SQ YD. |
| F | ASPHALT SURFACE TREATMENT, SINGLE SEAL 14m TO BE APPLIED AT AN AVERAGE RATE OF 11 LBS/SY, EMULSION RATE OF 0.20 GAL/SY |
| M | MILL ASPHALT PAVEMENT, 1½" DEPTH ENTIRE WIDTH |
| M1 | MILL ASPHALT PAVEMENT, 0" TO 1½" |
| S | SHOULDER RECONSTRUCTION (SEE DETAIL) |