Approximate quantities only. Clearing and grubbing, unclassified excavation, fine grading, borrow excavation, and removal of existing asphalt pavement will be paid for at the lump sum price for "Grading" (see Special Provision).

PROJ. REFERENCE NO.	SHEET NO.
B-5534	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt
L (LT)	(cu. yd.)	(cu. yd.)	L (LT)	(cu. yd.)	(cu. yd.)	L (LT)	(cu. yd.)	(cu. yd.)	L (LT)	(cu. yd.)	(cu. yd.)	L (LT)	(cu. yd.)	(cu. yd.)	L (LT)	(cu. yd.)	(cu. yd.)
	PHASE I			PHASE II													
15+00.00	0	0	13+78.00	0	0												
15+50.00	1	14	14+00.00	2	0												
16+00.00	1	45	14+50.00	6	4												
16+50.00	1	145	15+00.00	2	6												
17+00.00	1	314	15+50.00	0	4												
17+50.00	1	455	16+00.00	10	2												
18+00.00	0	527	16+50.00	36	1												
18+50.00	0	584	17+00.00	55	0												
19+00.00	0	656	17+50.00	191	0												
19+50.00	1	738	18+00.00	324	0												
20+00.00	2	818	18+50.00	315	0												
20+50.00	8	856	19+00.00	366	0												
21+00.00	17	898	19+50.00	446	0												
21+16.00	6	318	20+00.00	435	0												
SUBTOTAL	**39**	**6368**	20+50.00	435	0												
			21+00.00	445	0												
22+21.00	0	0	21+16.00	134	0												
22+50.00	0	680	21+34.00	143	0												
23+00.00	0	1191	**SUBTOTAL**	**3345**	**17**												
23+50.00	0	1208															
24+00.00	0	1124	22+00.00	0	0												
24+50.00	0	1016	22+21.00	200	0												
25+00.00	0	781	22+50.00	302	0												
25+50.00	0	500	23+00.00	467	0												
26+00.00	0	296	23+50.00	420	0												
26+50.00	0	118	24+00.00	391	0												
27+00.00	0	52	24+50.00	316	0												
27+25.00	5	10	25+00.00	281	16												
27+50.00	6	2	25+50.00	203	37												
28+00.00	4	18	26+00.00	41	35												
SUBTOTAL	**15**	**6996**	26+50.00	0	26												
			27+00.00	0	29												
TOTAL	**54**	**13364**	27+25.00	0	19												
			27+50.00	0	22												
			28+00.00	0	46												
			28+50.00	2	53												
			29+00.00	5	45												
			29+50.00	8	25												
			29+78.00	3	5												
			SUBTOTAL	**2639**	**358**												
			TOTAL	**5984**	**375**												