STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	B-5534	1	10

REFERENCE: B-5534

PROJECT: 55034

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE SUBSURFACE INVESTIGATION

COUNTY DUPLIN

PROJECT DESCRIPTION BRIDGE NO. 82 ON NC HIGHWAY 11/111 OVER BURNT COAT CREEK AT -L- STATION 21+68.5

CONTENTS

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTES:
1. THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
2. BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

CATLIN PERSONNEL

INVESTIGATED BY S. V. HUDSON

DRAWN BY S. V. HUDSON

CHECKED BY J. L. STONE, LG

SUBMITTED BY S. V. HUDSON, LG

DATE AUGUST 2019

CATLIN
Engineers and Scientists
Washington, NC

NORTH CAROLINA LICENSED SEAL 1583 GEOLOGIST STEVEN V HUDSON

DocuSigned by:
01DB23BB746D469...
SIGNATURE

1/2/2020
DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PROJECT REFERENCE NO.	SHEET NO.
B-5534	2

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION

SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE,
VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6

SOIL LEGEND AND AASHTO CLASSIFICATION

GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)							SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS		
GROUP CLASS.	A-1		A-3	A-2				A-4	A-5	A-6	A-7	A-1, A-2 A-3	A-4, A-5 A-6, A-7	
	A-1-a	A-1-b		A-2-4	A-2-5	A-2-6	A-2-7				A-7-5, A-7-6			
SYMBOL														
% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX	51 MN 10 MX	35 MX	35 MX	35 MX	35 MX	36 MN	36 MN	36 MN	36 MN	GRANULAR SOILS	SILT-CLAY SOILS	MUCK, PEAT
MATERIAL PASSING #40 LL PI	— 6 MX		— NP	40 MX 10 MX	41 MN 10 MX	40 MX 11 MN	41 MN 11 MN	40 MX 10 MX	41 MN 10 MX	40 MX 11 MN	41 MN 11 MN	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER		HIGHLY ORGANIC SOILS
GROUP INDEX	0		0	0		4 MX		8 MX	12 MX	16 MX	NO MX			
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND		FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND				SILTY SOILS		CLAYEY SOILS				
GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD							FAIR TO POOR				FAIR TO POOR	POOR	UNSUITABLE

PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30

CONSISTENCY OR DENSENESS

PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTENCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH ($TONS/FT^2$)
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 4 4 TO 10 10 TO 30 30 TO 50 > 50	N/A
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	< 2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 > 30	< 0.25 0.25 TO 0.5 0.5 TO 1.0 1 TO 2 2 TO 4 > 4

TEXTURE OR GRAIN SIZE

U.S. STD. SIEVE SIZE	4	10	40	60	200	270
OPENING (MM)	4.76	2.00	0.42	0.25	0.075	0.053

BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)

GRAIN SIZE	MM	305	75	2.0	0.25	0.05	0.005
	IN.	12	3				

SOIL MOISTURE - CORRELATION OF TERMS

SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION
	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE
LL — LIQUID LIMIT		
PLASTIC RANGE (PI)	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE
PL — PLASTIC LIMIT		
OM — OPTIMUM MOISTURE SL — SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE
	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE

PLASTICITY

	PLASTICITY INDEX (PI)	DRY STRENGTH
NON PLASTIC	0-5	VERY LOW
SLIGHTLY PLASTIC	6-15	SLIGHT
MODERATELY PLASTIC	16-25	MEDIUM
HIGHLY PLASTIC	26 OR MORE	HIGH

COLOR

DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.

GRADATION

WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE.
UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE.
GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.

ANGULARITY OF GRAINS

THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.

MINERALOGICAL COMPOSITION

MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.

COMPRESSIBILITY

SLIGHTLY COMPRESSIBLE	LL < 31
MODERATELY COMPRESSIBLE	LL = 31 - 50
HIGHLY COMPRESSIBLE	LL > 50

PERCENTAGE OF MATERIAL

ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE	1 - 10%
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE	10 - 20%
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME	20 - 35%
HIGHLY ORGANIC	> 10%	> 20%	HIGHLY	35% AND ABOVE

GROUND WATER

- WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING
- STATIC WATER LEVEL AFTER 24 HOURS
- PW — PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA
- SPRING OR SEEP

MISCELLANEOUS SYMBOLS

- ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION
- SOIL SYMBOL
- ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT
- INFERRED SOIL BOUNDARY
- INFERRED ROCK LINE
- ALLUVIAL SOIL BOUNDARY
- 25/025 — DIP & DIP DIRECTION OF ROCK STRUCTURES
- SPT, DPT, DMT, VST, PMT — TEST BORING
- AUGER BORING
- CORE BORING
- MW — MONITORING WELL
- PIEZOMETER INSTALLATION
- SLOPE INDICATOR INSTALLATION
- CONE PENETROMETER TEST
- SOUNDING ROD
- TEST BORING WITH CORE
- SPT N-VALUE

RECOMMENDATION SYMBOLS

- UNDERCUT
- SHALLOW UNDERCUT
- UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE
- UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK
- UNCLASSIFIED EXCAVATION - ACCEPTABLE, BUT NOT TO BE USED IN THE TOP 3 FEET OF EMBANKMENT OR BACKFILL

ABBREVIATIONS

AR - AUGER REFUSAL
BT - BORING TERMINATED
CL. - CLAY
CPT - CONE PENETRATION TEST
CSE. - COARSE
DMT - DILATOMETER TEST
DPT - DYNAMIC PENETRATION TEST
e - VOID RATIO
F - FINE
FOSS. - FOSSILIFEROUS
FRAC. - FRACTURED, FRACTURES
FRAGS. - FRAGMENTS
HI. - HIGHLY
MED. - MEDIUM
MICA. - MICACEOUS
MOD. - MODERATELY
NP - NON PLASTIC
ORG. - ORGANIC
PMT - PRESSUREMETER TEST
SAP. - SAPROLITIC
SD. - SAND, SANDY
SL. - SILT, SILTY
SLI. - SLIGHTLY
TCR - TRICONE REFUSAL
w - MOISTURE CONTENT
V - VERY
VST - VANE SHEAR TEST
WEA. - WEATHERED
γ - UNIT WEIGHT
γ_d - DRY UNIT WEIGHT

SAMPLE ABBREVIATIONS

S - BULK
SS - SPLIT SPOON
ST - SHELBY TUBE
RS - ROCK
RT - RECOMPACTED TRIAXIAL
CBR - CALIFORNIA BEARING RATIO

EQUIPMENT USED ON SUBJECT PROJECT

DRILL UNITS:
- [X] CME-45B
- [ ] CME-55
- [X] CME-550
- [ ] VANE SHEAR TEST
- [ ] PORTABLE HOIST
- [ ] _____
- [ ] _____

ADVANCING TOOLS:
- [ ] CLAY BITS
- [ ] 6" CONTINUOUS FLIGHT AUGER
- [ ] 8" HOLLOW AUGERS
- [ ] HARD FACED FINGER BITS
- [ ] TUNG.-CARBIDE INSERTS
- [X] CASING [ ] W/ ADVANCER
- [X] TRICONE 2 7/8" STEEL TEETH
- [ ] TRICONE _____" TUNG.-CARB.
- [ ] CORE BIT
- [ ] _____

HAMMER TYPE:
- [X] AUTOMATIC [ ] MANUAL

CORE SIZE:
- [ ] -B _____ [ ] -H _____
- [ ] -N _____

HAND TOOLS:
- [ ] POST HOLE DIGGER
- [X] HAND AUGER
- [ ] SOUNDING ROD
- [ ] VANE SHEAR TEST
- [ ] _____

ROCK DESCRIPTION

HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK.
ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:

WEATHERED ROCK (WR)	NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.
CRYSTALLINE ROCK (CR)	FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.
NON-CRYSTALLINE ROCK (NCR)	FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YEILD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.
COASTAL PLAIN SEDIMENTARY ROCK (CP)	COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.

WEATHERING

FRESH	ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.
VERY SLIGHT (V SLI.)	ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN, CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.
SLIGHT (SLI.)	ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.
MODERATE (MOD.)	SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.
MODERATELY SEVERE (MOD. SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. *IF TESTED, WOULD YIELD SPT REFUSAL*
SEVERE (SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. *IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF*
VERY SEVERE (V SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. *IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF*
COMPLETE	ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.

ROCK HARDNESS

VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.
HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.
MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.
MEDIUM HARD	CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PEICES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.
SOFT	CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.
VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.

FRACTURE SPACING

TERM	SPACING
VERY WIDE	MORE THAN 10 FEET
WIDE	3 TO 10 FEET
MODERATELY CLOSE	1 TO 3 FEET
CLOSE	0.16 TO 1 FOOT
VERY CLOSE	LESS THAN 0.16 FEET

BEDDING

TERM	THICKNESS
VERY THICKLY BEDDED	4 FEET
THICKLY BEDDED	1.5 - 4 FEET
THINLY BEDDED	0.16 - 1.5 FEET
VERY THINLY BEDDED	0.03 - 0.16 FEET
THICKLY LAMINATED	0.008 - 0.03 FEET
THINLY LAMINATED	< 0.008 FEET

INDURATION

FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.

FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.

TERMS AND DEFINITIONS

ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER.

AQUIFER - A WATER BEARING FORMATION OR STRATA.

ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND.

ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC.

ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE.

CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE.

COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE.

CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.

DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK.

DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL.

DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH.

FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE.

FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES.

FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL.

FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM.

FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD.

JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED.

LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT.

LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS.

MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE.

PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM.

RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK.

ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.

SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK.

SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS.

SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE.

STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS.

STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE.

STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE.

TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.

BENCH MARK: ELEVATION & LOCATIONS OBTAINED WITH RTK SURVEY GRADE GLOBAL POSITIONING SYSTEM

ELEVATION: FEET

NOTES:

FIAD = FILLED IMMEDIATELY AFTER DRILLING

U.C.P. = UNDIVIDED COASTAL PLAIN

DATE: 8-15-14

CATLIN
Engineers and Scientists
Washington, North Carolina

PROJECT REFERENCE NO.	SHEET NO.
B-5534	3

SITE PLAN

0 30 60
FEET

SKEW = 90°

-N-

20+00

23+00

WOODS

BEGIN BRIDGE
-L- Sta. 21+16.00

END BRIDGE
-L- Sta. 22+21.00

BURNT COAT CREEK

EB1 BENT LINE

B1 BENT LINE

B2 BENT LINE

EB2 BENT LINE

TO NC 903

-L-
NC II/III

L 2130

L 2225

TO NC 11

NC II/NC III 35.5' BST

BST OVER CONC
BRIDGE #82

EB1-B

B1-B

B2-B

EB2-B

EXISTING R/W

WOODS

F

W

WLB

T FO

S

T

FSS

MTL

JS

0 10 20
HORIZONTAL SCALE IN FEET
VE = 0.5

PROFILE THROUGH BORINGS PROJECTED ALONG -L-

CATLIN Engineers and Scientists
220 Old Dairy Road
Wilmington, NC 28405
Corporate Licensure No. for Engineering Services C-0585
219076

PROJECT REFERENCE NO.	SHEET
B-5534	4

EB1-B 21+16 48' RT

SS-001
PAVEMENT
FIAD
3
4
2
24
9
7
8
21
14
100/0.7
15
18
22
100/0.2
100/0.2
100/0.4
100/0.9
58
BT

SOFT, LIGHT BROWN, SANDY CLAY
MOIST TO WET. (ROADWAY EMBANKMENT)

SS-001
(A)
08/19
BT

MEDIUM DENSE, DARK GREEN,

(C)

MEDIUM DENSE,

MEDIUM HARD TO VERY HARD,

B1-B 21+40 49' RT

10' LT

FIAD
WOH
6
10
7
9
23
17
100/0.8
15
18
14
60/0.1
100/0.8
100/0.4
BT

EXISTING LAND SURFACE

WATER SURFACE ELEVATION
ON (02-06-19)

(B)

MEDIUM STIFF TO HARD, GRAY TO DARK GRAY, CLAY AND SANDY CLAY
WITH MICA AND SHELL FRAGMENTS. WET.
(PEEDEE FORMATION)

GRAY, AND GRAY BLUE, SAND AND CLAYEY SAND WITH CLAY LAYERS AND

STIFF, DARK GRAY, CLAY, SANDY CLAY, AND SILT.
GLAUCONITIC WITH MICA AND SHELL FRAGMENTS. WET.

DARK GREEN, GRAY, AND DARK GRAY, SILTY AND CLAYEY SAND WITH

GRAY, F. AND CSE. SANDY LIMESTONE WITH SHELL FRAGMENTS. WET.

B2-B 21+90 49' RT

FIAD
19
6
6
14
11
12
16
13
13
60/0.1
100/0.8
100/0.6
100/0.8
64
BT

LOOSE TO MEDIUM DENSE, BROWN, SAND
WITH TR. SILT AND CLAY. MOIST TO SAT.
(ROADWAY EMBANKMENT)

VERY SOFT, MUCK AND MODERATELY ORGANIC SILT, WET TO SAT.

(B)

SHELL FRAGMENTS. SAT.

SHELL FRAGMENTS AND INTERBEDDED
LAYERS OF SANDY CLAY. SAT.

DENSE TO VERY DENSE, GRAY, F. AND CSE. SAND WITH SHELL FRAGMENTS. SAT.

EB2-B 22+21 48' RT

7' RT

PAVEMENT
FIAD
S-001
10
7
WOH
8
34
7
7
17
11
10
60/0.1
18
18
100/0.5
100/0.6
100/0.4
100/0.6
36
BT

S-001 08/19 (ALLUVIAL)

(B)

(C)

BT

(A) VERY LOOSE, DARK BROWN TO BLACK, MUCK AND MODERATELY ORGANIC SILTY SAND, MOIST TO SAT. (ALLUVIAL)

(B) LOOSE TO MEDIUM DENSE, GRAY TO BROWN, SILTY SAND. SAT. (ALLUVIAL)

(C) HARD TO VERY HARD, GRAY, SANDY LIMESTONE.

NOTE: GROUNDLINE PROFILE ALONG -L- TAKEN FROM b5534_ls_tin_171122.tin DATED 11/22/17

NOTE: INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO PROFILE.

120 100 80 60 40 20 0 -20 -40 -60

21+00 21+20 21+40 21+60 21+80 22+00 22+20 22+40

GEOTECHNICAL BORING REPORT
BORE LOG

219076 CATLIN Engineers and Scientists 220 Old Dairy Road Wilmington, NC 28405 Corporate Licensure No. for Engineering Services C-0585

PROJECT REFERENCE NO.	SHEET
B-5534	5

WBS: 55034.1.1	**TIP:** B-5534	**COUNTY:** DUPLIN	**GEOLOGIST:** L. PUGH
SITE DESCRIPTION: BRIDGE NO. 82 ON -L- (NC 11/111) OVER BURNT COAT CREEK AT -L- STA. 21+68.5			**GROUND WTR (ft)**
BORING NO.: EB1-B	**STATION:** 21+16	**OFFSET:** 48 ft RT	**ALIGNMENT:** -L-	**0 HR.** 14.0
COLLAR ELEV.: 76.9 ft	**TOTAL DEPTH:** 84.8 ft	**NORTHING:** 477,989	**EASTING:** 2,352,402	**24 HR.** FIAD
DRILL RIG/HAMMER EFF./DATE: CAT1303 CME-550 94% 09/26/2018		**DRILL METHOD:** Mud Rotary	**HAMMER TYPE:** AUTOMATIC
DRILLER: D.T. Chalmers, Jr.	**START DATE:** 08/14/19	**COMP. DATE:** 08/14/19	**SURFACE WATER DEPTH:** N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT 0.5ft	0.5ft	0.5ft	BLOWS PER FOOT 0 25 50 75 100	SAMP. # RESULT	MOI	LOG	SOIL AND ROCK DESCRIPTION ELEV. (ft)	DEPTH (ft)
80											
										76.9	0.0
										GROUND SURFACE	
75	75.5	1.4	1	1	2	3		M		75.5 PAVEMENT	1.4
										ROADWAY EMBANKMENT LIGHT BROWN, SANDY CLAY	
	72.8	4.1	1	2	2	4		M			
70											
	68.6	8.3	1	1	1	2	SS-001 A-2-4(0)	W		68.0	8.9
										ALLUVIAL DARK BROWN, SILTY SAND WITH MOD. ORG. AND ROOTS	
65										64.9 GRAY BROWN, SILTY, F. SAND	12.0
	63.6	13.3	6	10	14	24		Sat.		60.9	16.0
60										**COASTAL PLAIN** DARK GRAY, CLAY WITH SOME F. SAND (PEEDEE FORMATION)	
	58.6	18.3	3	4	5	9		M			
55											
	53.6	23.3	2	3	4	7		M			
50											
	48.6	28.3	2	4	4	8		M		45.9 DARK GREEN, CLAYEY, F. SAND WITH INTERBEDDED LAYERS OF SANDY CLAY	31.0
45											
	43.6	33.3	5	10	11	21		Sat.		40.9 DARK GRAY, SANDY CLAY, GLAUCONITIC WITH SHELL FRAGS. AT BASE OF STRATUM	36.0
40											
	38.6	38.3	4	6	8	14		W			
35											
	33.6	43.3	3	4	96/0.2	100/0.7		W		32.6	44.3
										LIMESTONE (NO RECOVERY; INFERRED FROM CUTTINGS)	
30										30.9 DARK GRAY GREEN, CLAYEY, F. SAND WITH INTERBEDDED LAYERS OF CLAY AT BASE OF STRATUM	46.0
	28.6	48.3	4	6	9	15		Sat.			
25											
	23.6	53.3	5	8	10	18		Sat.			
20											
	18.6	58.3	6	9	13	22		Sat.			
15											
	13.6	63.3	100/0.2			100/0.2		Sat.		14.6 GRAY, SANDY LIMESTONE	62.3
10											
	8.6	68.3	63	100/0.2		100/0.2		Sat.			
5											
	3.6	73.3	80	100/0.4		100/0.4		Sat.			
0											

NCDOT BORE DOUBLE B5534 GEO BRDG BURNTCREEK CATLIN.GPJ NCDOT_CATLIN.GDT 09/11/19

WBS: 55034.1.1	**TIP:** B-5534	**COUNTY:** DUPLIN	**GEOLOGIST:** L. PUGH
SITE DESCRIPTION: BRIDGE NO. 82 ON -L- (NC 11/111) OVER BURNT COAT CREEK AT -L- STA. 21+68.5			**GROUND WTR (ft)**
BORING NO.: EB1-B	**STATION:** 21+16	**OFFSET:** 48 ft RT	**ALIGNMENT:** -L-	**0 HR.** 14.0
COLLAR ELEV.: 76.9 ft	**TOTAL DEPTH:** 84.8 ft	**NORTHING:** 477,989	**EASTING:** 2,352,402	**24 HR.** FIAD
DRILL RIG/HAMMER EFF./DATE: CAT1303 CME-550 94% 09/26/2018		**DRILL METHOD:** Mud Rotary	**HAMMER TYPE:** AUTOMATIC
DRILLER: D.T. Chalmers, Jr.	**START DATE:** 08/14/19	**COMP. DATE:** 08/14/19	**SURFACE WATER DEPTH:** N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT 0.5ft	0.5ft	0.5ft	BLOWS PER FOOT 0 25 50 75 100	SAMP. # RESULT	MOI	LOG	SOIL AND ROCK DESCRIPTION
0						Match Line				
	-1.4	78.3	32	53	47/0.4	100/0.9		Sat.		GRAY, SANDY LIMESTONE *(continued)*
-5										-5.1 82.0
	-6.4	83.3	15	25	33	58		Sat.		GRAY, F. AND CSE. SAND WITH SHELL FRAGS.
										-7.9 84.8
										BORING TERMINATED AT ELEVATION -7.9 ft IN VERY DENSE F. AND CSE. SAND (PEEDEE FORMATION)

GEOTECHNICAL BORING REPORT
BORE LOG

CATLIN Engineers and Scientists
220 Old Dairy Road
Wilmington, NC 28405
Corporate Licensure No. for Engineering Services C-0585
219076

PROJECT REFERENCE NO.	SHEET
B-5534	6

WBS: 55034.1.1	**TIP:** B-5534	**COUNTY:** DUPLIN	**GEOLOGIST:** C. FUTRAL	
SITE DESCRIPTION: BRIDGE NO. 82 ON -L- (NC 11/111) OVER BURNT COAT CREEK AT -L- STA. 21+68.5				**GROUND WTR (ft)**
BORING NO.: B1-B	**STATION:** 21+40	**OFFSET:** 49 ft RT	**ALIGNMENT:** -L-	**0 HR.** N/A
COLLAR ELEV.: 67.1 ft	**TOTAL DEPTH:** 64.5 ft	**NORTHING:** 477,987	**EASTING:** 2,352,426	**24 HR.** FIAD
DRILL RIG/HAMMER EFF./DATE: CAT1314 CME-45B 94% 09/26/2018		**DRILL METHOD:** Mud Rotary	**HAMMER TYPE:** AUTOMATIC	
DRILLER: S. BOWMAN	**START DATE:** 08/19/19	**COMP. DATE:** 08/20/19	**SURFACE WATER DEPTH:** N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT 0.5ft	0.5ft	0.5ft	BLOWS PER FOOT 0 25 50 75 100	SAMP. #	RESULT	MOI	LOG	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)
70													
	67.1	0.0	WOH	WOH	WOH	0			Sat.		GROUND SURFACE	67.1	0.0
65											**ALLUVIAL** DARK GRAY TO BLACK, MUCK	64.6	2.5
	62.6	4.5	2	2	4	6			W		GRAY, F. SAND WITH TR. WOOD FRAGS.	59.6	7.5
60	58.0	9.1	3	5	5	10			W		**COASTAL PLAIN** GRAY TO DARK GRAY, SANDY CLAY WITH MICA. (PEEDEE FORMATION)		
55	53.0	14.1	2	3	4	7			W				
50	48.0	19.1	2	4	5	9			W			45.1	22.0
45	43.0	24.1	5	9	14	23			Sat.		DARK GRAYISH BLUE, F. SAND WITH MICA AND SHELL FRAGS.	39.6	27.5
40	38.0	29.1	5	8	9	17			W		DARK GRAY, SANDY CLAY WITH MICA.		
35	33.0	34.1	3	97/0.3		100/0.8			W			32.5	34.6
30	28.0	39.1	5	6	9	15			Sat.		SANDY WEATHERED LIMESTONE GRAY TO DARK GRAY, SILTY, F. SAND WITH TR. SHELL FRAGS.	32.1	35.0
25	23.0	44.1	5	7	11	18			Sat.				
20	18.0	49.1	5	6	8	14			Sat.				
15	13.0	54.1	60/0.1			60/0.1			Sat.		GRAY, LIMESTONE WITH LAYERS OF F. SAND	15.1	52.0
10	8.0	59.1	48	52/0.3		100/0.8			Sat.				
5	3.0	64.1	100/0.4			100/0.4			Sat.		BORING TERMINATED AT ELEVATION 2.6 ft IN HARD LIMESTONE (PEEDEE FORMATION)	2.6	64.5

WBS: 55034.1.1	**TIP:** B-5534	**COUNTY:** DUPLIN	**GEOLOGIST:** C. FUTRAL	
SITE DESCRIPTION: BRIDGE NO. 82 ON -L- (NC 11/111) OVER BURNT COAT CREEK AT -L- STA. 21+68.5				**GROUND WTR (ft)**
BORING NO.: B2-B	**STATION:** 21+90	**OFFSET:** 49 ft RT	**ALIGNMENT:** -L-	**0 HR.** N/A
COLLAR ELEV.: 61.9 ft	**TOTAL DEPTH:** 69.7 ft	**NORTHING:** 477,986	**EASTING:** 2,352,476	**24 HR.** FIAD
DRILL RIG/HAMMER EFF./DATE: CAT1303 CME-550 94% 09/26/2018		**DRILL METHOD:** Mud Rotary	**HAMMER TYPE:** AUTOMATIC	
DRILLER: S. BOWMAN	**START DATE:** 08/22/19	**COMP. DATE:** 08/22/19	**SURFACE WATER DEPTH:** 4.0ft	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT 0.5ft	0.5ft	0.5ft	BLOWS PER FOOT 0 25 50 75 100	SAMP. #	RESULT	MOI	LOG	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)
65													
	61.9	0.0	WOH	5	14	19			W		GROUND SURFACE	61.9	0.0
60											**COASTAL PLAIN** DARK GRAY, SILTY AND SANDY CLAY WITH MICA (PEEDEE FORMATION)		
55	53.7	8.2	2	3	3	6			W				
50	48.7	13.2	2	3	3	6			W		DARK GRAY, SANDY CLAY WITH MICA AND SHELL FRAGS.	50.9	11.0
45	43.7	18.2	3	6	8	14			Sat.		DARK GRAY, CLAYEY, F. SAND WITH TR. SHELL FRAGS.	45.4	16.5
40	38.7	23.2	3	5	6	11			M		DARK GRAY, CLAY WITH MICA	40.4	21.5
35	33.7	28.2	3	5	7	12			W		DARK GRAY, SILT WITH SHELL FRAGS.	35.9	26.0
30	28.7	33.2	5	6	10	16			W		DARK GRAY, SILTY, F. SAND	30.4	31.5
25	23.7	38.2	3	5	8	13			W				
20	18.7	43.2	4	4	9	13			W		GRAY, SAND WITH SANDY CLAY LAYERS AND SHELL FRAGS.	20.4	41.5
15	13.7	48.2	60/0.1			60/0.1					LIMESTONE (NO RETURN: INFERRED FROM CUTTINGS)	15.4	46.5
10	8.7	53.2	57	43/0.3		100/0.8					GRAY AND LIGHT GRAY, SANDY LIMESTONE	10.4	51.5
5	3.7	58.2	80	20/0.1		100/0.6							
0	-1.3	63.2	52	48/0.3		100/0.8							
-5	-6.3	68.2	19	29	35	64					GRAY TO LIGHT GRAY, F. SAND TO F. AND CSE. SAND WITH SHELL FRAGS.	-4.6	66.5
											BORING TERMINATED AT ELEVATION -7.8 ft IN VERY DENSE F. SAND (PEEDEE FORMATION)	-7.8	69.7

NCDOT BORE DOUBLE B5534_GEO_BRDG_BURNTCREEK_CATLIN.GPJ NCDOT_CATLIN.GDT 09/11/19

GEOTECHNICAL BORING REPORT
BORE LOG

CATLIN Engineers and Scientists
220 Old Dairy Road
Wilmington, NC 28405
Corporate Licensure No. for Engineering Services C-0585
219076

PROJECT REFERENCE NO.	SHEET
B-5534	7

WBS: 55034.1.1	**TIP:** B-5534	**COUNTY:** DUPLIN	**GEOLOGIST:** L. PUGH
SITE DESCRIPTION: BRIDGE NO. 82 ON -L- (NC 11/111) OVER BURNT COAT CREEK AT -L- STA. 21+68.5			**GROUND WTR (ft)**
BORING NO.: EB2-B	**STATION:** 22+21	**OFFSET:** 48 ft RT	**ALIGNMENT:** -L-	**0 HR.** 10.2
COLLAR ELEV.: 76.9 ft	**TOTAL DEPTH:** 84.5 ft	**NORTHING:** 477,986	**EASTING:** 2,352,507	**24 HR.** FIAD
DRILL RIG/HAMMER EFF./DATE: CAT1303 CME-550 94% 09/26/2018		**DRILL METHOD:** Mud Rotary	**HAMMER TYPE:** AUTOMATIC
DRILLER: D.T. Chalmers, Jr.	**START DATE:** 08/13/19	**COMP. DATE:** 08/13/19	**SURFACE WATER DEPTH:** N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT 0.5ft	0.5ft	0.5ft	BLOWS PER FOOT 0 25 50 75 100	SAMP. #	RESULT	MOI	LOG	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)
80													
											GROUND SURFACE	76.9	0.0
75	75.6	1.3	5	6	4	10			M		PAVEMENT	75.6	1.3
	72.8	4.1									**ROADWAY EMBANKMENT** BROWN, F. SAND WITH TR. SILT AND CLAY AND CLAYEY, F. SAND		
70			1	2	5	7			M			69.9	7.0
	68.9	8.0	WOH	WOH	WOH				Sat.		**ALLUVIAL** DARK BROWN, MOD. ORG. SILT	67.7	9.2
65	63.9	13.0	1	4	4	0					GRAY BROWN, SILTY, F. SAND	64.9	12.0
60	58.9	18.0				8			Sat.		**COASTAL PLAIN** DARK GRAY, SANDY CLAY (PEEDEE FORMATION)	60.9	16.0
55	53.9	23.0	13	18	16	34			M				
50	48.9	28.0	3	3	4	7			M				
45	43.9	33.0	3	3	4	7			M				
40	38.9	38.0	3	6	11	17			M		DARK GREEN, F. SAND WITH SILT	43.1	33.8
35	33.9	43.0	3	4	7	11			M		DARK GRAY, CLAY WITH TR. SAND. GLAUCONITIC. GRADING TO GRAY, SANDY CLAY WITH SHELL FRAGS.	39.9	37.0
30	28.9	48.0	3	4	6	10			W			35.9	41.0
25	23.9	53.0	60/0.1			60/0.1			W		LIMESTONE (NO RECOVERY: INFERRED FROM CUTTINGS) DARK GREEN, CLAYEY, F. SAND WITH INTERBEDDED LAYERS OF SANDY CLAY AT BASE OF STRATUM	29.4 28.4	47.5 48.5
20	18.9	58.0	5	6	12	18			Sat.				
15	13.9	63.0	5	7	11	18			Sat.				
10	8.9	68.0	100/0.5			100/0.5			Sat.		LIGHT GRAY, SANDY LIMESTONE	15.9	61.0
5	3.9	73.0	46	75	25/0.1	100/0.6			Sat.				
0			67	100/0.4		100/0.4			Sat.				

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT 0.5ft	0.5ft	0.5ft	BLOWS PER FOOT 0 25 50 75 100	SAMP. #	RESULT	MOI	LOG	SOIL AND ROCK DESCRIPTION
0						Match Line					
	-1.1	78.0	70	95	5/0.1	100/0.6			Sat.		LIGHT GRAY, SANDY LIMESTONE *(continued)*
-5											-4.1 81.0 LIGHT GRAY, F. AND CSE. SAND
	-6.1	83.0	19	17	19	36			Sat.		-7.6 84.5 BORING TERMINATED AT ELEVATION -7.6 ft IN DENSE F. AND CSE. SAND (PEEDEE FORMATION)

NCDOT BORE DOUBLE B5534 GEO_BRDG_BURNTCREEK_CATLIN.GPJ NCDOT_CATLIN.GDT 09/11/19

GEOTECHNICAL BORING REPORT
BORE LOG

219076 CATLIN Engineers and Scientists 220 Old Dairy Road Wilmington, NC 28405 Corporate Licensure No. for Engineering Services C-0585

PROJECT REFERENCE NO.	SHEET
B-5534	8

WBS: 55034.1.1	**TIP:** B-5534	**COUNTY:** DUPLIN	**GEOLOGIST:** L. PUGH	
SITE DESCRIPTION: BRIDGE NO. 82 ON -L- (NC 11/111) OVER BURNT COAT CREEK AT -L- STA. 21+68.5				**GROUND WTR (ft)**
BORING NO.: L-2130	**STATION:** 21+30	**OFFSET:** 10 ft LT	**ALIGNMENT:** -L-	**0 HR.** N/A
COLLAR ELEV.: 68.3 ft	**TOTAL DEPTH:** 6.0 ft	**NORTHING:** 478,047	**EASTING:** 2,352,418	**24 HR.** 0.3
DRILL RIG/HAMMER EFF./DATE: Hand Auger		**DRILL METHOD:** Hand Auger	**HAMMER TYPE:** N/A	
DRILLER: N/A	**START DATE:** 08/15/19	**COMP. DATE:** 08/15/19	**SURFACE WATER DEPTH:** N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT 0.5ft	0.5ft	0.5ft	BLOWS PER FOOT 0 25 50 75 100	SAMP. # RESULT	MOI	LOG	SOIL AND ROCK DESCRIPTION ELEV. (ft)	DEPTH (ft)
70											
										68.3 GROUND SURFACE	0.0
										ALLUVIAL DARK BROWN, MODERATELY ORGANIC SILTY SAND	
65										64.3	4.0
										GRAY BROWN, SILTY SAND	
										62.3	6.0
										BORING TERMINATED AT ELEVATION 62.3 ft IN VERY LOOSE SILTY SAND. (ALLUVIAL)	

WBS: 55034.1.1	**TIP:** B-5534	**COUNTY:** DUPLIN	**GEOLOGIST:** L. PUGH	
SITE DESCRIPTION: BRIDGE NO. 82 ON -L- (NC 11/111) OVER BURNT COAT CREEK AT -L- STA. 21+68.5				**GROUND WTR (ft)**
BORING NO.: L-2225	**STATION:** 22+25	**OFFSET:** 7 ft RT	**ALIGNMENT:** -L-	**0 HR.** N/A
COLLAR ELEV.: 68.2 ft	**TOTAL DEPTH:** 6.0 ft	**NORTHING:** 478,026	**EASTING:** 2,352,512	**24 HR.** 0.4
DRILL RIG/HAMMER EFF./DATE: Hand Auger		**DRILL METHOD:** Hand Auger	**HAMMER TYPE:** N/A	
DRILLER: N/A	**START DATE:** 08/15/19	**COMP. DATE:** 08/15/19	**SURFACE WATER DEPTH:** N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT 0.5ft	0.5ft	0.5ft	BLOWS PER FOOT 0 25 50 75 100	SAMP. # RESULT	MOI	LOG	SOIL AND ROCK DESCRIPTION
70										
										68.2 GROUND SURFACE 0.0
							S-001 A-4(0)			**ALLUVIAL** MUCK. HIGHLY ORGANIC (30.9%) SILT
65										64.7 3.5
										GRAY BROWN, SILTY SAND
										62.2 6.0
										BORING TERMINATED AT ELEVATION 62.2 ft IN VERY LOOSE SILTY SAND. (ALLUVIAL)

CATLIN Engineers and Scientists 219074 220 Old Dairy Road Wilmington, NC 28405 Corporate Licensure No. for Engineering Services C-0585	PROJECT REFERENCE NO.	SHEET
	B-5534	9

LABORATORY SUMMARY SHEET

AASHTO Standard Specifications

(As modified by NCDOT, Material and Tests Unit, 2000.)

TEST RESULTS															
Proj. Sample Number	**SS-001**	**S-001**													
Lab Sample Number	SS-001	S-001													
Retained #4 Sieve %	1.1	10.1													
Passing #10 Sieve %	98.6	89.2													
Passing #40 Sieve %	96	91													
Passing #200 Sieve %	32	78													
MINUS NUMBER 10 FRACTION															
SOIL MORTAR - 100%															
Coarse Sand Ret.-#60 %	9.0	12.3													
Fine Sand Ret.-#270 %	63.4	11.3													
Silt 0.05 - 0.005mm %	13.6	55.7													
Clay <0.005mm %	14.1	20.7													
Liquid Limit (LL)	NP	NP													
Plasticity Index (PI)	NP	NP													
AASHTO Classification /Group Index	**A-2-4(0)**	**A-4(0)**													
Organic Content %	**9.4**	**30.9**													
Station	21+16	22+25													
Offset	48ft RT	7ft RT													
Alignment	-L-	-L-													
Boring Identification	**EB1-B**	**L-2225**													
Depth (FT)	8.9	0.0													
to	9.8	3.5													
Field Moist. Content %															
Tested By	MDM	MDM													
Submitted By	LGP	LGP													
Date Submitted	08/16/19	08/16/19													

NP = Non-Plastic

NEM = Not Enough Material for Analysis

N/A = Not Applicable / Not Analyzed

Michael D. Mason
Laboratory Manager

Report Date: 8/26/2019

BRIDGE NO. 82 ON NC 11/111 OVER BURNT COAT CREEK

219074 CATLIN Engineers and Scientists
220 Old Dairy Road
Wilmington, NC 28405
Corporate Licensure No. for Engineering Services C-0585

PROJECT REFERENCE NO.	SHEET
B-5534	10



BURNT COAT CREEK FACING SOUTH
(DOWNSTREAM)

NOTES: SITE PHOTOS OBTAINED FROM BRIDGE SCOUR REPORT
300082_2019_B-5534_BURNT_COAT_CREEK_NC_111.pdf
PROVIDED BY NCDOT