

4/7/2020 4:10:47 PM G:\Projects\2018\Division 3 (SEA)\B-5639 (Duplin 36 NC11 over Maxwell Creek)\Structures\Drawings\Final\B5639_SMJ_LRFR_300036.dgn

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE										SERVICE III LIMIT STATE					COMMENT NUMBER			
						MOMENT					SHEAR					MOMENT								
						LIVELOAD FACTORS	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (FT)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (FT)	LIVELOAD FACTORS	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN		GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (FT)	
DESIGN LOAD RATING	HL-93(Inv)	N/A	1	1.974	--	1.75	0.278	2.49	55'	EL	27	0.526	1.97	55'	EL	5.4	0.80	0.278	2.27	55'	EL	27		
	HL-93(Opr)	N/A	--	2.559	--	1.35	0.278	3.23	55'	EL	27	0.526	2.56	55'	EL	5.4	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	2	2.358	84.885	1.75	0.278	3.12	55'	EL	27	0.526	2.36	55'	EL	5.4	0.80	0.278	2.84	55'	EL	27		
	HS-20(Opr)	36.000	--	3.057	110.036	1.35	0.278	4.04	55'	EL	27	0.526	3.06	55'	EL	5.4	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	5.965	80.53	1.4	0.278	8.19	55'	EL	27	0.526	6.71	55'	EL	5.4	0.80	0.278	5.97	55'	EL	27	
		SNGARBS2	20.000	--	4.621	92.422	1.4	0.278	6.36	55'	EL	27	0.526	4.86	55'	EL	5.4	0.80	0.278	4.62	55'	EL	27	
		SNAGRIS2	22.000	--	4.434	97.548	1.4	0.278	6.12	55'	EL	21.6	0.526	4.55	55'	EL	5.4	0.80	0.278	4.43	55'	EL	27	
		SNCOTTS3	27.250	--	2.974	81.029	1.4	0.278	4.08	55'	EL	27	0.526	3.36	55'	EL	5.4	0.80	0.278	2.97	55'	EL	27	
		SNAGGRS4	34.925	--	2.555	89.234	1.4	0.278	3.51	55'	EL	27	0.526	2.85	55'	EL	5.4	0.80	0.278	2.56	55'	EL	27	
		SNS5A	35.550	--	2.494	88.65	1.4	0.278	3.42	55'	EL	27	0.526	2.93	55'	EL	5.4	0.80	0.278	2.49	55'	EL	27	
		SNS6A	39.950	--	2.318	92.619	1.4	0.278	3.18	55'	EL	27	0.526	2.7	55'	EL	5.4	0.80	0.278	2.32	55'	EL	27	
	TTST	TNAGRIT3	33.000	--	2.836	93.596	1.4	0.278	3.89	55'	EL	27	0.526	3.19	55'	EL	5.4	0.80	0.278	2.84	55'	EL	27	
		TNT4A	33.075	--	2.857	94.504	1.4	0.278	3.92	55'	EL	27	0.526	3.08	55'	EL	5.4	0.80	0.278	2.86	55'	EL	27	
		TNT6A	41.600	--	2.366	98.442	1.4	0.278	3.25	55'	EL	27	0.526	2.94	55'	EL	5.4	0.80	0.278	2.37	55'	EL	27	
		TNT7A	42.000	--	2.395	100.575	1.4	0.278	3.29	55'	EL	27	0.526	2.76	55'	EL	5.4	0.80	0.278	2.39	55'	EL	27	
		TNT7B	42.000	--	2.499	104.94	1.4	0.278	3.43	55'	EL	27	0.526	2.6	55'	EL	5.4	0.80	0.278	2.50	55'	EL	27	
		TNAGRIT4	43.000	--	2.365	101.706	1.4	0.278	3.25	55'	EL	27	0.526	2.51	55'	EL	5.4	0.80	0.278	2.37	55'	EL	27	
		TNAGT5A	45.000	--	2.216	99.716	1.4	0.278	3.04	55'	EL	27	0.526	2.53	55'	EL	5.4	0.80	0.278	2.22	55'	EL	27	
TNAGT5B	45.000	3	2.177	97.95	1.4	0.278	2.99	55'	EL	27	0.526	2.38	55'	EL	5.4	0.80	0.278	2.18	55'	EL	27			

LOAD FACTORS:

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ _{DC}	γ _{DW}
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.
 ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.
 DISTANCE FROM LEFT END OF SPAN IS MEASURED FROM C BEARING.

CONTROLLING LOAD RATING

① DESIGN LOAD RATING (HL-93)


② DESIGN LOAD RATING (HS-20)

③ LEGAL LOAD RATING ***

*** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION


I - INTERIOR GIRDER
 EL - EXTERIOR LEFT GIRDER
 ER - EXTERIOR RIGHT GIRDER



PROJECT NO. B-5639
DUPLIN COUNTY
 STATION: 23+55.00 -L-

DRAWN BY: T. BANKOVICH DATE: 2-20
 CHECKED BY: J.A. BATTS DATE: 2-20
 DESIGN ENGINEER OF RECORD: J.A. BATTS DATE: 2-20

PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**LRFR SUMMARY FOR
 55' CORED SLAB UNITS
 90° SKEW
 (NON-INTERSTATE TRAFFIC)**

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-5
1			3			TOTAL SHEETS
2			4			25

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**