

PROJ. REFERENCE NO. B-5662	SHEET NO. PMP-1
APPROVED: _____	
DATE: _____	
SEAL	
	
4/22/2020	
	
<small>Engineers • Planners • Scientists • Construction Managers 4601 Six Forks Road, Landmark Center II, Suite 210 Raleigh, NC 27609-5210 Phone (919) 783-9214 • Fax (919) 783-9266</small>	

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PAVEMENT MARKING PLAN

HALIFAX COUNTY

LOCATION: BRIDGE NO. 93 OVER CONOCONNARA SWAMP ON NC 561

TIP PROJECT: B-5662

CONTRACT: C204489

PAVEMENT MARKING SCHEDULE

<u>SYMBOL DESCRIPTION</u>	<u>FINAL PAVEMENT MARKINGS</u>
T1 WHITE EDGELINE	THERMOPLASTIC (4", 90 MILS)
T12 YELLOW 10 FT. SKIP	THERMOPLASTIC (4", 90 MILS)
T11 YELLOW SINGLE CENTER	THERMOPLASTIC (4", 90 MILS)
T13 YELLOW DOUBLE CENTER	THERMOPLASTIC (4", 90 MILS)
C13 YELLOW DOUBLE CENTER	COLD APPLIED (4", TYPE 2)
C1 WHITE EDGELINE	COLD APPLIED (4", TYPE 2)

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

<u>STD. NO.</u>	<u>TITLE</u>
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - PERMANENT AND TEMPORARY
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
-L- NC 561	THERMOPLASTIC	NONE
-BRIDGE-	COLD APPLIED (TYPE 2)	NONE

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.


D) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.







E) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS ON CONCRETE BRIDGE DECKS PRIOR TO PLACING COLD APPLIED (TYPE 2) PAVEMENT MARKING MATERIAL.

F) TYPE III COLD APPLIED PLASTIC MAY BE USED IN LIEU OF TYPE II COLD APPLIED PLASTIC. IF TYPE III COLD APPLIED PLASTIC IS USED, IT SHALL BE PAID FOR USING THE TYPE II COLD APPLIED PLASTIC PAY ITEM.

INDEX

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
PMP-1	PAVEMENT MARKING PLAN TITLE AND SCHEDULE SHEET
PMP-2	PAVEMENT MARKING DETAIL



PAVEMENT MARKING LEGEND	
	WHITE EDGELINE, THERMOPLASTIC (4", 90 MILS)
	YELLOW 10 FT. SKIP, THERMOPLASTIC (4", 90 MILS)
	YELLOW SINGLE CENTER, PAINT (4")
	YELLOW DOUBLE CENTER, PAINT (4")
	WHITE EDGELINE, COLD APPLIED (4", TYPE 2)
	YELLOW DOUBLE CENTER, COLD APPLIED (4", TYPE 2)

PAVEMENT MARKING DETAIL

22-APR-2020 14:45:21 B-5662\TrafficControl\TC\B5662.PMP_02.dgn
RUBEN