

PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.14.11.10451	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1245000000-E	1297000000-E			1503000000-E	1523000000-E	1575000000-E	1577000000-E	1662000000-E	1840000000-E	8867000000-E			
												SHOULDER RECONSTRUCTION	4" MILLING	2" MILLING	1½" MILLING	INTERMEDIATE COURSE, I19.0C	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	ASPHALT PLUG JOINT REPAIR/REPLACEMENT (18"-24" WIDE, W/PLATE)			
												MI	SY	SY	SY	TONS	TONS	TONS	TONS	TON	LF	LF			
2021CPT.14.11.10451	Henderson	1	US 25 NORTH	FROM .003 MILES NORTH OF BRIDGE #114 TO SC	1	2	MD	YES	NO	5.81	34	5.25	6,000	115,890		875	11,378	725	258	4,229	61,354	250			
TOTAL FOR MAP NO. 1											5.81	6,000	115,890		875	11,378	725	258	4,229	61,354	250				
2021CPT.14.11.10451	Henderson	2	US 25 SOUTH	FROM SC LINE TO BRIDGE #111	1	2	MD	YES	NO	5.765	34	3.38	6,000	114,993		875	10,664	682	256	4,196	60,878				
TOTAL FOR MAP NO. 2											5.765	6,000	114,993		875	10,664	682	256	4,196	60,878					
2021CPT.14.11.10451	Henderson	3	EXIT 1 RAMP	FROM NORTH TO US 225	2	1		NO	NO	0.25	26			3,813		354	21								
TOTAL FOR MAP NO. 3											0.25				3,813		354	21							
2021CPT.14.11.10451	Henderson	4	EXIT 1 RAMP	FROM US 225 TO US 25 NORTH	2	1		NO	NO	0.15	26					204	12								
TOTAL FOR MAP NO. 4											0.15				2,200		204	12							
2021CPT.14.11.10451	Henderson	5	EXIT 1 RAMP	FROM US 25 SOUTH TO SR 1104 /US 225	2	1		NO	NO	0.25	26			3,813		354	21								
TOTAL FOR MAP NO. 5											0.25				3,813		354	21							
2021CPT.14.11.10451	Henderson	6	EXIT 1 RAMP	ENTRANCE FROM SR-1104/US 225 TO US 25 SOUTH	2	1		NO	NO	0.3	26			4,576		425	25								
TOTAL FOR MAP NO. 6											0.3				4,576		425	25							
2021CPT.14.11.10451	Henderson	7	EXIT 3 RAMP	FROM US 25 NORTH TO SR-1106	2	1		NO	NO	0.25	26			3,813		354	21								
TOTAL FOR MAP NO. 7											0.25				3,813		354	21							
2021CPT.14.11.10451	Henderson	8	EXIT 3 RAMP	FROM SR-1106 TO US 25 NORTH	2	1		NO	NO	0.25	26			3,813		354	21								
TOTAL FOR MAP NO. 8											0.25				3,813		354	21							
2021CPT.14.11.10451	Henderson	9	EXIT 3 RAMP	FROM US 25 SOUTH TO SR-1106	2	1		NO	NO	0.3	26			4,576		425	25								
TOTAL FOR MAP NO. 9											0.3				4,576		425	25							
2021CPT.14.11.10451	Henderson	10	EXIT 3 RAMP	FROM SR-1106 TO US 25 SOUTH	2	1		NO	NO	0.25	26			3,813		354	21								
TOTAL FOR MAP NO. 10											0.25				3,813		354	21							
2021CPT.14.11.10451	Henderson	11	EXIT 5 RAMP	FROM US 25 NORTH TO .01 MILES SOUTH US 225	2	1		NO	NO	0.095	26			1,449		135	8								
TOTAL FOR MAP NO. 11											0.095				1,449		135	8							
2021CPT.14.11.10451	Henderson	12	EXIT 5 RAMP	FROM .02 MILES SOUTH OF US 25 TO US 25 NORTH	2	1		NO	NO	0.2	26			3,051		283	17								
TOTAL FOR MAP NO. 12											0.2				3,051		283	17							
2021CPT.14.11.10451	Henderson	13	EXIT 5 RAMP	FROM US 25 TO US 225	2	1		NO	NO	0.25	26			3,813		354	21								
TOTAL FOR MAP NO. 13											0.25				3,813		354	21							
2021CPT.14.11.10451	Henderson	14	EXIT 5 RAMP	FROM US 225 TO US 25 SOUTH	2	1		NO	NO	0.25	26			3,813		354	21								
TOTAL FOR MAP NO. 14											0.25				3,813		354	21							
TOTAL FOR PROJ NO. 2021CPT.14.11.10451											14.37				8.63	12,000	230,883	42,543	1,750	25,992	1,641	514	8,425	122,232	250
GRAND TOTAL											14.37				8.63	12,000	230,883	42,543	1,750	25,992	1,641	514	8,425	122,232	250