

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LAN ES	FINAL SURFACE TEST. REQ'D	WARM MIX ASPHALT REQUIRED	LENGTH		SHOULDER RECONSTRUCTION	ASB	0" TO 1.5" MILLING	INC. MILLING	S9.5B	S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXI. PAV'T	BLOT-TING SAND	2'-6" CURB & GUT-TER	4" CONC SIDE-WALK	RETRO-FIT EXI. CURB RAMP	CONC CURB RAMP	REM & REPL CURB RAMPS	ADJ. OF MAN-HOLES	ADJ. OF METER OR VALVE BOX	PORT-ABLE LIGHT-ING	TEMP. SILT FENCE	SEED & MULCH-ING	RE-SPONSE FOR EC	LEAD-IN CABLE (14-2 PAIR)				
									MI	FT																						SMI	TON	SY	SY
2021CPT.08.07.20761	Randolph	1	SR1526 EDGAR RD.	(FROM: SR1525 BEESON FARM RD. TO: SR1527 MARLBORO CHURCH RD. )	1	2	NO	NO	1.76	20	3.52	500		390	1,874		126	220																	
		2	SR1911 ASH-LAND ST.	(FROM: PVMT JOINT NEAR SR 1009 MAIN ST. TO: GUILFORD CO. LINE.	1,2	2	NO	NO	0.87	20	1.74	244	265		1,953		131	257	20																
		3	SR 1955 S. STOUT ST.	(FROM: SR 1009 HIGHWAY 311 EXT. TO: SR 1950 W. ACADEMY ST.)	2,3	2	NO	NO	1.337	20	2.67	374	176		1,820	1,574	94	530																	
		4	SR1938 HOCK-ETT DAIRY RD.	(FROM: SR2039 RIVER MILL RD TO: SR1007 RANDLEMAN RD.)	1	2	NO	NO	1.88	20	3.76	528			1,040	2,163		145	100																
		5	SR1009 US HIGH-WAY 311	(FROM: 10' S OF JOINT BELOW SR1747 LILLY FLOWER RD. TO: SR3182 COMANCHE DR.)	2,3	2	NO	NO	2.447	40-60	0.23	35	10,972	2,860		7,899		474	400		50	250	23	1	14	12	2	*	50	0.25	2	600			
		6	SR1944 BRAN-SON DAVIS RD.	(FROM: BRIDGE 526 I-74 NORTH JOINT TO:SR1926 DAVIS COUNTRY RD.)	1	2	NO	NO	3.08	22	6.16	865			3,560	3,872		260	700																
		7	SR1004 FLINT HILL RD.	(FROM:SR1525 BEESON FARM RD. TO:SR1539 EARNHARDT RD.)	1	2	NO	NO	1.7	22	3.40	812.6			780	2,111		142	250																
		8	SR1547 FULLER MILL RD N.	(FROM: DAVIDSON COUNTY TO: SR1547 FINCH FARM RD.)	1	2	NO	NO	3.61	21	7.22	1,014			2,600	4,436		297	1,500																
		9	SR1577 ARCH-DALE RD.	(FROM:GUILFORD COUNTY LINE TO:SR1603 SCHOOL RD.)	1,2	2	NO	NO	1.3	26	3.02	424	500		2,484	2,944		197	378								5	2							
		10	SR1504 W. CEN-TRAL AVE.	(FROM:SR1502 W. BALFOUR AVE.TO:BUS 220 N. FAYETTEVILLE ST.)	1,2	2	NO	NO	0.93	29.5	1.75	245	700		2,210	1,588		106	100								4								300
<b>GRAND TOTAL FOR PROJ NO. 2021CPT.08.07.20761</b>									<b>18.914</b>		<b>33.47</b>	<b>5,041.6</b>	<b>12,613</b>	<b>17,744</b>	<b>20,941</b>	<b>9,473</b>	<b>1,972</b>	<b>4,435</b>	<b>20</b>	<b>50</b>	<b>250</b>	<b>23</b>	<b>1</b>	<b>14</b>	<b>21</b>	<b>5</b>	<b>1</b>	<b>50</b>	<b>0.25</b>	<b>2</b>	<b>900</b>				