

- INSTALL ETHERNET EDGE SWITCH
- INSTALL WIRELESS EQUIPMENT
- INSTALL 8.5 DB GAIN YAGI ANTENNA VERTICALLY POLARIZED, SEE NOTE 1
- ATTACH ANTENNA 24" BELOW TOP OF SIGNAL POLE
- AIM TOWARDS 07-2098



NOTES:

1. REMOVE THE EXISTING RADIO ANTENNA AND CABLES FOR SIGNAL 07-2146, AND INSTALL THE NEW ANTENNA AND ROUTE THE NEW COAXIAL CABLE TO THE SIGNAL CABINET VIA THE EXISTING 2" RIGID GALVANIZED STEEL RISER AND CONDUIT. SEAL THE EXISTING RISER WITH HEAT SHRINK TUBING RETROFIT KIT.
2. BETWEEN THE POINT OF EXITING THE RISER AND THE ANTENNA, SECURE THE COAXIAL CABLE TO THE STRUCTURE USING 3/4" STAINLESS STEEL STRAPS EVERY 12".
3. MAINTAIN PROPER CLEARANCE FROM ALL UTILITIES PER THE NATIONAL ELECTRICAL SAFETY CODE.
4. SEE 2018 NCDOT ROADWAY STANDARD DRAWINGS 1736.01 FOR WIRELESS RADIO ANTENNA TYPICAL DETAILS.
5. RETURN EXISTING WIRELESS RADIO EQUIPMENT AND TRANSCEIVERS TO THE NCDOT DIVISION 7 SIGNAL SHOP. THE DIVISION 7 OFFICE IS LOCATED AT 1584 YANCEYVILLE STREET, GREENSBORO, NC 27415 AND CAN BE REACHED AT 336-487-0175.
6. SIX (6) WEEKS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM, CONTACT THE NCDOT DIVISION 7 DEPUTY TRAFFIC ENGINEER MARK ALDRIDGE AT 336-487-0175 TO REQUEST THE DIVISION'S ASSISTANCE IN PROGRAMMING THE NEW ETHERNET EDGE SWITCHES WITH THE NECESSARY NETWORK CONFIGURATION DATA, INCLUDING BUT NOT LIMITED TO: THE PROJECT IP ADDRESS, DEFAULT GATEWAY, SUBNET MASK AND VLAN ID INFORMATION. NOTIFY THE DEPUTY TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

MATCHLINE - SHEET SCP 3 & SCP 8

MATCHLINE - SHEET SCP 6

PREPARED IN THE OFFICE OF:  
**Accelerate Engineering, PLLC**  
 875 Walnut Street, Suite 316  
 Cary, NC 27511  
 Tel: 919.263.5678 Fax: 919.263.5687  
 NC License No. P-1442

TMP 1 and Final Communications Plan SR 1007 (Mebane Oaks Rd) CLS Cable Routing Plan		DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED  SEAL NORTH CAROLINA PROFESSIONAL ENGINEER ZHAOLONG TENG 032179
Division 7 Alamance County Mebane PLAN DATE: November 2019 PREPARED BY: Z. "Gavin" Teng	REVIEWED BY: Z. "Gavin" Teng REVISIONS INIT. DATE	
750 N. Greenfield Pkwy, Garner, NC 27529  		SEAL NORTH CAROLINA PROFESSIONAL ENGINEER ZHAOLONG TENG 032179 DATE: 12/17/2019 CADD Filename:

\$\$\$\$\$\$SYTIME\$\$\$\$\$\$  
 \$\$\$\$\$\$DATE\$\$\$\$\$\$  
 \$\$\$\$\$\$DRAWING\$\$\$\$\$\$  
 \$\$\$\$\$\$FILENAME\$\$\$\$\$\$