



| PAVEMENT SCHEDULE | |
|-------------------|---|
| C | PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ YD. |
| C1 | PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 165 LBS PER SQ YD. |
| D | PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 456 LBS. PER SY. YD. |
| M | MILL ASPHALT PAVEMENT, 1½" DEPTH ENTIRE WIDTH |
| M2 | MILL ASPHALT PAVEMENT, 4" DEPTH ENTIRE WIDTH |
| S | SHOULDER RECONSTRUCTION (SEE DETAIL) |
| U | EXISTING PAVEMENT |