

PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.14.01.10561	4	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1245000000-E	1297000000-E		1308000000-E	1330000000-E	1503000000-E	1523000000-E	1575000000-E	1577000000-E	1662000000-E	1704000000-E	2830000000-N	
												SHOULDER RECONSTRUCTION	1 1/2" MILLING	2 1/2" MILLING	0" TO 1 1/2" MILLING	INCIDENTAL MILLING	INTERMEDIATE COURSE, I19.0C	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED	PATCHING EXISTING PAVEMENT	ADJUSTMENT OF MANHOLES	
											MI	FT	SMI	SY	SY	SY	SY	TONS	TONS	TONS	TONS	TON	TONS	EA
2022CPT.14.01.10561	Macon	1	US 23/441-SOUTH	FROM .02 MILES NORTH OF SR-1648 TO GEORGIA LINE	1	5	MU	YES	NO	8.63	75	12.00	121,510	121,510	31,600	600	17,725	43,300	3,449	889	14,575	2,000	7.00	
TOTAL FOR MAP NO. 1											8.63		12.00	121,510	121,510	31,600	600	17,725	43,300	3,449	889	14,575	2,000	7.00
TOTAL FOR PROJ NO. 2022CPT.14.01.10561											8.63		12.00	121,510	121,510	31,600	600	17,725	43,300	3,449	889	14,575	2,000	7.00
GRAND TOTAL											8.63		12.00	121,510	121,510	31,600	600	17,725	43,300	3,449	889	14,575	2,000	7.00

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E	4457000000-N	4685000000-E		4700000000-E	4725000000-E			4810000000-E		4891000000-E	4895000000-N			
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	12" X 90 M YELLOW THERMO	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	THERMO MERGE ARROW 90 M	4" YELLOW PAINT	4" WHITE PAINT	24" X 90 M WHITE THERMO	NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKERS			
										MI	FT	SF	LS	LF	LF	LF	EA	EA	EA	LF	LF	LF	EA	
2022CPT.14.01.10561	Macon	1	US 23/441-SOUTH	FROM .02 MILES NORTH OF SR-1648 TO GEORGIA LINE	1	5	MU	8.63	75	968	1	115,390	113,890	100	276	6	3	227,780	230,780	640	2,300			
TOTAL FOR MAP NO. 1											8.63		968	1	115,390	113,890	100	276	6	3	227,780	230,780	640	2,300
TOTAL FOR PROJ NO. 2022CPT.14.01.10561											8.63		968	1	115,390	113,890	100	276	6	3	227,780	230,780	640	2,300
GRAND TOTAL											8.63		968	1	115,390	113,890	100	276	6	3	227,780	230,780	640	2,300