STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
BR-0042	X-1A

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing asphalt pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
11+54.68	0	0	0
12+00.00	4	0	15
12+50.00	6	0	56
13+00.00	11	0	75
13+50.00	31	0	83
14+00.00	25	0	78
14+50.00	2	0	108
15+00.00	0	0	172
15+50.00	0	0	227
16+00.00	0	0	341
16+50.00	0	0	500
17+00.00	0	0	688
17+50.00	0	0	873
18+00.00	0	0	1065
18+50.00	31	0	1256
18+52.99	4	0	80

Station L	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
20+60.99	0	0	0
21+00.00	0	0	2013
21+50.00	10	0	2297
22+00.00	16	0	1722
22+50.00	13	0	1121
23+00.00	18	0	584
23+50.00	26	0	291
24+00.00	222	74	113
24+50.00	360	152	0
25+00.00	309	148	3
25+50.00	267	125	11
26+00.00	192	55	19
26+50.00	140	0	19
27+00.00	99	0	17
27+50.00	66	0	14
28+00.00	48	0	18
28+50.00	43	0	36
29+00.00	23	0	44
29+40.98	5	0	16

Station Y	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0	0
10+50.00	273	0	4
11+00.00	412	0	3
11+50.00	569	0	5
12+00.00	429	0	103
12+50.00	146	0	110
13+00.00	166	0	31
13+50.00	151	0	39
14+00.00	166	0	31
14+50.00	742	0	23
15+00.00	1674	0	18
15+50.00	1998	0	8
16+00.00	1827	0	4
16+50.00	1712	0	8
17+00.00	1540	0	11
17+50.00	1033	0	6
18+00.00	405	0	3

Station Y1	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
11+70.00	0	0	0
12+00.00	2	0	2
12+50.00	1	0	47
12+80.97	0	0	54

Station Y2	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
10+12.08	0	0	0
10+50.00	42	0	87
11+00.00	46	0	91
11+45.00	19	0	30

Station Y3	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
10+18.54	0	0	0
10+50.00	0	0	156
11+00.00	4	0	311
11+50.00	45	0	276
12+00.00	43	0	120
12+50.00	6	0	37
12+55.00	1	0	1

Station Y4	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
11+50.00	0	0	0
12+00.00	4	0	25
12+50.00	0	0	68
13+00.00	6	0	108
13+50.00	19	0	229
14+00.00	14	0	601
14+08.71	0	0	151